

SHELF AT NIGHT DROP ELEVATION | 3/4" = 1'-0" | 12



PHONE ROOM COUNTERTOP | 1 1/2" = 1'-0" | 11



PHONE ROOM ELEVATION | 3/4" = 1'-0" | 10



LOCKER ELEVATION | 1" = 1'-0" | 9



CHECK DESK - SECTION | 1" = 1'-0" | 8



CHECK DESK - SECTION | 1" = 1'-0" | 7



CHECK DESK - SECTION | 1" = 1'-0" | 6



CHECK DESK | NTS | 5



CHECK DESK - ELEVATION | 1" = 1'-0" | 4



CHECK DESK - ELEVATION | 1" = 1'-0" | 3



CHECK DESK - ELEVATION | 1" = 1'-0" | 2



CHECK DESK - ENLARGED PLAN | 1" = 1'-0" | 1

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

STATE OF GEORGIA
STUART M. ROMM
07/02/26
CERTIFICATE NO. 34651
REGISTERED ARCHITECT

Copyright (c) 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26302
Project Name:
WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Key Plan:

Sheet Title:
CHECK DESK - ENLARGED PLAN & DETAILS

Sheet Number:
A-708

7/8/2026 2:39:10 PM



MILLWORK SECTION @ SINK | 1 1/2" = 1'-0" | 7



MILLWORK SECT. @ DISHWASHER | 1 1/2" = 1'-0" | 6



MILLWORK SECTION @ DRAWERS | 1 1/2" = 1'-0" | 5



MILLWORK SECTION @ TRASH | 1 1/2" = 1'-0" | 4



EMPLOYEE LOUNGE 3D VIEW | NTS | 3



EMPLOYEE LOUNGE ELEVATION | 3/4" = 1'-0" | 2



EMPLOYEE LOUNGE PLAN | 3/4" = 1'-0" | 1

PL2 COUNTERTOP FINISH O/ 1"THK. PLYWOOD	17.4 SQ FT
WT1 WALL TILE	8.2 SQ FT
WT2 WALL TILE	1.6 SQ FT
WT9 WALL TILE	1.3 SQ FT
7	2.7 FT
(2) 1x4 BLOCKING	15.7 FT
(3) 2x4 BLOCKING	8.7 FT

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

STATE OF GEORGIA
STUART M. ROMM
07/02/26
CERTIFICATE NO. 34625
REGISTERED ARCHITECT

Copyright (c) 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26302
Project Name:
WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Key Plan:

Sheet Title:
EMPLOYEE LOUNGE - ENLARGED PLAN & DETAILS

Sheet Number:
A-705

: INDICATES TO SLOPE SLAB. SEE ARCHITECTURAL FOR AMOUNT OF SLOPE AND EXACT LOCATION.

[0'-0"] INDICATES ELEVATION OF FINISH FLOOR SLAB. SEE CIVIL DRAWINGS FOR DATUM.

[ ]: NUMBER INSIDE OF BRACKETS INDICATES TOP OF FOOTING ELEVATION

INDICATES A STEP IN FOOTING. SEE GENERAL NOTES FOR CRITERIA. SEE DETAIL 5 / S-680

S.C.J. : INDICATES A SAW-CUT JOINT IN THE SLAB ON GRADE. SEE TYPICAL SAW-CUT JOINT DETAIL 3 / S-680

C.J. : INDICATES A CONSTRUCTION JOINT. USE 24 GAUGE KEYED TYPE. DISCONTINUE MESH AT JOINT. SEE TYPICAL CONTROL JOINT DETAIL AND SPECIFICATIONS. SEE DETAIL 2 / S-680

R.B.: INDICATES TO PROVIDE 2#4 X 3'-0" LONG. CENTER AT INTERSECTION OF DUMMY JOINT WHERE JOINT IS NOT CONTINUOUS NOR ALIGNED. PLACE 1 BAR 1" CLEAR TOP, AND A SECOND BAR 3" CLEAR TOP OF SLAB.

NOTE: ALL ELEVATIONS SHOWN ARE TOP OF FOOTING ELEVATION.

NOTE: SEE TYPICAL DETAIL AT BASE OF STEEL COLUMNS. WHERE CONCRETE PIERS ARE NOT SPECIFICALLY DETAILED, PROVIDE A PIER AS NOTED ON DETAIL.

FOUNDATION PLAN NOTES

NOTE: UNLESS NOTED OTHERWISE ON PLANS, TOP OF FOOTINGS AT ALL INTERIOR FOOTINGS SHALL BE [-2'-0"] BELOW FINISH FLOOR SLAB.

NOTE: MAXIMUM SPACING OF VERTICAL CONTROL JOINTS IN EXTERIOR MASONRY VENEER IS 16'-0" FROM CORNERS AND 32'-0" FOR INTERMEDIATE VERTICAL JOINTS. SEE ARCHITECT FOR EXACT LOCATIONS.

NOTE: FOR ISOLATION JOINT AT COLUMN BASES, SEE TYPICAL DETAIL: 8 / S-680

NOTE: MAXIMUM EARTH DIFFERENTIAL WHEN BACKFILLING SHOULD NOT EXCEED 2'-0"

NOTE: SLABS-ON-GRADE REQUIRE CONTROL JOINTS PER THE TYPICAL DETAILS UNLESS NOTED OTHERWISE. LOCATE CONSTRUCTION AND CONTROL JOINTS IN SUCH A WAY TO MINIMIZE THE EFFECTS OF SHRINKAGE AND CURLING OF THE CONCRETE SLAB SECTIONS. SUBMIT TO THE ARCHITECT/ENGINEER/EQUIPMENT VENDOR THE SEQUENCE AND METHOD OF CASTING CONCRETE SLABS-ON-GRADE PRIOR TO PLACING THESE ELEMENTS. JOINT SPACING SHALL NOT EXCEED **12'-6"**, AND THE RESULTING PLAN ASPECT RATIO (PANEL LENGTH TO PANEL WIDTH) OF ANY GIVEN SECTION OF SLAB SHALL NOT EXCEED **1.5**. WHERE POSSIBLE, CONTROL JOINT LAYOUT SHALL BE SUCH THAT JOINTS ALIGN WITH THE VERTICES OF COLUMN ISOLATION BLOCKOUTS AND SHALL BE ARRANGED IN A GENERALLY ORTHOGONAL MANNER.

NOTE: GENERAL CONTRACTOR SHALL ENGAGE A SURVEYOR TO PROVIDE LOCATIONS OF ALL EXISTING UTILITES, TRENCHES, ETC. TO ENSURE THAT NEW FOUNDATIONS WILL NOT INTERFERE, UNDERMINE, OR BEAR ON EXISTING UTILITIES.

NOTE: CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF ALL FLOOR JOINTS AND DUMMY JOINTS WITH THE ARCHITECTURAL JOINTS IN FINISHES. ALL FLOOR JOINTS SHOULD COINCIDE DIRECTLY UNDER A JOINT IN THE ARCHITECTURAL FINISH ABOVE. SEE ARCHITECTURAL DRAWINGS.



FOOTING KEY

NOTE: UNLESS NOTED OTHERWISE ON PLANS, TOP OF FOOTINGS AT ALL EXTERIOR FOOTINGS SHALL BE [-2'-0"] BELOW FINISH FLOOR SLAB.

STEEL COLUMN SCHEDULE

High Roof											High Roof
16' - 0" Low Roof											16' - 0" Low Roof
13' - 0"											13' - 0"
Level 1	HSS7X7X1/2	HSS6X6X3/8	HSS5X5X3/8	HSS6X6X3/8	HSS6X6X3/8	HSS6X6X1/2	HSS7X7X1/2	HSS8X6X3/8	HSS5X5X3/8	HSS6X6X1/4	Level 1
0' - 0"											0' - 0"
Column Locations	A-1, A.5-1, B-1, C-2	A-2.6, A-4, A.5-6	A-2.9	A-6, B-2	B-4	B-6	C-3	C-6, D-6, E-3	C-7	D-5	

Gridline Type Legend

NEW GRIDLINE

SLAB AND DECK SCHEDULE

MARK	DESCRIPTION
RD-1.5	DECK: 1-1/2" WIDE RIB TYPE B GAUGE: 22 (t = 0.0295") FINISH: GALVANIZED (G90) GRADE: 50 ksi FASTENER TYPE AT SUPPORT: 5/8" Ø PUDDLE WELDS WITH WELDING WASHERS END SUPPORT ATTACHMENT PATTERN: 36/4 INTERMEDIATE SUPPORT ATTACHMENT PATTERN: 36/4 PERIMETER SUPPORT ATTACHMENT PATTERN: 12" o.c. MAX. SIDE LAP FASTENER: #10 TEK SCREWS @ 18" o.c. MAX. MINIMUM END LAP = 4" (AT SUPPORTS ONLY)
SOG-4	4" CONCRETE SLAB ON A VAPOR RETARDER ON A GRAVEL BED OR SAND CUSHION AS RECOMMENDED BY THE GEOTECHNICAL REPORT. REINFORCE SLAB WITH WELDED WIRE FABRIC 6/6-W2.9xW2.9 IN FLAT SHEETS. FINISH FLOOR SLAB ELEVATION SEE CIVIL FOR DATUM

ANCHOR BOLT SCHEDULE (F1554 GRADE 36)

ANCHOR BOLT DIAMETER	ANCHOR BOLT PROJECTION ABOVE TOP OF FOUNDATION	GROUT THICKNESS	MIN. WASHER WIDTH	MIN. WASHER THICKNESS	COUNT
3/4"	8"	2"	2"	1/4"	56
1"	8"	2"	3"	3/8"	24

BASE PLATE SCHEDULE (36 KSI)

MARK	PLATE WIDTH	PLATE LENGTH	PLATE THICKNESS	ANCHOR BOLT DIAMETER	ANCHOR BOLT EMBEDMENT	COUNT
BP12	12"	12"	3/4"	HEADED ANCHOR BOLT : 3/4" Ø	8"	10
BP14	14"	14"	1"	HEADED ANCHOR BOLT : 3/4" Ø	8"	4
BP1518	15"	18"	3/4"	HEADED ANCHOR BOLT : 1" Ø	8"	4



BP1518



BP14

NOTE: WELD ALL WASHERS TO BASE PLATES AT ALL BRACE FRAME AND MOMENT FRAME COLUMN LOCATIONS.



BP16



BP12



NOTE: SQUARE OR CIRCULAR WASHERS ARE ACCEPTABLE.

HEADED ANCHOR BOLT & WASHER

WALL FOOTING SCHEDULE

MARK	WIDTH	THICKNESS	BOTTOM REINFORCEMENT	TOP REINFORCEMENT
WF20	2' - 0"	1' - 0"	2 #6	

SPREAD FOOTING SCHEDULE

MARK	LENGTH	WIDTH	THICKNESS	BOTTOM REINFORCEMENT	TOP REINFORCEMENT	COUNT
F30	3' - 0"	3' - 0"	1' - 0"	4 #4 EA. WAY		3
F38	3' - 8"	3' - 8"	1' - 0"	5 #4 EA. WAY		3
F50	5' - 0"	5' - 0"	1' - 2"	5 #5 EA. WAY		6
F60	6' - 0"	6' - 0"	1' - 4"	7 #5 EA. WAY		1
F70	7' - 0"	7' - 0"	1' - 4"	7 #6 EA. WAY		1
F10050	10' - 0"	7' - 0"	1' - 4"	7 #6 SW, 5 #6 LW	7 #6 SW, 5 #6 LW	1
F7040	7' - 0"	4' - 0"	1' - 4"	9 #6 SW, 5 #6 LW	9 #6 SW, 5 #6 LW	1



1 S-201 Foundation Plan

1/4" = 1'-0"

- F50 — 6.0 EA
- F38 — 3.0 EA
- F10050 — 1.0 EA
- F70 — 1.0 EA
- F30 — 3.0 EA
- F60 — 1.0 EA
- F7040 — 1.0 EA
- SAW-CUT JOINT - 3/S680 — 364.1 FT
- WF20 — 124.2 FT
- BP12 — 9.0 EA
- BP1518 — 4.0 EA
- BP14 — 4.0 EA
- ISOLATION JOINT - 8/S680 — 39.2 FT
- 10"THK. CONCRETE STEM WALL W/ #4 BARS @ 10" O.C @ 2'H — 8.4 FT
- 8"THK. CONCRETE STEM WALL W/ #4 BARS @ 10" O.C & #4 DOWEL BAR @ 18" O.C @ 2'H — 193.8 FT
- 4"THK. CONCRETE SLAB ON GRADE W/ 6x6 W2.9xW2.9 WIRE MESH O/ VAPOR BARRIER O/ GRAVEL BED — 1917.6 SQ FT
- New Count — 2.0 EA

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers
2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (hereinafter referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Structural Plan - Foundation

Sheet Number:

S-201

RELEASED FOR CONSTRUCTION AND PERMIT

ROOF FRAMING PLAN NOTES

##k BEAM SIZE ##k

ASD REACTION IN KIPS

FRAMING KEY

— · — · — : INDICATES CONTINUOUS HORIZONTAL RIGID BRACING AT TOP AND BOTTOM CHORD OF JOIST. ADD "X" TYPE BRIDGING IN FIRST PANEL AND AT EVERY SIXTH PANEL. WELD TO JOIST, FRAMING, AND AT CROSSOVER POINTS. SEE SPECIFICATIONS.

: INDICATES THE DIRECTION THE DECK IS SPANNING.

±FORCE (KIPS) INDICATES COLLECTOR ELEMENT FORCE IN JOIST OR BEAM.

#.#k INDICATES LOAD ON JOIST FROM HOSE REEL, FOR SUPPORT DETAILS SEE: 9 / zS686

INDICATES A MOMENT CONNECTION AT EACH END OF BEAM TO COLUMN. SEE TYPICAL DETAIL FOR FULL PENETRATION WELD OF FLANGES AT EACH END. SEE DETAIL 3 / S-682

H.B. : INDICATES ANGLE 3"x3"x1/4" HORIZONTAL BRACE EXTENDING FROM TOP CHORD OF JOIST OR BEAM TO FACE OF COLUMN. WELD ALL AROUND EACH END WITH A 3/16" FILLET WELD.

A.X. : INDICATES ADDITIONAL "X" TYPE BRIDGING. USE 2"x2"x1/4" ANGLE

S.J. : INDICATES A STRUT JOIST, SEE SPECIFICATIONS.

S.P. : INDICATES A BEAM SPLICE POINT, SEE TYPICAL SPLICE POINT DETAIL9 / S-681

NOTE: WHERE STEEL FRAMING IS USED FOR LATERAL RESISTANCE, SEE STEEL FRAMING ELEVATIONS. FOR WORK POINT AND CONNECTION DETAILS AT BRACING AND KNEE BRACING, SEE DETAILS 1 / S-301 AND 3 / S-301

NOTE: AFTER ALL ROOF DEAD LOAD HAS BEEN INSTALLED, PROVIDE ANGLE BRACES, OR TENSION RODS AS NOTED IN "TYPICAL BAR JOIST ROOF CONSTRUCTION" SEE DETAIL 4 / S-682

NOTE: WHERE CONDENSING UNITS BEAR ON ROOF STRUCTURE, PROVIDE A SUPPORT FRAME SIMILAR TO A ROOF OPENING SUPPORT AT THE PERIMETER OF THE UNIT. PROVIDE ANGLES AS SHOWN IN DETAIL 10 / S-681

NOTE : WHERE TUBE FRAME MEMBERS CONNECT TO COLUMNS, PROVIDE A WELDED CONNECTION ALL AROUND FROM TUBE TO COLUMN, TYP.

NOTE: STEEL REINF. TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-706 AND THAT WELDING SHALL BE IN ACCORDANCE WITH AWS D1.4, STRUCTURAL WELDING CODE - REINFORCING STEEL BY AMERICAN WELDING SOCIETY FOR COMPLIANCE WITH ACI 318.

NOTE: FOR FRAMING AROUND ROOF HATCH, PROVIDE CHANNEL FRAMING AS SHOWN ON THE TYPICAL DETAIL FOR FRAMING AROUND MECHANICAL UNITS. (UNLESS NOTED OTHERWISE)

NOTE: KEEP STRUCTURE GUYED AND BRACED UNTIL ALL MASONRY/CONCRETE SHEAR WALLS, DIAGONAL BRACES, MOMENT FRAMES, FRAMED FLOORS AND ROOF DECKS ARE IN PLACE.

NOTE: SEE ARCHITECT AND PLUMBING DRAWINGS FOR LOCATIONS OF ROOF DRAINS. ROOF IS DESIGNED FOR A MAXIMUM DEPTH OF 4" OF WATER AT ANY LOCATION OF THE ROOF. WATER SHALL BE RELIEVED BY EITHER SCUPPERS OR AN INDEPENDENT EMERGENCY OVERFLOW DRAIN AT THE 4" LEVEL.

NOTE: FOR FRAMING AROUND THE PERIMETER OF A MECHANICAL UNIT, SEE TYPICAL DETAIL: 3 / S-681

NOTE: FOR FRAMING AROUND ROOF OPENINGS INCLUDING EXHAUST FANS, ROOF DRAINS AND ANY PENETRATIONS LARGER THAN 12", SEE TYPICAL DETAIL: 10 / S-681

NOTE: CONTRACTOR COORDINATE LOCATION OF OPENINGS AND WEIGHTS OF MECHANICAL UNITS, WITH THE MECHANICAL DRAWINGS. IF WEIGHTS EXCEED WHAT IS SHOWN ON THE STRUCTURAL PLAN, THEN NOTIFY THE STRUCTURAL ENGINEER OF THE CHANGE PRIOR TO ANY DETAILING OR FABRICATION OF JOIST, DECK OR STEEL.

NOTE: AT PERIMETER OF ALL ROOFS, EXPANSION JOINTS, AND TRANSITIONS FROM HIGH TO LOW ROOFS, PROVIDE ROOF CLOSURE ANGLES AS PER SECTIONS DETAILED. WHERE NOT SHOWN, PROVIDE A 4" x 3" x 1/4" CONT. ANGLE LONG LEG VERTICAL. WHERE ANGLE BEARS ON JOIST SEATS, FIELD WELD TO EACH JOIST WITH A 3/16" FILLET WELD. WHERE ANGLE BEARS ON A ROOF BEAM, FIELD WELD WITH A 3/16" FILLET WELD 2" at 12" o.c. MAX.

NOTE: FOR SUPPORT OF ROOF PIPING PERPENDICULAR TO JOIST, AND PARALLEL TO JOIST, SEE DETAIL - / ---

SLAB AND DECK SCHEDULE

MARK	DESCRIPTION
RD-1.5	DECK: 1-1/2" WIDE RIB TYPE B GAUGE: 22 (t = 0.0295") FINISH: GALVANIZED (G90) GRADE: 50 ksi FASTENER TYPE AT SUPPORT: 5/8" Ø PUDDLE WELDS WITH WELDING W... END SUPPORT ATTACHMENT PATTERN: 36/4 INTERMEDIATE SUPPORT ATTACHMENT PATTERN: 36/4 PERIMETER SUPPORT ATTACHMENT PATTERN: 12" o.c. MAX. SIDE LAP FASTENER: #10 TEK SCREWS @ 18" o.c. MAX. MINIMUM END LAP = 4" (AT SUPPORTS ONLY)
SOG-4	4" CONCRETE SLAB ON A VAPOR RETARDER ON A GRAVEL BED OR SAND CUSHION AS RECOMMENDED BY THE GEOTECHNICAL REPORT. REINFORC... SLAB WITH WELDED WIRE FABRIC 6/6-W2.9xW2.9 IN FLAT SHEETS. FINISH F... SLAB ELEVATION SEE CIVIL FOR DATUM

12KCS2 ROOF JOIST	54.0 FT
16KCS3 ROOF JOIST	248.6 FT
18KCS2 ROOF JOIST	108.5 FT
HSS4x4x1/4 BEAM	40.2 FT
HSS5x5x1/4 BEAM	21.5 FT
HSS6x4x3/8 BEAM	22.2 FT
HSS6x4x3/8 BEAM	9.0 FT
HSS6x6x3/8 BEAM	3.1 FT
HSS8x2x1/4 BEAM	76.7 FT
HSS8x3x1/4 BEAM	36.9 FT
HSS8x6x1/4 BEAM	33.6 FT
HSS10x6x1/4 BEAM	65.2 FT
W8x10 BEAM	13.5 FT
W10x12 BEAM	51.5 FT
W10x22 BEAM	11.9 FT
W12x14 BEAM	74.7 FT
W12x22 BEAM	15.0 FT
W14x26 BEAM	19.5 FT
W14x30 BEAM	20.1 FT
W16x26 BEAM	20.1 FT
HSS6x2x1/4 BEAM	3.0 FT
L3x3x3/16 ANGLE	99.4 FT
L4x3x1/4 LLV ANGLE	179.9 FT
C7x9.8 CHANNEL	236.7 FT
L2x2x3/16 ANGLE @ 4'L	18.0 EA
6" METAL STUD CANOPY FRAMING @ 16" O.C	416.9 SQ FT
L2x2x3/16 ANGLE @ 5'8"L	1.0 EA
L3x3x1/4 HORIZONTAL BRACING	19.1 FT
HSS4x4x1/4 POST @ 1'4"H	6.0 EA
1-1/2" WIDE RIB TYPE B 22GA. GALVANIZED (G90) ROOF DECK	2208.4 SQ FT
RIGID JOIST BRACING *2	121.9 FT
L2-1/2x2-1/2x1/4 X-TYPE BRIDGING *2	35.5 FT
C5x6.7 CHANNEL	53.4 FT

1 S-203 Roof Framing Plan

1/4" = 1'-0"

Gridline Type Legend

NEW GRIDLINE

PRAXIS3

100 Peachtree St NW Suite 1450 Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers

2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Structural Plan - Roof

Sheet Number:

S-203

RELEASED FOR CONSTRUCTION AND PERMIT

ROOF FRAMING PLAN NOTES

##k BEAM SIZE ##k

ASD REACTION IN KIPS

FRAMING KEY

: INDICATES CONTINUOUS HORIZONTAL RIGID BRACING AT TOP AND BOTTOM CHORD OF JOIST. ADD "X" TYPE BRIDGING IN FIRST PANEL AND AT EVERY SIXTH PANEL. WELD TO JOIST, FRAMING, AND AT CROSSOVER POINTS. SEE SPECIFICATIONS.

: INDICATES THE DIRECTION THE DECK IS SPANNING.

±FORCE (KIPS) INDICATES COLLECTOR ELEMENT FORCE IN JOIST OR BEAM.

#.#k INDICATES LOAD ON JOIST FROM HOSE REEL, FOR SUPPORT DETAILS SEE: 9 / zS686

INDICATES A MOMENT CONNECTION AT EACH END OF BEAM TO COLUMN. SEE TYPICAL DETAIL FOR FULL PENETRATION WELD OF FLANGES AT EACH END. SEE DETAIL 3 / S-682

H.B. : INDICATES ANGLE 3"x3"x1/4" HORIZONTAL BRACE EXTENDING FROM TOP CHORD OF JOIST OR BEAM TO FACE OF COLUMN. WELD ALL AROUND EACH END WITH A 3/16" FILLET WELD.

A.X. : INDICATES ADDITIONAL "X" TYPE BRIDGING. USE 2"x2"x1/4" ANGLE

S.J. : INDICATES A STRUT JOIST, SEE SPECIFICATIONS.

S.P. : INDICATES A BEAM SPLICE POINT, SEE TYPICAL SPLICE POINT DETAIL9 / S-681

NOTE: WHERE STEEL FRAMING IS USED FOR LATERAL RESISTANCE, SEE STEEL FRAMING ELEVATIONS. FOR WORK POINT AND CONNECTION DETAILS AT BRACING AND KNEE BRACING, SEE DETAILS 1 / S-301 AND 3 / S-301

NOTE: AFTER ALL ROOF DEAD LOAD HAS BEEN INSTALLED, PROVIDE ANGLE BRACES, OR TENSION RODS AS NOTED IN "TYPICAL BAR JOIST ROOF CONSTRUCTION" SEE DETAIL 4 / S-682

NOTE: WHERE CONDENSING UNITS BEAR ON ROOF STRUCTURE, PROVIDE A SUPPORT FRAME SIMILAR TO A ROOF OPENING SUPPORT AT THE PERIMETER OF THE UNIT. PROVIDE ANGLES AS SHOWN IN DETAIL 10 / S-681

NOTE : WHERE TUBE FRAME MEMBERS CONNECT TO COLUMNS, PROVIDE A WELDED CONNECTION ALL AROUND FROM TUBE TO COLUMN, TYP.

NOTE: STEEL REINF. TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-706 AND THAT WELDING SHALL BE IN ACCORDANCE WITH AWS D1.4, STRUCTURAL WELDING CODE - REINFORCING STEEL BY AMERICAN WELDING SOCIETY FOR COMPLIANCE WITH ACI 318.

NOTE: FOR FRAMING AROUND ROOF HATCH, PROVIDE CHANNEL FRAMING AS SHOWN ON THE TYPICAL DETAIL FOR FRAMING AROUND MECHANICAL UNITS. (UNLESS NOTED OTHERWISE)

NOTE: KEEP STRUCTURE GUYED AND BRACED UNTIL ALL MASONRY/CONCRETE SHEAR WALLS, DIAGONAL BRACES, MOMENT FRAMES, FRAMED FLOORS AND ROOF DECKS ARE IN PLACE.

NOTE: SEE ARCHITECT AND PLUMBING DRAWINGS FOR LOCATIONS OF ROOF DRAINS. ROOF IS DESIGNED FOR A MAXIMUM DEPTH OF 4" OF WATER AT ANY LOCATION OF THE ROOF. WATER SHALL BE RELIEVED BY EITHER SCUPPERS OR AN INDEPENDENT EMERGENCY OVERFLOW DRAIN AT THE 4" LEVEL.

NOTE: FOR FRAMING AROUND THE PERIMETER OF A MECHANICAL UNIT, SEE TYPICAL DETAIL: 3 / S-681

NOTE: FOR FRAMING AROUND ROOF OPENINGS INCLUDING EXHAUST FANS, ROOF DRAINS AND ANY PENETRATIONS LARGER THAN 12", SEE TYPICAL DETAIL: 10 / S-681

NOTE: CONTRACTOR COORDINATE LOCATION OF OPENINGS AND WEIGHTS OF MECHANICAL UNITS, WITH THE MECHANICAL DRAWINGS. IF WEIGHTS EXCEED WHAT IS SHOWN ON THE STRUCTURAL PLAN, THEN NOTIFY THE STRUCTURAL ENGINEER OF THE CHANGE PRIOR TO ANY DETAILING OR FABRICATION OF JOIST, DECK OR STEEL.

NOTE: AT PERIMETER OF ALL ROOFS, EXPANSION JOINTS, AND TRANSITIONS FROM HIGH TO LOW ROOFS, PROVIDE ROOF CLOSURE ANGLES AS PER SECTIONS DETAILED. WHERE NOT SHOWN, PROVIDE A 4" x 3" x 1/4" CONT. ANGLE LONG LEG VERTICAL. WHERE ANGLE BEARS ON JOIST SEATS, FIELD WELD TO EACH JOIST WITH A 3/16" FILLET WELD. WHERE ANGLE BEARS ON A ROOF BEAM, FIELD WELD WITH A 3/16" FILLET WELD 2" at 12" o.c. MAX.

NOTE: FOR SUPPORT OF ROOF PIPING PERPENDICULAR TO JOIST, AND PARALLEL TO JOIST, SEE DETAIL - / ---

SLAB AND DECK SCHEDULE

MARK	DESCRIPTION
RD-1.5	DECK: 1-1/2" WIDE RIB TYPE B GAUGE: 22 (t = 0.0295") FINISH: GALVANIZED (G90) GRADE: 50 ksi FASTENER TYPE AT SUPPORT: 5/8" Ø PUDDLE WELDS WITH WELDING WASHERS END SUPPORT ATTACHMENT PATTERN: 36/4 INTERMEDIATE SUPPORT ATTACHMENT PATTERN: 36/4 PERIMETER SUPPORT ATTACHMENT PATTERN: 12" o.c. MAX. SIDE LAP FASTENER: #10 TEK SCREWS @ 18" o.c. MAX. MINIMUM END LAP = 4" (AT SUPPORTS ONLY)
SOG-4	4" CONCRETE SLAB ON A VAPOR RETARDER ON A GRAVEL BED OR SAND CUSHION AS RECOMMENDED BY THE GEOTECHNICAL REPORT. REINFORCE SLAB WITH WELDED WIRE FABRIC 6/6-W2.9xW2.9 IN FLAT SHEETS. FINISH FLOOR SLAB ELEVATION SEE CIVIL FOR DATUM



2 S-203 Frame Elevation

3/16" = 1'-0"



3 S-203 Frame Elevation

3/16" = 1'-0"



1 S-203 Roof Framing Plan

1/4" = 1'-0"

HSS6x6x3/8 COLUMN	61.4 FT
C7x9.8 CHANNEL	14.0 FT
C8x11.5 CHANNEL	10.1 FT
HSS5x5x3/8 COLUMN	20.3 FT

Gridline Type Legend

NEW GRIDLINE

PRAXIS3

100 Peachtree St NW Suite 1450 Atlanta, GA 30303

404-875-4500 tel 404-876-8884 fax www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers

2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Structural Plan - Roof

Sheet Number:

S-203

RELEASED FOR CONSTRUCTION AND PERMIT

6/26/2026 12:52:19 PM





HSS COLUMN BASE WITH BRACE CONNECTION

NOTES:
1. FABRICATOR TO SUBMIT BRACE CONNECTION CALCS WITH SHOP DRAWINGS.
2 "P" - BRACE UNFACTORED (ASD) AXIAL FORCE IN KIPS, SEE ELEVATION FOR FORCES.



BRACE CONNECTION OF WIDE FLANGE BEAM TO HSS COLUMN

NOTES:
1. FABRICATOR TO SUBMIT BRACE CONNECTION CALCS WITH SHOP DRAWINGS. CONNECTIONS SHALL BE DESIGNED FOR FORCES SHOWN ON BRACE ELEVATIONS AND FRAMING PLANS.
2. FABRICATOR HAS OPTION TO USE BOLTED GUSSET CONNECTIONS, SUBMIT DETAIL FOR ACCEPTANCE PRIOR TO SUBMITTING SHOP DRAWINGS.
3. TOP OR BOTTOM BRACE MAY NOT BE PRESENT AT SIMILAR CONDITIONS.
4. "P" - BRACE UNFACTORED (ASD) AXIAL FORCE IN KIPS, SEE ELEVATION FOR FORCES.

HSS6x6x3/8 COLUMN	175.0 FT
HSS6x6x1/4 DIAGONAL BRACING	59.6 FT
C7x9.8 CHANNEL	177.8 FT
HSS6x6x1/2 COLUMN	19.7 FT
HSS4x4x1/4 DIAGONAL BRACING	28.6 FT
HSS7x7x1/2 COLUMN	97.3 FT
W10x12 BEAM	4.8 FT
C8x11.5 CHANNEL	14.5 FT
HSS4x4x1/4 COLUMN	5.6 FT
HSS5x5x3/8 COLUMN	18.9 FT



3 S-301 **Typical Knee Brace Detail**
3/4" = 1'-0"

2 S-301 **Typical Detail At Brace Connections**
1 1/2" = 1'-0"







4 S-301 **Framing Elevation**
3/16" = 1'-0"

5 S-301 **Framing Elevation**
3/16" = 1'-0"

6 S-301 **Framing Elevation**
3/16" = 1'-0"











7 S-301 **Framing Elevation**
3/16" = 1'-0"

8 S-301 **Framing Elevation**
3/16" = 1'-0"

9 S-301 **Framing Elevation**
3/16" = 1'-0"

10 S-301 **Framing Elevation**
3/16" = 1'-0"

11 S-301 **Framing Elevation**
3/16" = 1'-0"

6/26/2026 12:52:22 PM

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS
Mark Nannis Structural Engineers
2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:
FIFTH THIRD BANK

Project Number: 26302
Project Name:
WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:
Elevations - Steel Frames

Sheet Number:
S-301

RELEASED FOR CONSTRUCTION AND PERMIT



1 S-600 Section at Exterior Wall

3/4" = 1'-0"



2 S-600 Section at Exterior Wall

3/4" = 1'-0"



3 S-600 Section at Exterior Wall and Opening

3/4" = 1'-0"



4 S-600 Section at Exterior Wall and Storefront

3/4" = 1'-0"



5 S-600 Section at Exterior Wall

3/4" = 1'-0"



6 S-600 Section At Foundation And Wing Wall

3/4" = 1'-0"

6/26/2026 12:52:27 PM

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers
2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Wall Sections - Foundation

Sheet Number:

S-600

RELEASED FOR CONSTRUCTION AND PERMIT



1 S-601 Section at Roof - Joist Parallel

3/4" = 1'-0"



2 S-601 Section at Roof at Canopy

3/4" = 1'-0"



3 S-601 Section at Exterior Wall

3/4" = 1'-0"



4 S-601 Section at Canopy at Hanger

3/4" = 1'-0"



5 S-601 Section at Canopy

3/4" = 1'-0"



6 S-601 Section at Exterior Wall

3/4" = 1'-0"

6/26/2026 12:52:28 PM

RELEASED FOR CONSTRUCTION AND PERMIT

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers
2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Wall Sections

Sheet Number:

S-601



1 S-602 Section at Exterior Wall

3/4" = 1'-0"



2 S-602 Section at Exterior Wall

3/4" = 1'-0"



3 S-602 Section at Exterior Wall

3/4" = 1'-0"



4 S-602 Section at Roof and Canopy

3/4" = 1'-0"



5 S-602 Section at Exterior Wall

3/4" = 1'-0"



6 S-602 Section at Roof and Canopy

3/4" = 1'-0"

6/26/2026 12:52:28 PM

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers

2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Wall Sections

Sheet Number:

S-602

RELEASED FOR CONSTRUCTION AND PERMIT



1 S-603 Section at Canopy Outrigger at Column

3/4" = 1'-0"



2 S-603 Section At Roof And Canopy

3/4" = 1'-0"



3 S-603 Typical Detail Of Shoring At Channel

1" = 1'-0"



4 S-603 Section At Wing Wall And Roof

3/4" = 1'-0"



5 S-603 Section at Exterior Wall

3/4" = 1'-0"



6 S-603 Section At Wing Wall

3/4" = 1'-0"

6/26/2026 12:52:29 PM

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers
2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Wall Sections

Sheet Number:

S-603

RELEASED FOR CONSTRUCTION AND PERMIT