VENTILATION CALCULATIONS: RTU-1

1. Summary

Ventilation Sizing Method .... **ASHRAE Standard 62.1-2019**
Design Condition **Cooling operation**
Occupant Diversity (D) **1.000**
Uncorrected Outdoor Air Intake (Vou) **165** CFM
System Ventilation Efficiency (Ev) **0.887**
Outdoor Air Intake (Vot) **186** CFM

2. Space Ventilation Analysis

	Supply Air (CFM)	Space Floor Area (sqft)	Area Outdoor Air Rate (CFM/sqft)	Time Averaged Occupancy (Occupants)	People Outdoor Air Rate (CFM/person)	Air Distribution Effectiveness	Space Outdoor Air (CFM)	Breathing Zone Outdoor Air (CFM)	Space Ventilation Efficiency
Zone Name / Space Name	**(Vpz)**	**(Az)**	**(Ra)**	**(Pz)**	**(Rp)**	**(Ez)**	**(Voz)**	**(Vbz)**	**(Evz)**
Zone 1									
100 Weather Vestibule	458	90.1	0.06	2.0	5.00	1.00	**15**	*15*	1.070
101 Entry	168	114.6	0.06	2.0	7.50	1.00	**22**	*22*	0.973
103 Gathering Area	218	243.6	0.06	4.0	7.50	1.00	**45**	*45*	0.898
104 Booth	257	88.8	0.06	3.0	5.00	1.00	**20**	*20*	1.024
105 Meeting Room	208	119.5	0.06	3.0	5.00	1.00	**22**	*22*	0.996
112 Women's	60	67.3	0.12	1.0	5.00	1.00	**13**	*13*	0.887
113 Men's	66	67.4	0.12	1.0	5.00	1.00	**13**	*13*	0.906
114 Phone Room	61	51.2	0.06	1.0	5.00	1.00	**8**	*8*	0.972
116 Vestibule	104	108.5	0.06	2.0	0.00	1.00	**7**	*7*	1.040
Totals	**1600**							**165**	**0.887**

VENTILATION CALCULATIONS: RTU-2

1. Summary

Ventilation Sizing Method **ASHRAE Standard 62.1-2019**
Design Condition .... **Cooling operation**
Occupant Diversity (D) **1.000**
Uncorrected Outdoor Air Intake (Vou) .... **140** CFM
System Ventilation Efficiency (Ev) **0.916**
Outdoor Air Intake (Vot) .... **153** CFM

2. Space Ventilation Analysis

	Supply Air (CFM)	Space Floor Area (sqft)	Area Outdoor Air Rate (CFM/sqft)	Time Averaged Occupancy (Occupants)	People Outdoor Air Rate (CFM/person)	Air Distribution Effectiveness	Space Outdoor Air (CFM)	Breathing Zone Outdoor Air (CFM)	Space Ventilation Efficiency
Zone Name / Space Name	**(Vpz)**	**(Az)**	**(Ra)**	**(Pz)**	**(Rp)**	**(Ez)**	**(Voz)**	**(Vbz)**	**(Evz)**
Zone 2									
102 Relaxed Seated Area	742	305.5	0.06	3.0	7.50	1.00	**41**	*41*	1.033
107 Library	139	146.7	0.06	2.0	7.50	1.00	**24**	*24*	0.916
108 Transaction Bar	276	179.8	0.06	2.0	7.50	1.00	**26**	*26*	0.994
110 Employee Lounge	328	189.9	0.12	2.0	5.00	1.00	**33**	*33*	0.988
111 Work Room	114	114.9	0.06	2.0	5.00	1.00	**17**	*17*	0.939
Totals	**1600**							**140**	**0.916**

COMCHECK REPORT



COM*check* Software Version 4.1.5.5

Mechanical Compliance Certificate

Project Information

Energy Code:	2015 IECC
Project Title:	
Location:	Warner Robins, Georgia
Climate Zone:	3a
Project Type:	New Construction

Construction Site:
GA

Owner/Agent:

Designer/Contractor:

Additional Efficiency Package(s)

Credits: 1.0 Required 0.0 Proposed

Mechanical Systems List

Quantity	System Type & Description
1	RTU-1 (Single Zone): Heating: 1 each - Other, Electric, Capacity = 60 kBtu/h No minimum efficiency requirement applies Cooling: 1 each - Single Package DX Unit, Capacity = 49 kBtu/h, Air-Cooled Condenser, Air Economizer Proposed Efficiency = 17.00 SEER, Required Efficiency: 14.00 SEER Fan System: None
1	RTU-2 (Single Zone): Heating: 1 each - Other, Electric, Capacity = 60 kBtu/h No minimum efficiency requirement applies Cooling: 1 each - Single Package DX Unit, Capacity = 49 kBtu/h, Air-Cooled Condenser, Air Economizer Proposed Efficiency = 17.00 SEER, Required Efficiency: 14.00 SEER Fan System: None
1	AHU-1/CU-1 (Single Zone): Split System Heat Pump Heating Mode: Capacity = 19 kBtu/h, Proposed Efficiency = 9.20 HSPF, Required Efficiency = 8.20 HSPF Cooling Mode: Capacity = 18 kBtu/h, Proposed Efficiency = 20.20 SEER, Required Efficiency: 14.00 SEER Fan System: None
1	WH-1: Electric Storage Water Heater, Capacity: 20 gallons w/ Circulation Pump Proposed Efficiency: 1.65 SL, %/h (if > 12 kW), Required Efficiency: 1.65 SL, %/h (if > 12 kW)

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2015 IECC requirements in COM*check* Version 4.1.5.5 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Paige Faucett Paige Faucett 06/29/26
Name - Title Signature Date

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 1 of 11



COM*check* Software Version 4.1.5.5

Inspection Checklist

Energy Code: 2015 IECC

Requirements: 0.0% were addressed directly in the COM*check* software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR2]^{1}	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C103.2 [PR3]^{1}	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C406 [PR9]^{1}	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 2 of 11



Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.2.4.5, C403.2.4.6 [FO9]^{3}	Snow/ice melting system sensors for future connection to controls. Freeze protection systems have automatic controls installed.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 3 of 11



Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5, C404.5.1, C404.5.2 [PL6]^{3}	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.5, C404.5.1, C404.5.2 [PL6]^{3}	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.5, C404.5.1, C404.5.2 [PL6]^{3}	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.5, C404.5.1, C404.5.2 [PL6]^{3}	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.6.1, C404.6.2 [PL3]^{1}	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.6.3 [PL7]^{3}	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.6.3 [PL7]^{3}	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.6.3 [PL7]^{3}	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.6.3 [PL7]^{3}	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.7 [PL8]^{3}	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 4 of 11



Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.7 [PL8]^{3}	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.7 [PL8]^{3}	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.7 [PL8]^{3}	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 5 of 11



Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 [ME41]^{3}	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.12.1 [ME65]^{3}	HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.2.12.1 [ME65]^{3}	HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.2.12.1 [ME65]^{3}	HVAC fan systems at design conditions do not exceed allowable fan system motor nameplate hp or fan system bhp.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.2.12.3 [ME117]^{2}	Fans have efficiency grade (FEG) >= 67. The total efficiency of the fan at the design point of operation <= 15% of maximum total efficiency of the fan.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.12.3 [ME117]^{2}	Fans have efficiency grade (FEG) >= 67. The total efficiency of the fan at the design point of operation <= 15% of maximum total efficiency of the fan.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.12.3 [ME117]^{2}	Fans have efficiency grade (FEG) >= 67. The total efficiency of the fan at the design point of operation <= 15% of maximum total efficiency of the fan.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.13 [ME71]^{2}	Unenclosed spaces that are heated use only radiant heat.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.3 [ME55]^{2}	HVAC equipment efficiency verified.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.2.6.1 [ME59]^{1}	Demand control ventilation provided for spaces >500 ft2 and >25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.6.2 [ME115]^{3}	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.7 [ME57]^{1}	Exhaust air energy recovery on systems meeting Table C403.2.7(1) and C403.2.7(2).	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 6 of 11



Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.2.8 [ME116]^{3}	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.9 [ME60]^{2}	HVAC ducts and plenums insulated. Where ducts or plenums are installed in or under a slab, verification may need to occur during Foundation Inspection.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.9 [ME10]^{2}	Ducts and plenums sealed based on static pressure and location.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.9.1.3 [ME11]^{3}	Ductwork operating >3 in. water column requires air leakage testing.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.9.1.3 [ME11]^{3}	Ductwork operating >3 in. water column requires air leakage testing.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.9.1.3 [ME11]^{3}	Ductwork operating >3 in. water column requires air leakage testing.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.4.2.3.2.1 [ME121]^{3}	Closed-circuit cooling tower within heat pump loop have either automatic bypass valve or lower leakage positive closure dampers. Open-circuit tower within heat pump loop have automatic valve to bypass all heat pump water flow around the tower. Open- or closed-circuit cooling towers used in conjunction with a separate heat exchanger have heat loss by shutting down the circulation pump on the cooling tower loop.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.4.4.6 [ME110]^{3}	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.4.4.6 [ME110]^{3}	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C403.4.4.6 [ME110]^{3}	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	*See the Mechanical Systems list for values.*
C408.2.2.1 [ME53]^{3}	Air outlets and zone terminal devices have means for air balancing.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 7 of 11



Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.5, C403.5.1, C403.5.2 [ME123]^{3}	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2..	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 8 of 11



Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C303.3, C408.2.5.3 [FI8]^{3}	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.2 [FI27]^{3}	HVAC systems and equipment capacity does not exceed calculated loads.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1 [FI47]^{3}	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1 [FI47]^{3}	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1 [FI47]^{3}	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1.1 [FI42]^{3}	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1.2 [FI38]^{3}	Thermostatic controls have a 5 °F deadband.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.1.3 [FI20]^{3}	Temperature controls have setpoint overlap restrictions.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.2 [FI39]^{3}	Each zone equipped with setback controls using automatic time clock or programmable control system.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C403.2.4.2.1, C403.2.4.2.2 [FI40]^{3}	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.3 [FI11]^{3}	Heat traps installed on supply and discharge piping of non-circulating systems.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C404.4 [FI25]^{2}	All piping insulated in accordance with section details and Table C403.2.10.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 9 of 11



Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C404.6.1 [FI12]^{3}	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.1 [FI28]^{1}	Commissioning plan developed by registered design professional or approved agency.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.3.1 [FI31]^{1}	HVAC equipment has been tested to ensure proper operation.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.3.2 [FI10]^{1}	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.4 [FI29]^{1}	Preliminary commissioning report completed and certified by registered design professional or approved agency.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.5.1 [FI7]^{3}	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.5.3 [FI43]^{1}	An air and/or hydronic system balancing report is provided for HVAC systems.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C408.2.5.4 [FI30]^{1}	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 06/26/26
Data filename: Y:\StudioATL02\Fifth-Third Bank\2026-0980 Fifth Third - Watson\M\MECH COMCHECK.cck Page 10 of 11

6/30/2026 4:54:55 PM

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GARRY M. JENKINS
No. 032221

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:

FIFTH THIRD BANK

Project Number: 26032
Project Name:

FIFTH THIRD BANK
WATSON
1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:

MECHANICAL VENTILATION SCHEDULES

Sheet Number:

M-102