


PARTITION HEAD DETAILS



A-T03




B-T01




A-T02

PARTITION BASE DETAILS




A-B01

PARTITION SERIES - A



PARTITION TYPE	FRAMING			DETAILS		ATTEN THK	FIRE RTG	UL LISTING	STC RTG
	THK (IN)	DEPTH	SPACING	TOP	BOT				

PARTITION LEGEND



PARTITION TAG
PARTITION HEIGHT DESIGNATOR (SEE **TABLE D** BELOW)
FRAMING MEMBER DEPTH (SEE **TABLE B** OR **TABLE C** - BELOW
PARTITION SERIES (SEE **TABLE A** - BELOW)
FIRE RATING (IF APPLICABLE)

TABLE A- PARTITION SERIES CONSTRUCTION ASSEMBLY

SERIES	SHEATHING	FRAMING	SHEATHING
A	1-LAYER	MTL STUD	1-LAYER
B	1-LAYER	MTL STUD	1-LAYER
C	1-LAYER	MTL STUD	1-LAYER
D	1-LAYER	MTL STUD	NONE
E	1-LAYER (PLY.WD)	MTL STUD	NONE
F	1-LAYER	MTL STUD	NONE
G	1-LAYER	NONE	NONE
H	1-LAYER	MTL STUD	NONE
J	2-LAYERS	MTL STUD	LINER PANEL
K	1-LAYER	(2) MTL STUDS	1-LAYER
L	2-LAYERS	(2) MTL STUDS	2-LAYERS

TABLE B- FRAMING DEPTH SCHEDULE

TAG NUMBER DESIGNATION	MTL STUD DEPTH	MTL C-H STUD DEPTH	WOOD STUD DEPTH
-	NO FRAMING		
0	7/8" FURRING CHANNEL		N/A
1	1 5/8"	N/A	N/A
2	2 1/2"	2 1/2"	N/A
3	3 5/8"	N/A	N/A
4	4"	4"	3 1/2"
6	6"	6"	5 1/2"
8	8"	N/A	N/A
10	10"	N/A	N/A

TABLE C- MASONRY WIDTH SCHEDULE

TAG NUMBER DESIGNATION	CMU WIDTH
4	3 5/8"
6	5 5/8"
8	7 5/8"
10	9 5/8"
12	11 5/8"

TABLE D - PARTITION HEIGHT DESIGNATOR

TAG NUMBER DESIGNATION	PARTITION HEIGHT
A	FROM SLAB TO STRUCTURE ABOVE
B	FROM SLAB TO STRUCTURE ABOVE W/ BATT
C	FROM SLAB TO 6" ABOVE SCHEDULED CEILING
D	FROM SLAB TO 6" ABOVE SCHEDULED CEILING W/ BATT
E	FROM SLAB TO SCHEDULED CEILING
F	FROM SLAB TO SCHEDULED CEILING W/ BATT
G	PARTIAL HEIGHT REFER TO DETAILS

STEEL SHEET THICKNESS FOR STUDS AND RUNNERS


GUAGE*	MIN. STEEL BASE METAL THICKNESS (UNCOATED)		
	INCH	MILS	MM
12	0.1017	97	X
14	0.0713	68	X
16	0.0566	54	1.34
18	0.0451	43	1.09
20	0.0312	30	0.84
22	0.0270	27	0.68
25	0.0179	18	0.45

*GUAGE 16,18 USED FOR STRUCTURAL FRAMING; 20, 22, AND 25 USED FOR NON-STRUCTURAL FRAMING
*USE OF DIMPLED STEEL STUDS ACCEPTABLE PROVIDED CONTRACTOR SUPPLIES DOCUMENTATION PROVING THE EQUIVALENT MINIMUM BASE METAL THICKNESS IS ACHIEVED

GENERAL NOTES - PARTITIONS


A. REFERENCE SPECIFICATIONS FOR ALL STUD GAUGES AND LIMITING HEIGHTS
B. ALL PARTITIONS CONTAINING PLUMBING OR HAVING AN EXT. FACE SHALL BE INSULATED.
C. ALL ELEC /MECH ROOMS AND A/V EQUIPMENT / LIGHTING ROOMS, SHALL HAVE THEIR PERIMETER PARTITIONS INSULATED USING MINERAL WOOL
D. ALL OFFICES AND TOILET ROOMS SHALL HAVE THEIR PERIMETER PARTITIONS INSULATED WITH SOUND ATTENUATION BATTS AS SPECIFIED.
E. ALL RATED PARTITIONS TO EXTEND FROM TOP OF SLAB TO UNDERSIDE OF STRUCTURE. SEAL TOP AND BOTTOM, TYP.
F. ALL INT. ROOF DRAINS AND OVERFLOW DRAINS TO BE WRAPPED CONTINUOUSLY WITH SOUND ATTEN. BATT
G. 'UNDERSIDE OF STRUCTURE' INDICATED AT HEAD CONDITION DETAIL IS DIAGRAMMATIC ONLY, AND DOES NOT INDICATE EXACT CONSTRUCTION CONDITIONS.
H. INSTALL FRAMING AND GYPSUM BOARD TO OFFSET AROUND STRUCTURAL MEMBERS OR OTHER OBSTRUCTIONS TO MAINTAIN FIRE RESISTIVE RATINGS.
I. WHERE GYPSUM BOARD EXTENDS TO THE UNDERSIDE OF STRUCTURE, STOP GYPSUM BOARD 1/2" BELOW THE LINE OF STRUCTURE AND SEAL AS REQUIRED.
J. FIRE RESISTANT, RATED PARTITIONS TO BE INSTALLED WITH FIRESTOP SEALANT, U.N.O.
K. NON-RATED PARTITIONS TO BE INSTALLED WITH ACOUSTICAL SEALANT, U.N.O.
L. REFER TO MECHANICAL DRAWINGS FOR DETAILS ON PIPE PENETRATIONS THROUGH ACOUSTICAL PARTITIONS AS WELL AS RATED PARTITIONS.
M. INSTALL FIRE RETARDANT, TREATED BLOCKING IN PARTITIONS AS REQD ON DRAWINGS.
N. ALL PARTITIONS SCHEDULED TO RECEIVE TILE OR FRP, SHALL BE CONSTRUCTED OF WATER-RESISTANT CORE GYPSUM WALL BOARD.
O. PER MOLD PREVENTION GUIDELINES, DO NOT INSTALL GYP. BD IN DIRECT CONTACT WITH THE FLOOR. ALL PARTITIONS SHALL BE SHIMMED 1/2" OFF THE FLOOR WITH PLASTIC NON-POROUS SHIMS. GYP. BD WALL SHIMS ARE NOT ACCEPTABLE.

PARTITION HEAD DETAILS




A-T01

PARTITION BASE DETAILS



B-B01

PARTITION SERIES - B



PARTITION TYPE	FRAMING			DETAILS		ATTEN THK	FIRE RTG	UL LISTING	STC RTG
	THK (IN)	DEPTH	SPACING	TOP	BOT				

PARTITION HEAD DETAILS

C-T01

PARTITION BASE DETAILS

C-B01

PARTITION SERIES - C

PARTITION TYPE	FRAMING			DETAILS		ATTEN THK	FIRE RTG	UL LISTING	STC RTG
	THK (IN)	DEPTH	SPACING	TOP	BOT				

PARTITION HEAD DETAILS

D-T02

D-T01

PARTITION BASE DETAILS

D-B01

PARTITION SERIES - D

PARTITION TYPE	FRAMING			DETAILS		ATTEN THK	FIRE RTG	UL LISTING	STC RTG
	THK (IN)	DEPTH	SPACING	TOP	BOT				

PARTITION HEAD DETAILS

15 PARTITION HEAD DETAIL
3" = 1'-0"

14 PARTITION HEAD DETAIL
3" = 1'-0"

PARTITION BASE DETAILS

E-B01

PARTITION SERIES - E

PARTITION TYPE	FRAMING			DETAILS		ATTEN THK	FIRE RTG	UL LISTING	STC RTG
	THK (IN)	DEPTH	SPACING	TOP	BOT				

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

STATE OF GEORGIA
STUART M. ROMM
07/02/26
CERTIFICATE NO. 3457
REGISTERED ARCHITECT

Copyright (c) 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26302
Project Name:
WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Key Plan:

Sheet Title:
INTERIOR PARTITION SCHEDULE & DETAILS

Sheet Number:
A-620

7/8/2026 2:38:52 PM