GENERAL NOTES:

1. PRE-BID SITE VISIT: CONTRACTOR PROPOSING TO UNDERTAKE WORK UNDER THIS DIVISION SHALL VISIT THE SITE OF THE WORK AND FULLY INFORM THEMSELVES OF ALL CONDITIONS THAT EFFECT THE WORK AND COST THEREOF AND EXAMINE THE DRAWINGS AS RELATED TO THE SITE CONDITIONS. BIDDERS WHO DO NOT VISIT THE SITE MAY BE UNILATERALLY NOT PERMITTED TO SUBMIT A BID IF THE OWNER SO DESIGNATES.
2. BID TERMS AND CONDITIONS: THE ELECTRICAL CONTRACTOR SHALL OBTAIN A FULL SET OF PLANS AND SPECIFICATIONS FROM THE GENERAL CONTRACTOR PRIOR TO BID. CONSIDERATION WILL NOT BE GRANTED FOR ANY ALLEGED MISUNDERSTANDINGS OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF PROPOSAL SHALL CONVEY FULL AGREEMENT TO THE ITEMS AND CONDITIONS INDICATED IN THE PLANS AND SPECIFICATIONS. ANY DISCREPANCIES OR OMISSIONS FOUND IN THE CONTRACT DOCUMENTS OR DOUBT AS TO THE INTENT THEREOF, SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ARCHITECT IN WRITING TO OBTAIN CLARIFICATION FROM THE ENGINEER AND/OR OWNER'S REPRESENTATIVE PRIOR TO SUBMITTING PROPOSAL FOR WORK. WHERE CLARIFICATION CANNOT BE PROVIDED PRIOR TO BID, THE CONTRACTOR SHALL ASSUME THE MORE EXPENSIVE METHOD FOR THE BID. WITHOUT FORMAL AUTHORIZATION, THE ARCHITECT AND OWNER RESERVE THE RIGHT TO REQUIRE THE MORE RESTRICTIVE SPECIFICATION.
3. EXCLUSIONS: MATERIAL AND LABOR EXCLUDED BY THE ELECTRICAL CONTRACTOR SHALL NOT RELIEVE THE GENERAL CONTRACTOR FROM PROVIDING SAME.
4. COMPLETE SYSTEM: FURNISH ALL LABOR, MATERIALS, EQUIPMENT, TOOLS, TRANSPORTATION, SUPERINTENDENTS AND SERVICES REQUIRED TO CONSTRUCT, INSTALL, AND MODIFY THE ELECTRICAL SYSTEMS AS HEREIN SPECIFIED AND SHOWN ON THESE DRAWINGS FOR A COMPLETE AND FULLY OPERATIONAL SYSTEM. COORDINATE WORK TO BE PERFORMED OR INSTALLED BY OTHERS AFFECTING THE ELECTRICAL WORK AND FURNISH AND INSTALL ALL NECESSARY STEEL SHAPES, BLOCKING, ANCHORS, SLEEVES, HANGERS, ETC. FOR ATTACHING OR CONNECTING ELECTRICAL WORK TO RELATED WORK OF OTHER TRADES. ALL ITEMS NOT SPECIFICALLY MENTIONED HEREIN OR NOT INDICATED IN THE DRAWINGS, WHICH ARE NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE PROVIDED WITHOUT ADDITIONAL EXPENSE TO THE OWNER. DRAWINGS AND SPECIFICATIONS DO NOT UNDERTAKE TO INDICATE EVERY ITEM OF MATERIAL, EQUIPMENT, OR LABOR REQUIRED TO PRODUCE A COMPLETE AND PROPERLY OPERATING INSTALLATION.
5. PERMITS: OBTAIN ALL NECESSARY PERMITS, LICENSES, AND INSPECTIONS AS REQUIRED BY ANY OF THE FOREGOING AUTHORITIES AND PAY FOR ALL OTHER COSTS IN CONNECTION WITH THE WORK.
6. INSPECTIONS: CONTRACTOR SHALL NOT CONCEAL ANY WORK UNTIL INSPECTED AND APPROVED BY ELECTRICAL INSPECTOR AND/OR ARCHITECT/ENGINEER.
7. REGULATIONS: ALL ELECTRICAL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE LATEST ADOPTED NATIONAL ELECTRICAL CODE (NEC) AND ALL OTHER APPLICABLE FEDERAL, STATE, AND LOCAL BUILDING CODES, RULES, REGULATIONS AND AUTHORITIES HAVING JURISDICTION. WORKMANSHIP: ALL WORK SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER IN ACCORDANCE WITH APPLICABLE NECA STANDARDS SUBJECT TO THE APPROVAL OF THE OWNER OR OWNER'S AUTHORIZED REPRESENTATIVE. RACEWAY, FIXTURES, AND WIRING DEVICES SHALL BE PROPERLY ALIGNED, LEVELED, PLUMBED AND SUPPORTED. RACEWAY SHALL BE GROUPED AND INSTALLED IN RUNS WHICH ARE PARALLEL AND PERPENDICULAR WITH BUILDING LINES.
8. COORDINATION: PRIOR TO COMMENCEMENT OF WORK, EXAMINE ALL CONSTRUCTION DRAWINGS AND SPECIFICATIONS AND COORDINATE WITH ALL OTHER TRADES INCLUDING GENERAL CONTRACTOR, MECHANICAL CONTRACTOR, LOW VOLTAGE CONTRACTOR, AND SECURITY CONTRACTOR IN ORDER TO BECOME FAMILIAR WITH ALL ASPECTS OF THE DESIGN AFFECTING THE ELECTRICAL WORK AND TO CONFIRM SITE SPECIFIC INSTALLATION REQUIREMENTS. REFER TO ARCHITECTURAL DRAWINGS AND EQUIPMENT CUT SHEETS FOR EQUIPMENT POWER/CONTROL REQUIREMENTS, CONNECTIONS, WIRING DEVICE TYPE, MOUNTING HEIGHTS, MEANS OF ATTACHMENT, AND LOCATIONS OF ALL NEW EQUIPMENT AND ELECTRICAL DEVICES. FIELD VERIFY EXACT NAMEPLATE DATA ON ALL EQUIPMENT FURNISHED UNDER OTHER DIVISIONS AND/OR BY THE OWNER PRIOR TO THE INSTALLATION OF ELECTRICAL WORK AND MAKE ANY ADJUSTMENTS TO OUTLETS, CONDUITS, WIRE, AND/OR CIRCUIT BREAKER/FUSE RATINGS AS REQUIRED TO MATCH EQUIPMENT ACTUALLY FURNISHED.
9. EQUIPMENT AND DEVICE LOCATIONS: LOCATIONS ON THE ELECTRICAL PLANS ARE APPROXIMATE. EXACT LOCATIONS SHALL BE DETERMINED FROM ARCHITECTURAL PLANS, SECTIONS, AND ELEVATIONS. FINAL LOCATION OF EQUIPMENT AND DEVICES TO BE COORDINATED WITH ARCHITECT, OWNER, AND/OR OWNER'S REPRESENTATIVE. VERIFY STUB-UP LOCATION FOR ALL UNDER SLAB CONDUITS PRIOR TO ROUGH-IN.
10. UTILITIES: UTILITY COORDINATION INFORMATION SHOWN ON THE DRAWINGS SHALL BE CONSIDERED PRELIMINARY. COORDINATE WITH LOCAL POWER COMPANY AND TELCO (TELEPHONE/CABLE/INTERNET) PROVIDERS FOR SERVICE REQUIREMENTS AND VERIFY FINAL POINT OF CONNECTION PRIOR TO MOBILIZATION IN THE FIELD. NOTIFY UTILITIES OF COMMENCEMENT OF WORK AND MAKE ALL ARRANGEMENTS FOR TEMPORARY AND PERMANENT SERVICES. PROVIDE ALL EQUIPMENT, MATERIAL, AND LABOR TO MEET UTILITY REQUIREMENTS. INCLUDE ALL ASSOCIATED COSTS TO SET-UP AND COORDINATE TEMPORARY AND PERMANENT ELECTRIC AND TELCO SERVICES IN BID. ALL MATERIALS MUST BE APPROVED BY THE LOCAL UTILITY. IF REQUIRED, THE ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT SYSTEMS FOR UTILITY MEDIUM VOLTAGE FROM UTILITY PRIMARY TO POINT OF INTERCEPTION AT EDGE OF PROPERTY LINE.
11. TEMPORARY POWER: PROVIDE TEMPORARY SERVICE FOR LIGHTING, POWER EQUIPMENT (DRILLS, SAWS, ETC.), AND CONTRACTOR MOBILIZED WORK TRAILERS. VERIFY TEMPORARY SERVICE REQUIREMENTS WITH GENERAL CONTRACTOR. TEMPORARY LIGHTING AND POWER SHALL MEET OSHA REQUIREMENTS AND LOCAL CODE.
12. INTERRUPTION OF SERVICE: COORDINATE ALL WORK REQUIRING INTERRUPTION OF SERVICE (POWER, SECURITY, DATA, FIRE ALARM, ETC) WITH ALL AFFECTED PARTIES, INCLUDING BUT NOT LIMITED TO GENERAL CONTRACTOR, BUILDING OWNER AND/OR LANDLORD, TENANT(S), AND OWNER AND/OR OWNER'S REPRESENTATIVE AND OBTAIN WRITTEN PERMISSION FROM SAID PARTIES AT LEAST 48 HOURS PRIOR TO SHUT DOWN. PROVIDE NOTICE TO ALL OTHER TRADES OF ALL SCHEDULED INTERRUPTIONS. ALL OUTAGES OR INTERRUPTIONS SHALL BE KEPT TO MINIMUM DURATION. PROVIDE TEMPORARY SERVICE DURING OUTAGE WHEN REQUIRED BY AFFECTED PARTIES. CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE PERSONNEL FOR FIRE AND SECURITY WATCH DURING OUTAGES TO FIRE AND SECURITY SYSTEMS.
13. PRODUCTS: ALL ELECTRICAL MATERIALS SHALL BE NEW EXCEPT WHERE SPECIFICALLY NOTED AS EXISTING TO BE REUSED. MATERIAL AND METHODS OF INSTALLATION SHALL CONFORM TO THE STANDARDS OF UNDERWRITERS LABORATORIES, INC. (UL), ANSI, NFPA, ADA, AND ALL OTHER APPLICABLE LOCAL ORDINANCES. DEFECTIVE EQUIPMENT AND/OR EQUIPMENT DAMAGED DURING INSTALLATION AND/OR TESTING SHALL BE REPLACED OR REPAIRED IN A MANNER MEETING THE APPROVAL OF THE ARCHITECT AND THE ENGINEER. PROPOSED EQUIPMENT SHALL BE NRTL LISTED, LABELED, OR APPROVED.
14. SHOP DRAWINGS AND SUBMITTALS: SUBMIT MANUFACTURER'S STANDARD PRODUCT INFORMATION, PERFORMANCE SPECIFICATIONS, ELECTRICAL RATINGS, PHYSICAL DIMENSIONS, AND OTHER INFORMATION NECESSARY FOR ENGINEER TO ENSURE COMPLIANCE WITH SPECIFICATIONS. SHOP DRAWINGS SHALL BE SUBMITTED FOR APPROVAL PRIOR TO ORDERING AND INSTALLING ANY EQUIPMENT. SUBMITTALS AND SHOP DRAWINGS SHALL CLEARLY INDICATE ITEMS TO BE REVIEWED BY HIGHLIGHTING, AND ITEMS NOT TO BE REVIEWED SHALL BE CROSSED OUT. SUBMITTALS WITHOUT HIGHLIGHTING AND CROSSED OUT ITEMS SHALL NOT BE REVIEWED. ALL SUBMITTALS MUST BE RECEIVED BY THE ENGINEER WITHIN 30 DAYS OF CONTRACT AWARD TO THE GENERAL CONTRACTOR; NO EXCEPTIONS. EQUIPMENT ORDERED OR INSTALLED WITHOUT A FAVORABLY REVIEWED SUBMITTAL IS DONE AT THE CONTRACTOR'S OWN RISK.
15. VALUE ENGINEERING SUBMITTALS: VALUE ENGINEERING SUBMITTALS SHALL BE LABELED AS SUCH AND INDICATE A 'DEDUCT' OR CREDIT BACK TO THE OWNER. VE SUBMITTALS NOT CLEARLY LABELED OR NOT INCLUDING A DEDUCT SHALL BE REJECTED.
16. SUBSTITUTION AND ALTERATIONS: THERE SHALL BE NO DEVIATION FROM THE REQUIREMENTS HEREIN WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ALL COSTS INCURRED RESULTING FROM SUBSTITUTION OF EQUIPMENT AS WELL AS THE PERFORMANCE AND SPACE REQUIREMENTS OF SUCH EQUIPMENT.
    SUBSTITUTIONS AND ALTERATIONS OF OTHER DISCIPLINE'S EQUIPMENT: SUBSTITUTED AND ALTERED EQUIPMENT BY OTHER DISCIPLINES SHALL INCLUDE ALL MATERIAL AND LABOR COSTS FOR ELECTRICAL CONTRACTOR TO PROVIDE COMPLETE AND FULLY FUNCTIONAL SYSTEMS TO ACCOMMODATE THESE SUBSTITUTED AND ALTERED EQUIPMENT. THESE ADDITIONAL ELECTRICAL COSTS MUST BE ABSORBED BY THE OTHER DISCIPLINE'S CONTRACTOR IN ORDER FOR THE SUBSTITUTED OR ALTERED GEAR TO BE ACCEPTED.
17. FAULT CURRENT PROTECTION: ALL EQUIPMENT SHORT CIRCUIT CURRENT RATINGS (SCCR) AND OVERCURRENT PROTECTIVE DEVICE AMPERE INTERRUPTING CAPACITY (AIC) RATINGS SHALL BE GREATER THAN THE AVAILABLE FAULT CURRENT AT EACH RESPECTIVE PIECE OF EQUIPMENT. COORDINATE EQUIPMENT SCCR AND OVERCURRENT PROTECTIVE DEVICE AIC RATINGS WITH POWER COMPANY. OBTAIN THE AVAILABLE FAULT CURRENT AT TRANSFORMER SECONDARY FROM THE POWER COMPANY AND PROVIDE PROPOSED EQUIPMENT SCCR AND OVERCURRENT PROTECTIVE DEVICE AIC RATINGS FOR ENGINEER APPROVAL. OVERCURRENT PROTECTIVE DEVICES AIC RATINGS SHALL BE FULLY RATED WITH A MINIMUM 10% MARGIN BETWEEN THE CALCULATED FAULT LEVEL AND THE SPECIFIED SHORT CIRCUIT RATING OF THE EQUIPMENT UNO ON PLANS.
18. VOLTAGE DROP: WIRE SIZES SPECIFIED IN THESE PLANS ARE MINIMUM WIRE SIZES. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR INCREASING WIRE SIZES BASED ON ACTUAL CIRCUIT LENGTH TO MAINTAIN VOLTAGE DROP AT A MAXIMUM OF 3% FOR BRANCH CIRCUITS AND 2% FOR FEEDERS. THE CUMULATIVE VOLTAGE DROP FROM THE SOURCE TO THE END DEVICE SHALL NOT EXCEED 5% OF NOMINAL SYSTEM VOLTAGE.
19. WIRING: ALL CONDUCTORS CARRYING 50 VOLTS OR MORE SHALL BE MINIMUM #12 AWG, CU, UNO. PROVIDE DUAL RATED TYPE THHN-THWN FOR ABOVE GROUND AND TYPE THWN OR XHHW FOR BELOW GROUND, COORDINATE INSULATION TYPES WITH ENVIRONMENTAL CONDITIONS, NEC REQUIREMENTS, AND CONDUIT FILL REQUIREMENTS. CONDUCTORS #12 AND #10 SHALL BE SOLID, CONDUCTORS #8 AND LARGER SHALL BE STRANDED. ALL CONDUCTOR SIZES ARE BASED ON COPPER WITH 60°C INSULATION FOR CIRCUITS RATED 100A OR LESS AND 75°C FOR CIRCUITS RATED MORE THAN 100A
22. LOW VOLTAGE WIRING: LOW VOLTAGE WIRING FOR SPECIAL SYSTEMS IS PERMITTED TO BE FREE-WIRED ONLY ABOVE ACCESSIBLE CEILINGS AND BELOW RAISED FLOOR SYSTEMS, UNO. FREE-WIRED CABLE SHALL BE UL LISTED, PLENUM RATED. LOW VOLTAGE WIRING IN OPEN CEILINGS, HARD CEILINGS, WALLS, PASSING THROUGH ADJACENT TENANT SPACES, OR ROUTED UNDERGROUND OR BELOW SLAB SHALL BE INSTALLED IN CONDUIT. LOW VOLTAGE WIRING IS NOT SHOWN ON PLANS, UNLESS SPECIFICALLY CALLED OUT.
23. COLOR CODING: FOR EXISTING WIRING SYSTEMS, COLOR CODING SHALL FOLLOW EXISTING SITE REQUIREMENTS. FOR NEW INSTALLATIONS OR WHERE EXISTING INSTALLATIONS DO NOT HAVE A COLOR CODING CONVENTION, THE FOLLOWING SYSTEMS OF COLOR CODING SHALL BE STRICTLY ADHERED TO AND FOLLOWED THROUGHOUT:

CONDUCTOR	480Y/277V, 3-PH	208Y/120V, 3-PH	240D/120V, 3-PH	240/120V, 1-PH
PHASE A:	BROWN	BLACK	BLACK	BLACK
PHASE B:	ORANGE	RED	ORANGE	RED
PHASE C:	YELLOW	BLUE	BLUE	-
NEUTRAL:	GRAY	WHITE	WHITE	WHITE
EQUIPMENT GROUND:	GREEN	GREEN	GREEN	GREEN
ISOLATED GROUND:	---	GREEN/YELLOW	GREEN/YELLOW	GREEN/YELLOW

24. SHARED CIRCUIT NEUTRALS: SHARED CIRCUIT NEUTRALS SHALL NOT BE USED UNLESS INDICATED OTHERWISE ON PANEL SCHEDULE. WHERE USED, CIRCUIT BREAKER HANDLE TIES SHALL BE PROVIDED TO DISCONNECT POWER TO EACH PHASE CONDUCTOR OF THE SHARED NEUTRAL CIRCUIT.
25. GROUNDING: ALL CIRCUITS SHALL BE PROVIDED WITH AN INSULATED GREEN COPPER EQUIPMENT GROUND CONDUCTOR SIZED PER NEC. THE EQUIPMENT GROUND CONDUCTOR SHALL BE INCREASED IN SIZE BY EQUAL PROPORTION TO THE PHASE CONDUCTORS WHENEVER THE PHASE CONDUCTORS HAVE BEEN UPSIZED TO MAINTAIN ACCEPTABLE VOLTAGE DROP LEVELS. EQUIPMENT GROUNDS SHALL BE BONDED TO ALL EQUIPMENT AND DEVICES. USE OF METALLIC CONDUIT SHALL NOT TAKE THE PLACE OF AN EQUIPMENT GROUND CONDUCTOR.
26. CONDUIT: ALL WIRING SHALL BE INSTALLED IN CONDUIT, MINIMUM 1/2" FOR INDOOR AND 3/4" FOR OUTDOOR AND UNDER SLAB. EMT IS ACCEPTABLE WITH COMPRESSION FITTINGS ONLY. ALL HOMERUNS SHALL BE HARD PIPED. MC IS ACCEPTABLE FOR FIXTURE WHIPS ONLY. ALL CONDUIT AND WIRING SHALL BE CONCEALED IN FLOORS, WALLS, AND/OR CEILINGS UNLESS SPECIFICALLY NOTED OTHERWISE. CHANNEL EXISTING WALLS WHERE REQUIRED. WHERE CONDUITS ARE UNABLE TO BE CONCEALED, HARD PIPED CONDUIT SHALL BE USED AND PAINTED TO MATCH ADJOINING SURFACE.
27. UNDERGROUND CONDUITS: MINIMUM BURIAL DEPTH SHALL BE 24" TO TOP OF CONDUIT. PROVIDE DETECTABLE WARNING TAPE WHERE REQUIRED BY AHJ OR CODE.
28. ROUTING: FOR CLARITY, CONDUIT ROUTING SHOWN IS SYMBOLIC AND DIAGRAMMATIC. INSTALL CONDUIT TO FIT ACTUAL FIELD CONDITIONS.
29. OPEN CEILINGS: IN AREAS WITHOUT CEILINGS OR WHERE ANY CONDUITS, CONDUCTORS, FEEDERS, OR LOW VOLTAGE CABLING IS VISIBLE, ALL WIRING SHALL BE HARD PIPED IN CONDUIT. BX, AC, AND MC CABLE OR FLEX CONDUIT ARE NOT PERMITTED. CONDUITS SHALL BE ROUTED TIGHT TO DECK EITHER PARALLEL OR PERPENDICULAR TO BUILDING LINES, GROUPED ALONG STRUCTURAL MEMBERS, AND DROP AT POINT OF CONNECTION. MAINTAIN 1-1/2" CLEARANCE FROM ROOF DECK PER NEC 300.4(E). WHERE EXPOSED TO VIEW, ALL MATERIALS (CONDUIT, JUNCTION BOXES, ETC.) SHALL BE INSTALLED IN AN ORDERLY FASHION AND SHALL BE CLEAN, FREE FROM ALL VISIBLE MARKINGS, AND PAINTED TO MATCH ADJOINING SURFACE. JUNCTION BOXES SHALL HAVE CIRCUIT NUMBERS WRITTEN ON THE INSIDE OF THE JUNCTION BOX COVER.
30. PENETRATIONS: CONTRACTOR SHALL INSPECT AREA OF WORK AND PERFORM GROUND PENETRATING RADAR (GPR) SCAN OR X-RAY ALL PROPOSED PENETRATIONS PRIOR TO WORK TO DETERMINE EXACT LOCATIONS OF STRUCTURAL REINFORCEMENT OR EMBEDDED SYSTEMS. COORDINATE FLOOR AND WALL PENETRATIONS WITH STRUCTURAL ENGINEER. ALL PENETRATIONS SHALL BE SEALED BY APPROVED MEANS TO PREVENT ENERGY LOSS AND MOISTURE AND RODENT INTRUSION.
31. FIRE-RATED PENETRATIONS: ALL PENETRATIONS THROUGH FIRE-RATED SLABS AND/OR PARTITIONS SHALL BE SEALED WITH A UL LISTED FIRE-RATED ASSEMBLY OF EQUAL OR GREATER RATING THAN THAT OF THE EXISTING SLAB OR PARTITION.
32. TRENCHING: FIELD VERIFY UNDERGROUND UTILITIES PRIOR TO TRENCHING. ALL PROPOSED EXCAVATION IN THE VICINITY OF EXISTING UTILITIES, PIPING SYSTEMS, OR SIMILAR SHALL BE HAND EXCAVATED. HAND EXCAVATE IN THE VICINITY OF EXISTING TREES WHERE TRENCHING MAY ENCOUNTER TREE ROOT SYSTEM.
33. SLEEVES: SLEEVES AND SLEEVE SEALS SHALL BE PROVIDED AT PENETRATIONS OF WALL ASSEMBLIES.
34. SUPPORTS: ALL CONDUIT AND CABLING SHALL BE PROPERLY SUPPORTED AS REQUIRED BY CODE.
35. REPAIRS: THE CONTRACTOR SHALL REPAIR ALL WALL, CEILING, FLOOR, OR ROOF OPENINGS WHICH ARE CREATED BY DEMOLITION OR PENETRATION. THE REPAIRS SHALL BE WITH MATERIAL AND FINISHES TO MATCH EXISTING ADJACENT UNDISTURBED FINISHED SURFACES.
36. IDENTIFICATION: ALL ELECTRICAL DISTRIBUTION EQUIPMENT, TRANSFORMERS, PANELBOARDS, AND OTHER ENCLOSED EQUIPMENT SHALL BE IDENTIFIED AS INDICATED IN THE CONTRACT DOCUMENTS. SAID IDENTIFICATION SHALL CONSIST OF PERMANENTLY ATTACHED ENGRAVED LAMINATED PLASTIC NAMEPLATES. EACH BRANCH CIRCUIT OVERCURRENT PROTECTION DEVICE SHALL BE IDENTIFIED BY CIRCUIT NUMBER AND SCHEDULED INSIDE PANEL DOOR WITH A TYPEWRITTEN CIRCUIT DIRECTORY. EACH BRANCH CIRCUIT SPLICE OR TERMINATION SHALL BE IDENTIFIED BY PANEL AND CIRCUIT DESIGNATION SHOWN ON THE JUNCTION OR OUTLET BOX, OR UPON INDIVIDUAL WIRES IN CASES WHERE MORE THAN ONE OF EACH PHASE CONDUCTOR OCCUR. RECEPTACLES AND SWITCH COVER PLATES SHALL BE LABELED WITH PANEL AND CIRCUIT DESIGNATION USING TYPEWRITTEN CHARACTERS OF CONTRASTING COLOR (BLACK OR WHITE) ON CLEAR ADHESIVE BACKED LABELS OR FACTORY ENGRAVED COVER PLATES.
37. PANEL CLEARANCE: MAINTAIN ALL WORKING SPACE AND DEDICATED EQUIPMENT SPACE CLEARANCES AS REQUIRED BY ARTICLE 110 OF THE NEC. GENERAL CONTRACTOR SHALL COORDINATE BETWEEN TRADES SO THAT NO FOREIGN SYSTEMS ARE LOCATED IN THE DEDICATED EQUIPMENT SPACE. IN THE EVENT THAT FOREIGN SYSTEMS ARE INSTALLED ABOVE A PANEL'S DEDICATED EQUIPMENT SPACE, THE GENERAL CONTRACTOR SHALL ABSORB THE COST TO RELOCATE THE FOREIGN SYSTEMS.
38. WIRING DEVICES: WIRING DEVICES AND COVER PLATES SHALL BE DECORA STYLE OF COLORS SELECTED BY THE ARCHITECT OR INTERIOR DESIGNER. GANG ADJACENT DEVICES WITH A SINGLE ONE-PIECE COVER PLATE, UNO. FOR REMODELS, ALL DEVICES AND COVER PLATES WITHIN THE CONTRACT AREA SHALL BE REPLACED WITH NEW DECORA STYLE DEVICES AND COVER PLATES, UNO.
39. CLEANING: UPON COMPLETION OF WORK, THE CONTRACTOR SHALL THOROUGHLY CLEAN THE CONTRACT AREA AND ALL OTHER AREAS USED FOR STORAGE, STAGING, ETC. ALL EQUIPMENT AND DEVICES SHALL BE CLEANED AND POLISHED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. SOAP AND WATER CLEANING OR OTHER METHODS THAT LEAVE A FILM SHALL BE CORRECTED UPON REQUEST BY THE ENGINEER OR ARCHITECT.
40. TESTING: THE CONTRACTOR SHALL TEST ALL EQUIPMENT INSTALLED UNDER THIS CONTRACT AND DEMONSTRATE TO THE OWNER ITS PROPER OPERATION. AT THE TIME OF FINAL INSPECTION AND TESTS, ALL CONNECTIONS AT PANELBOARDS, CONTROL PANELS, DEVICES, AND EQUIPMENT AND ALL SPLICES MUST BE COMPLETED. EACH BRANCH CIRCUIT AND ITS RESPECTIVE CONNECTED EQUIPMENT MUST TEST FREE OF SHORT CIRCUITS.
41. TRAINING: OWNER AND/OR OWNER'S REPRESENTATIVE SHALL BE TRAINED ON THE USE OF ANY NEW ELECTRICAL EQUIPMENT AND LIGHTING CONTROLS PRIOR TO FINAL ACCEPTANCE.
42. FINAL ACCEPTANCE: AT THE END OF CONSTRUCTION, A FINAL WALK-THROUGH SHALL BE PERFORMED. ALL DEFICIENCIES IDENTIFIED DURING FINAL INSPECTION SHALL BE CORRECTED.
43. CERTIFICATES OF APPROVAL: ALL CERTIFICATES OF APPROVAL SHALL BE IN DUPLICATE, DELIVERED TO THE ARCHITECT, AND BECOME THE PROPERTY OF THE OWNER.
44. PROJECT RECORD DOCUMENTS: THE ELECTRICAL CONTRACTOR SHALL MAINTAIN AT THE SITE, FOR THE OWNER, ONE COPY OF ALL DRAWINGS, ADDENDA, APPROVED SHOP DRAWINGS, REVISIONS AND OTHER MODIFICATIONS IN GOOD ORDER AND MARKED TO RECORD ALL CHANGES MADE DURING CONSTRUCTION. THE SET OF DRAWINGS AND OTHER INFORMATION SHALL BE DELIVERED TO THE OWNER WITHIN 30 DAYS AFTER THE DATE OF SYSTEM ACCEPTANCE AND ONE COPY GIVEN TO THE ENGINEER UPON COMPLETION OF WORK. DRAWINGS SHALL INCLUDE AT A MINIMUM:
    A. SINGLE-LINE DIAGRAM OF THE BUILDING ELECTRICAL DISTRIBUTION SYSTEM AND
    B. FLOOR PLANS INDICATING LOCATION AND AREA SERVED FOR ALL DISTRIBUTION.
45. OPERATIONS AND MAINTENANCE (O&M) MANUALS: PROVIDE TWO COPIES OF OPERATIONS AND MAINTENANCE MANUALS TO THE BUILDING OWNER IN HARD COPY AND ELECTRONIC FORMAT. HARD COPIES SHALL BE COMPILED AND ORGANIZED IN A BINDER. THE MANUALS SHALL INCLUDE, AT A MINIMUM, THE FOLLOWING:
    A. SUBMITTAL DATA STATING EQUIPMENT RATING AND SELECTED OPTIONS FOR EACH PIECE OF EQUIPMENT REQUIRING MAINTENANCE.
    B. OPERATING AND MAINTENANCE MANUALS FOR EACH PIECE OF EQUIPMENT REQUIRING MAINTENANCE. REQUIRED ROUTINE MAINTENANCE ACTIONS SHALL BE CLEARLY IDENTIFIED.
    C. NAMES AND ADDRESSES OF AT LEAST ONE QUALIFIED SERVICE AGENCY.
    D. WARRANTY INFORMATION.
46. WARRANTY: THE ENTIRE ELECTRICAL SYSTEM INSTALLED UNDER THIS CONTRACT SHALL BE HANDED OVER IN PROPER WORKING ORDER. ANY WORK OR MATERIALS WHICH DEVELOP DEFECTS, EXCEPT FROM ORDINARY WEAR AND TEAR, WITHIN ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE SHALL BE REPLACED WITHOUT CHARGE. IF MATERIALS HAVE A STANDARD WARRANTY GREATER THAN ONE YEAR, THE MANUFACTURER'S STANDARD WARRANTY SHALL APPLY. BENEFICIAL USE SHALL NOT BE CONSTRUED AS FINAL ACCEPTANCE. THE ELECTRICAL CONTRACTOR SHALL, DURING THE ONE YEAR GUARANTEE PERIOD, BE RESPONSIBLE FOR THE PROPER REPAIR AND ADJUSTMENTS OF ALL ELECTRICAL SYSTEMS AND EQUIPMENT, APPARATUS, DEVICES, ETC. INSTALLED BY HIM, AND DO ALL WORK NECESSARY TO ENSURE

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 041568 PROFESSIONAL ENGINEER RAHN ONEAL WILLIAMS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:

FIFTH THIRD BANK

Project Number: 26032
Project Name:

FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:

ELECTRICAL GENERAL NOTES

Sheet Number:

E-002

6/30/2026 2:31:56 PM