MINIMUM DUCT INSULATION R-VALUES:

LOCATION (1)	SUPPLY DUCT	RETURN DUCT
EXTERIOR OF BUILDING	R-8	R-12
VENTILATED ATTIC	R-8	R-8
UNVENTED ATTIC ABOVE INSULATED CEILING	R-6	R-6
UNVENTED ATTIC WITH ROOF INSULATION	R-8	R-12
UNCONDITIONED SPACES (2)	R-6	R-6
INDIRECTLY CONDITIONED SPACES (3)	R-6	R-6
CONDITIONED SPACES	NONE	NONE

NOTES:
(1) INCLUDES RETURN AIR PLENUMS WITH OR WITHOUT EXPOSED ROOFS ABOVE.
(2) INCLUDES CRAWL SPACES, BOTH VENTILATED AND NON-VENTILATED.
(3) THIS TABLE APPLIES TO COMMERCIAL HVAC SYSTEMS ONLY AND INCLUDES BOTH SUPPLY AND RETURN DUCTS.
(4) MINIMUM INSULATION VALUES ARE BASED ON IECC C403 AND ASHRAE 90.1, AS ADOPTED BY THE AUTHORITY HAVING JURISDICTION.

EQUIPMENT ROOF STAND HEIGHTS:

MOUNTED MECHANICAL UNITS					
WIDTH OF MECHANICAL UNIT (IN)	< 24	25-36	47-48	49-60	> 60
MINMUM CLEARANCE ABOVE SURFACE	14	18	24	30	48

NOTES:
ROOF MOUNTED MECHANICAL UNITS SHALL BE MOUNTED ON CURBS RAISED A MINIMUM OF 8 INCHES ABOVE THE ROOF SURFACE OR WHERE ROOFING MATERIALS EXTEND BENEATH THE UNIT, ON RAISED EQUIPMENT SUPPORTS PROVIDING A MINIMUM CLEARANCE HEIGHT IN ACCORDANCE WITH TABLE THE TABLE PROVIDED.

MECHANICAL CONTROLS & ACCESSORIES

GENERAL CONTROLS REQUIREMENTS (ALL EQUIPMENT)

MECHANICAL CONTRACTOR(MC) SHALL PROVIDE TEMPORARY DIGITAL THERMOSTATS AS REQUIRED FOR EQUIPMENT START-UP AND INITIAL OPERATION. IOT SHALL FURNISH AND INSTALL ALL PERMANENT KMC CONTROLS AND COMPLETE BMS INTEGRATION AFTER EQUIPMENT START-UP AND PRIOR TO FINAL COMMISIONING.

MOUNT ALL THERMOSTATS AND SENSORS AT 44" AFF TO CENTER LINE OF VERTICAL DEVICE UNLESS NOTED OTHERWISE. COORDINATE FINAL DEVICE COLOR AND FINISH WITH ARCHITECT.

MC SHALL CORDINATE ALL REQUIRED CONTROL WIRING, POWER, INTERFACES, AND ACCESSORIES NECESSARY FOR FULLY FUNCTIONAL AND COMMISSIONED SYSTEM OPERATION.

RTU CONTROLS (CARRIER UNITS)

PERMANENT THERMOSTAT: KMC FLEXSTAT BAC-120063CW
(PURCHASED AND INSTALLED BY IOT)

MONITORING SENSOR: KMC APPROVED SENSORS
(PURCHASED AND INSTALLED BY IOT)

RTU'S TO USE TEMPORARY THERMOSTATS UNTIL THE PERMANENT KMC BRANDED FLEXSTATS WITH BMS INTEGRATION ARE INSTALLED AND COMMISSIONED. UPON CHANGEOVER, TEMPORARY THERMOSTATS SHALL BE REMOVED AND RETURNED TO MC.

RTU ACCESSORIES NOTE:
MECHANICAL CONTRACTOR TO PROVIDE ROOFTOP UNIT WITH THE FOLLOWING ACCESSORIES:

FIELD INSTALLED

1. WALL MOUNTED CO2 SENSOR (PART NO: 33ZCSPTC02-01)
2. RETURN ENTHALPY SENSOR KIT (PART NO: CRENTSEN001A00)
3. OUTDOOR ENTHALPY SENSOR KIT (PART NO: CRENTSEN001A00)
4. WIFI STICK FOR ECONOMIZERS (PART NO: CRWFTCK001A00)

FACTORY INSTALLED

5. ECONOMIZER CONTROLLER (SIEMENS POL224)
6. ACTUATOR (PART NO: HF23BL005)
7. POWER HARNESS (PART NO: 48TC005897)
8. SUPPLY AIR SENSOR (PART NO: HH79NZ039)

FCU THERMOSTAT NOTE:
MECHANICAL CONTRACTOR TO PROVIDE AND INSTALL THERMOSTAT WITH INTERFACE. IOT WILL SUPPLY KMC CONTROLS AND COMPLETE BMS INTEGRATION AFTER EQUIPMENT STARTUP.

THERMOSTAT INTERFACE ADAPTERS (BY MC AS REQUIRED)

- MITSUBISHI / TRANE THERMOSTAT INTERFACE: PAC-US445CN-1
- CARRIER THERMOSTAT INTERFACE: KSAIC0301230
  (EC MAY BE REQUIRED FOR HIGH VOLTAGE WIRING)

SPLIT SYSTEMS SHALL UTILIZE KMC FLEXSTAT WITH BMS INTEGRATION. MINI-SPLITS SHALL UTILIZE OEM-APPROVED THERMOSTAT INTERFACE ADAPTER WITH KMC FLEXSTAT FOR BMS INTEGRATION.

PACKAGED ROOFTOP HEAT PUMP AIR HANDLING UNIT SCHEDULE: GC PROVIDED

MARK	AREA SERVED	MFG.	MODEL	ROOM TEMP	NOMINAL SIZE	SUPPLY AIR FLOW (CFM)	MINIMUM OUTDOOR AIR FLOW (CFM)	FILTER TYPE	EXT S.P. (IN W.C.)	FAN MOTOR		COOLING CAPACITY				HEATING CAPACITY			ELECTRICAL				WEIGHT (LBS)	SEER
										RPM	MOTOR BPH	TOTAL CAPACITY	SENSIBLE CAPACITY	ENTERING AIR (° FDB/°FWB)	MEDIA	HEAT SOURCE	STAGES	MBH	VOLT	PH	HZ	MCA/MOCP (W/ HEAT)		
RTU-1	ENTRY/MEETING	CARRIER	48FEDA05J3M5-8W4D0	75° F	4.0	1,600	--	MERV 13	1.0	--	0.91	52.33 MBH	37.66 MBH	80/67	R-454B	NATURAL GAS	1	67	208V	3	60	24/30	797	14.0
RTU-2	SEATING/LOUNGE	CARRIER	48FEDA05J3M5-8W4D0	75° F	4.0	1600	--	MERV 13	1.0	--	0.91	52.33 MBH	37.66 MBH	80/67	R-454B	NATURAL GAS	1	67	208V	3	60	24/30	797	14.0

SCHEDULE NOTES:
ACCEPTABLE MANUFACTURERS INCLUDE CARRIER (BOD), TRANE, AND DAIKIN GIVEN COMPARABLE MODEL IS SELECTED. FIELD INSTALLED ACCESSORIES ARE ALSO ACCEPTABLE. CONTACT EMAIL FOR CARRIER REPRESENTATIVE: NATIONALACCOUNTS@CARRIER.COM.

1. PROVIDE 18" FACTORY INSULATED ROOF CURB. ROOF CURB TO BE PITCHED 1/4" PER FOOT ACCORDING TO ROOF SLOPE. SHEET METAL CONTRACTOR SHALL PROVIDE EXTENDED ROOF CURB FOR ROUTING OF DUCTWORK WITHIN CURB TO A SINGLE ROOF OPENING, CONFIRM WITH STRUCTURAL THAT DISCHARGE DUCT OPENING IN THE BOTTOM OF THE UNIT FITS BETWEEN THE JOISTS.
2. PROVIDE RTU WITH VERTICAL SUPPLY AND RETURN AIR CONNECTIONS AND DRAW THRU CONFIGURATION WITH STAINLESS STEEL DRAIN PAN.
3. INCLUDE UNIT WITH THE FOLLOWING; REFERENCE ENTHALPY CONTROLLED ECONOMIZER WITH LOW LEAKAGE DAMPERS, BAROMETRIC RELIEF DAMPER, AND OUTSIDE AIR SYSTEM INTAKE HOOD WITH AUTOMATIC DAMPER. EVAPORATOR FAN TO BE DIRECT DRIVE.
4. FURNISH FUSED DISCONNECT FOR INSTALLATION BY ELECTRICAL CONTRACTOR. PROVIDE THROUGH-THE-BASE ELECTRICAL DISCONNECT SWITCH WITH UNPOWERED CONVENIENCE OUTLET ON UNIT. INCLUDE UNIT AUTO RESET PHASE MONITOR.
5. PROVIDE TWO (2) SETS OF 2" MERV 13 CARTRIDGE FILTERS WITH EACH UNIT.
6. PROVIDE FACTORY SEACOAST SPRAY PROTECTION ON UNIT FOR ANY PROJECT LOCATION WITHIN 20 MILES OF A COASTLINE.
7. PROVIDE FACTORY INSTALLED BURGLAR BARS, CONDENSER COIL GUARD, AND EXTERNAL HAIL GUARDS.
8. PROVIDE WITH HURRICANE TIE DOWNS AND REFER TO ENGINEERED WIND LOAD MITIGATION CALCULATIONS.
9. PROVIDE UNITS WITH COIL CONFIGURATION HEAT THEN COOL, COIL LEAVING AIR TEMPERATURES TO BE NO LESS THAN 55°F. UNIT SELECTION SHALL BE BASED ON OUTSIDE AIR TEMPERATURE OF 110°F IN CLIMATE ZONES 1A-2A, ALL OTHER ZONES TO HAVE NET COOLING CAPACITY OF 95°F AMBIENT. HEAD PRESSURE CONTROL TO 0°F AMBIENT.
10. UNIT MOUNTED SIEMENS POL224 ECONOMIZER CONTROLLER. TEMPORARY THERMOSTATS SHALL BE DIGITAL THERMOSTATS FOR START UP THEN REPLACED BY IOT WITH FIFTH THIRD BMS KMC FLEXSTAT. TEMPORARY THERMOSTATS SHALL BE RETURNED TO MC UPON COMPLETION OF THE CONTROLS INSTALLATION. MONITORING SENSORS SHALL BE PROVIDED BY IOT AND INSTALLED BY MC.
11. ALL HVAC SYSTEM CONTROLS SHALL BE SELECTED TO BE COMPATIBLE WITH BMS CONTROL SYSTEM. MECHANICAL CONTRACTOR AND HVAC SYSTEM SUPPLIER SHALL CONFIRM WITH CONTROLS VENDOR TO ENSURE FULL COMPATIBILITY FOR ALL HVAC EQUIPMENT PRIOR TO ORDERING/PURCHASE.
12. PROVIDE DUCT SMOKE DETECTORS IN RETURN AND SUPPLY MAIN DUCT FOR ANY UNITS PROVIDING AT/OVER 2,000CFM OF AIRFLOW.
13. DEMAND CONTROL VENTILATION (DCV) WITH SPACE CO2 SENSOR FROM HVAC EQUIPMENT MANUFACTURER.
14. UNIT SHALL BE ASHRAE 90.1 COMPLIANT.
15. RTU'S TO BE PURCHASED WITH THE ELECTRO-MECHANICAL CONTROLS AND ULTRA LOW LEAK ECONOMIZER WITH BAROMETRIC RELIEF. REFER TO RTU ACCESSORIES NOTE FOR ADDITIONAL INFORMATION.
16. PROVIDE 2" DOUBLE WALL CONSTRUCTION FOR R-13 THERMAL RESISTANCE INCLUDING THE BOTTOM PANEL WITH HINGED ACCESS DOORS.
17. RTU TO COME WITH CONDENSATE OVERFLOW SWITCH - THIS SENSOR AND RELATED CONTROLLER MONITORS THE CONDENSATE LEVEL IN THE DRAIN PAN AND SHUTS DOWN COMPRESSION OPERATION WHEN OVERFLOW CONDITIONS OCCUR. IT INCLUDES:
    - INDICATOR LIGHT - SOLID RED (MORE THAN 10 SECONDS ON WATER CONTACT - COMPRESSORS DISABLED), BLINKING RED (SENSOR DISCONNECTED)
    - 10-SECOND DELAY TO BREAK - ELIMINATES NUISANCE TRIPS FROM SPLASHING OR WAVES IN PAN (SENSOR NEEDS 10 SECONDS OF CONSTANT WATER CONTACT BEFORE TRIPPING)
    - DISABLES THE COMPRESSORS OPERATION WHEN CONDENSATE PLUG IS DETECTED, BUT STILL ALLOWS FANS TO RUN FOR ECONOMIZER.
18. MECHANICAL CONTRACTOR TO NOTIFY IOT IF RTU UNITS ARE NOT EQUIPPED WITH SYSTEM VU CONTROLS. CONTACT GERRIANNE FAULHABER: GERRIANNE@IOFTEAM.COM, 224-213-6908.

MINI-SPLIT SYSTEM AIR CONDITIONER SCHEDULE: GC PROVIDED

MARK		SYSTEM ZONE	MFG.	INDOOR UNIT			OUTDOOR UNIT			COOLING				HEATING			ELECTRICAL				PHYSICAL	
INDOOR UNIT	OUTDOOR UNIT			MODEL NUMBER	MOUNTING	FAN AIRLOW	MODEL NUMBER	SYSTEM TYPE	REFR. TYPE	RATED CAPACITY (BTU/H)	MINIMAL CAPACITY (BTU/H)	SEER	EER	RATED CAPACITY (BTU/H)	MINIMAL CAPACITY (BTU/H)	HSPF	VOLT/PH/HZ	UNIT MCA		MOCP	INDOOR UNIT WEIGHT	OUTDOOR UNIT WEIGHT
																		INDOOR	OUTDOOR			
FCU-1	HP-1	ELECTRICAL / IT ROOM	MITSUBISHI	PKA-A12LNL	WALL MOUNT	385 CFM	PUZ-A12NL	HEAT PUMP	R-454B	12,200	4,300	21.1	14.8	18,000	4,300	10.1	208 / 230V, 1-PHASE, 60HZ	1 A	16 A	27 A	28 LBS	99.21 LBS

SCHEDULE NOTES:
NO ALTERNATIVE MANUFACTURERS OR MODEL NUMBERS ARE ACCEPTABLE. FIFTH THIRD BANK HAS A NATIONAL ACCOUNT AGREEMENT WITH THE TRANE COMPANY. FOR COMPLETE INFORMATION ON THE FOLLOWING EQUIPMENT PACKAGE PLEASE CONTACT TRANE NATIONAL ACCOUNTS: DANIEL SWEGLE AT DANIEL.SWEGLE@TRANE.COM / 636-875-6616.

1. INDOOR UNITS RECEIVE POWER FROM OUTDOOR UNITS THROUGH FIELD-SUPPLIED INTERCONNECTED WIRING. COORDINATE FINAL UNIT INSTALLATION LOCATION WITH STRUCTURAL CONDITIONS.
2. PROVIDE GRAVITY CONDENSATE DRAIN WHERE 1/4" PER FOOT SLOPE IS ACHIEVABLE. WHERE NOT ACHIEVABLE FOR WALL-MOUNTED UNITS, PROVIDE LITTLE GIANT VCMA-15ULST CONDENSATE PUMP WIRED FOR HIGH-WATER SHUTDOWN. DUCTED PEAD UNITS SHALL USE FACTORY CONDENSATE LIFT AND INTERNAL SAFETY; NO ADDITIONAL ACCESSORIES REQUIRED UNLESS LIFT EXCEEDS 27".
3. ZONES FED BY THIS SYSTEM ARE NON-OCCUPIABLE OR ARE NATURALLY VENTILATED.
4. PROVIDE WITH MITSUBISHI PAC-US445CN-1 HARD WIRED BACK-LIT MA REMOTE CONTROLLER. COMPONENTS TO HAVE BACNET INTERFACE AND INTERLOCK WITH BMS, PROVIDE CONTROL WIRING DIAGRAM FOR ENGINEER REVIEW.
5. PROVIDE FACTORY SEACOAST SPRAY PROTECTION ON UNIT FOR ANY PROJECT LOCATIONS WITHIN 20 MILES OF A COASTLINE.
6. REFRIGERANT CIRCUIT ACCESS PORTS LOCATED OUTDOORS SHALL BE FITTED WITH LOCKING TYPE TAMPER RESISTANT CAPS.
7. MOUNT OUTDOOR UNIT ON MINIMUM 18" HIGH NONISOLATED WIND AND SEISMIC RESTRAINT RAILS.BASIS OF DESIGN; VMC GROUP MODEL #R-7000.
8. HANG INDOOR WALL MOUNTED UNIT TO SECURE WALL STRUCTURE PER MANUFACTERE RECOMMENDATIONS (REFER TO INSTALLATION DETAIL).
9. PROVIDE FULL PORT BALL VALVES & SCHRADER VALVES WITH FLARED CONNECTIONS ON INDOOR WALL UNIT.
10. PROVIDE DRAIN PAN WITH UL#508 APPROVED WATER DETECTION SENSOR FOR UNIT SHUTDOWN. WIRE CONTROL CIRCUIT THROUGH NC CONTACT.
11. COOLING CAPACITY RATED AT 95°F AND HEATING CAPACITY RATED AT 17°F.
12. 100% HEATING CAPACITY AT 5°F AND HEATING PERFORMANCE, DOWN TO -13°F WITH AVERAGE OF 80% CAPACITY.
13. ELECTRICAL CONTRACTOR TO INCLUDE AND INSTALL 3-POLE DISCONNECT SWITCH.
14. MECHANICAL CONTRACTOR TO NOTIFY IOT IF DIFFERENT SPLIT SYSTEM IS PROVIDED. CONTACT GERRIANNE FAULHABER: GERRIANNE@IOFTEAM.COM, 224-213-6908.

DUCT SIZING GUIDE

SUPPLY DUCT (0.08SP)				RETURN DUCT (0.05SP)			
ROUND DUCT		RECTANGULAR DUCT		ROUND DUCT		RECTANGULAR DUCT	
CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)
1-100	6	1-125	6X6	1-75	6	1-100	6X6
101-210	8	126-260	8X8	76-160	8	101-200	8X8
211-395	10	261-470	10X10	161-290	10	201-365	10X10
396-625	12	471-760	12X12	291-470	12	366-595	12X12
626-910	14	761-1,145	14X14	471-710	14	596-895	14X14
911-1,300	16	1,146-1,635	16X16	711-1,010	16	896-1,275	16X16
1,301-1,800	18	1,636-2,235	18X18	1,011-1,375	18	1,276-1,745	18X18
1,801-2,325	20	2,236-2,955	20X20	1,376-1,815	20	1,746-2,310	20X20

NOTES:
1. FOR RECOMMENDED SQUARE SIZE DUCT AN APPROXIMATE EQUIVALENT RECTANGULAR CROSS SECTIONAL AREA IS ALSO ACCEPTABLE FOR ALTERNATIVE RECTANGULAR DUCT DIMENSIONS. DO NOT EXCEED A 3:1 DIMENSION RATIO.
2. ROUND AND SQUARE DUCT DIMENSIONS HAVE BEEN SIZED BASED ON 0.08 INCHES OF FRICTION HEAD LOSS FOR SUPPLY DUCT AND 0.05 FOR RETURN DUCT.

AIR DISTRIBUTION SCHEDULE

MARK	NECK SIZE	MAX CFM	DESCRIPTION
S (CFM)	6"ø	0-90	FACE SIZE SHALL BE 12X12 (SEE BELOW FOR REMAINING NOTES)
	6"ø	0-100	ARCHITECTURAL SQUARE PANEL CEILING SUPPLY AIR DIFFUSER - STEEL CONSTRUCTION, MODULE SIZE 24X24, CURVED BACK-PAN DESIGN AND ROUND DUCT CONNECTIONS, PROVIDE ROUND RUN-OUTS AS INDICATED BELOW; TITUS D-OMNI-1 (BORDER TYPE 3; LAY-IN FULL FACE FLAT T-BAR CEILING GRID) COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. COORDINATE LOCATIONS WITH LIGHTING DO NOT SCALE FROM MECHANICAL DRAWINGS
	8"ø	101-210	
	10"ø	211-330	
	12"ø	331-480	
	14"ø	481-650	
LSD (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT SUPPLY CEILING DIFFUSER WITH 1" SLOT, 4'-0" LONG WITH INSULATED PLENUM BOX, END BORDERS, AND FACE OPERATED REMOTE DAMPER AT PLENUM INLET. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
LSR (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT RETURN CEILING DIFFUSER, 4'-0" LONG, WITH NO PATTERN CONTROLLER, FOR RETURN AIR DUTY. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
LD (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT SUPPLY CEILING DIFFUSER, 2'-0" LONG WITH INSULATED PLENUM BOX, END BORDERS, AND FACE OPERATED REMOTE DAMPER AT PLENUM INLET. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
R (CFM) TR (CFM)	10" X10"	0-400	EGGCRATE RETURN AIR GRILLE - CORE OF 1/2"X1/2"X1" ALUMINUM GRID. TYPICAL PANEL SIZE; 12X12, 24X12, 24X24, AND 24X8. ALL CEILING RETURN, EXHAUST, TRANSFER GRILLES TO BE TITUS 50F (BORDER TYPE 3; LAY-IN FULL FACE FLAT T-BAR CEILING GRID) COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. SIZE AS INDICATED IN TABLE (PROVIDE SQUARE TO ROUND TRANSITION AS NEEDED). COORDINATE LOCATIONS WITH LIGHTING DO NOT SCALE FROM MECHANICAL DRAWINGS
	22" X 10"	401-800	
	22" X 22"	801-2,000	
	22" X 46"	2,001-4,000	

NOTES:
1. FURNISH WITH STANDARD WHITE BAKED ENAMEL FINISH (#26 WHITE). SUBMIT COLOR SAMPLE FOR ALL AIR DEVICES TO ARCHITECT BEFORE ORDERING.
2. FURNISH "RAPID-MOUNT" FRAMES FOR S-1 & R-1 DEVICES LOCATED IN DRYWALL CEILINGS. COORDINATE MOUNTING FRAME WITH CEILING/WALL TYPE.
3. PROVIDE 120/240 VAC TRANSFORMER POWER MODULE, CONTROLLER/THERMOSTAT AND PRESSURE RELIEF RING FOR ALL VAV DIFFUSERS.
4. SIZE FOR MAXIMUM NOISE CRITERION <30 FOR DIFFUSERS, REGISTERS, AND GRILLES.
5. PROVIDE DIRECTIONAL BLOW CLIPS WHERE REQUIRED OR DIRECTIONAL NECK BAFFLES WHERE INDICATED FOR BLOCKED AIRFLOW.
6. PROVIDE REMOTE CABLE OPERATED VOLUME DAMPERS LOCATED IN INACCESSIBLE CEILING/WALL CONSTRUCTION.

* BASIS OF DESIGN PRODUCTS ARE INDICATED FOR REFERENCE ONLY. COMPARABLE PRODUCTS WILL BE ACCEPTED PROVIDED COMPLIANCE WITH TECHNICAL SPECIFICATION REQUIREMENTS. ACCEPTABLE MANUFACTURERS SHALL BE PRICE, TITUS, ANEMOSTAT AND KRUEGER.

EXHAUST FAN SCHEDULE: GC PROVIDED

MARK	AREA SERVED	PRODUCT		MOUNTING TYPE	CFM	EXT S.P. (IN W.C.)	MOTOR DATA				NOTES
		MANUFACTURER	MODEL				RPM	TYPE	VOLT/PH/HZ	WATTS	
EF-1	JANITOR'S CLOSET	GREENHECK	SP-B90	CEILING	55	0.33	889	FSC	120/1/60	17 W	(1)(2)(4)(5)(6)
EF-2	MEN'S RESTROOM	GREENHECK	SP-B110	CEILING	80	0.33	650	FSC	120/1/60	30 W	(1)(2)(3)(4)(5)(6)
EF-3	WOMEN'S RESTROOM	GREENHECK	SP-B110	CEILING	80	0.33	650	FSC	120/1/60	30 W	(1)(2)(3)(4)(5)(6)

NOTES:
(1) ACCEPTABLE MANUFACTURERS: LOREN COOK, GREENHECK, OR CAPTIVEAIRE AND MUST MEET EQUIVALENT CHARACTERISTICS.
(2) PROVIDE FANS WITH FSC SPEED CONTROLLER (5A-120V), LOCATE WITHIN ACCESSIBLE LOCATION.
(3) EXHAUST FAN SHALL BE INTERLOCKED WITH LOCAL LIGHTING THAT TURN ON DURING ROOM SENSOR OCCUPIED MODE (COORDINATE WITH EC).
(4) PROVIDE FANS WITH THE FOLLOWING: TYPICAL DISCONNECT SWITCH, INTEGRAL GRAVITY BACKDRAFT DAMPER, AND HANGING ISOLATOR KIT.
(5) PURCHASE FANS WITH ALUMINUM CEILING GRILLE IF STANDARD IS PLASTIC.
(6) PROVIDE MOUNTING FRAME FOR GYPSUM BOARD CEILING.

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON
1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
MECHANICAL SCHEDULES

Sheet Number:
M-101

6/30/2026 4:54:52 PM