ABBREVIATIONS

A/C	ABOVE CEILING	HWRR	HOT WATER REVERSE RETURN
AAV	AIR ADMITTANCE VALVE	HWS	HOT WATER SUPPLY
AD	ACCESS DOOR		
ADJ	ADJUSTABLE	ID	INSIDE DIMENSION
AFF	ABOVE FINISHED FLOOR	IE	INVERTED ELEVATION
AUTO	AUTOMATIC	IN	INCHES
B/G	BELOW GRADE	KW	KILOWATTS
B/S	BELOW SLAB		
BAL	BALANCING	LB	POUNDS
BCO	BASE CLEANOUT	LP	LIQUID PROPANE GAS
BHP	BRAKE HORSEPOWER	LWR	LOOP WATER RETURN
BOD	BASIS OF DESIGN	LWS	LOOP WATER SUPPLY
CO	CLEANOUT	MAX	MAXIMUM
COND	CONDENSATE	MIN	MINIMUM
CW	COLD WATER (DOMESTIC)	MFR	MANUFACTURER
DN	DOWN	NC	NORMALLY CLOSED
DR	DRAIN	NFGH	NON-FREEZE GROUND HYDRANT
DWG	DRAWING	NFWH	NON-FREEZE WALL HYDRANT
		NG	NATURAL GAS
EA	EACH	NO	NORMALLY OPEN
ECC	ECCENTRIC	NOM	NOMINAL
EFF	EFFICIENCY		
EOD	EMERGENCY OVERFLOW DRAIN	OD	OUTSIDE DIMENSION
		OD	OVERFLOW DRAIN
EWT	ENTERING WATER TEMP.		
EX	EXISTING	PSI	POUNDS PER SQUARE INCH
F	FAHRENHEIT	RAD	RADIUS
FCO	FLOOR CLEANOUT	RED	REDUCER
FD	FLOOR DRAIN		
FLR	FLOOR	SAN	SANITARY
FOB	FLAT ON BOTTOM	SQ	SQUARE
FOT	FLAT ON TOP	ST	STORM
FPM	FEET PER MINUTE		
FPS	FEET PER SECOND	TEMP	TEMPERATURE
FT	FEET	TYP	TYPICAL
G	GATE	UON	UNLESS OTHERWISE NOTED
GA	GAUGE		
GCO	GRADE CLEANOUT	V	VENT
GL	GLOBE	VA	VALVE
GPM	GALLONS PER MINUTE	VTR	VENT THRU ROOF
GW	GREASE WASTE		
		WC	WATER COLUMN
HD	HUB DRAIN	WCO	WALL CLEANOUT
HP	HORSEPOWER	WHA	WATER HAMMER ARRESTOR
HW	HOT WATER (DOMESTIC)	WT	WEIGHT
HWR	HOT WATER RETURN	W	WASTE

APPLICABLE CODES

- International Building Code, 2024 Edition, with Georgia Amendments (2026)
- International Fire Code, 2024 Edition
- International Plumbing Code, 2024 Edition, with Georgia Amendments (2026)
- International Fuel Gas Code, 2024 Edition, with Georgia Amendments (2026)
- International Energy Conservation Code, 2015 Edition, with Georgia Supplements and Amendments

PLUMBING SHEET INDEX:

P-001	PLUMBING SPECIFICATIONS AND NOTES
P-101	PLUMBING TABLE AND SCHEUDLES
P-301	PLUMBING SANITARY FOUNDATION PLAN
P-302	PLUMBING DOMESTIC ROOF PLAN
P-303	PLUMBING STORM ROOF PLAN
P-304	PLUMBING NATURAL GAS ISO PLAN
P-401	PLUMBING ISOMETRIC RISER DIAGRAM
P-402	PLUMBING BUILDING ISOMETRIC
P-501	PLUMBING DETAILS

SPECIFICATIONS

PART 1 - GENERAL

1. SUBMITTALS
   A. PRODUCT DATA: FOR EACH TYPE OF PRODUCT INDICATED.

PART 2 - PRODUCTS

1. PIPING MATERIALS
   A. COMPLY WITH REQUIREMENTS IN "PLUMBING PIPING SCHEDULE" ARTICLE FOR APPLICATIONS OF PIPE, TUBE, AND FITTING MATERIALS, AND FOR JOINING METHODS, INSULATION, AND HANGING REQUIREMENTS FOR SPECIFIC SERVICES, SERVICE LOCATIONS, AND PIPE SIZES.
2. VALVES
   A. NSF COMPLIANCE: NSF 61 FOR VALVE MATERIALS FOR POTABLE -WATER SERVICE.
   B. WATER SHUTOFF SERVICE: TWO-PIECE, FULL PORT, BRASS BALL VALVES WITH BRASS TRIM.
   C. CHECK VALVES: BRASS SILENT CHECK VALVES WITH NONMETALLIC DISC SUITABLE FOR HORIZONTAL OR VERTICAL INSTALLATION.
   D. FUEL GAS SHUTOFF SERVICE: TWO-PIECE, FULL PORT, BRASS BALL VALVES WITH BRASS TRIM, UL LISTED FOR GAS SERVICE.
   E. FUEL GAS PRESSURE REGULATORS: COMMERCIAL STYLE REGULATORS WITH INTERNAL PRESSURE RELIEF VALVES.
3. HANGERS AND SUPPORTS
   A. PROVIDE HANGERS INDICATED ON DRAWINGS.
   B. WALL SUPPORTS
      - PIPING 3" AND SMALLER: STEEL RISER CLAMP.
   C. VERTICAL SUPPORT: STEEL RISER CLAMP.

PART 3 - EXECUTION

1. PIPING INSTALLATION
   A. INSTALL ESCUTCHEONS AT EACH WALL, FLOOR, AND CEILING PENETRATION IN EXPOSED FINISHED LOCATIONS AND WITHIN CABINETS AND MILLWORK. USE DEEP PATTERN ESCUTCHEONS WHERE REQUIRED TO CONCEAL PROTRUDING PIPE FITTINGS.
   B. INSTALL SLEEVES FOR PIPING PENETRATIONS OF WALLS, CEILINGS, AND FLOORS.
   C. INSTALL SLEEVE SEALS FOR PIPING PENETRATIONS OF CONCRETE WALLS AND SLABS.
   D. MAKE SOLDERED JOINTS USING LEAD FREE SOLDER AND A NON-CORROSIVE, PASTE-TYPE FLUX. CORE SOLDER IS NOT PERMITTED SOLDER SHALL BE SOLID STRING OR WIRE TYPE. WHERE SOLDERED COPPER PIPING IS CONNECTED TO THREADED BRASS PIPING, USE CAST BRASS ADAPTOR.
   E. PLACE PLUGS IN ENDS OF UNCOMPLETED PIPING AT END OF EACH DAY OR WHEN WORK STOPS.
   F. MINIMUM SLOPE OF HORIZONTAL DRAIN PIPING SHALL BE 1/4" PER FOOT FOR PIPING 2-1/2" OR LESS, 1/8" PER FOOT FOR PIPING 3" TO 6", AND 1/16" PER FOOT FOR PIPING 8" OR LARGER.
   G. MAKE CHANGES IN DIRECTION IN DRAIN PIPING WITH INDIVIDUAL EIGHT BENDS AND WYES.
   H. QUARTER BENDS, SWEEPS, TEES, AND COMBINATION WYE & EIGHT BEND FITTINGS ARE NOT PERMITTED FOR USE ON DRAIN PIPING.
   I. EXTEND RIGID GAS PIPING TO EXTERIOR GAS APPLIANCES AND INSTALL SHUTOFF VALVE, DIRT LEG, AND UNION AT EACH APPLIANCE.
2. JOINT CONSTRUCTION
   A. REAM ENDS OF PIPES AND TUBES AND REMOVE BURRS. BEVEL PLAIN ENDS OF STEEL PIPE.
   B. REMOVE SCALE, SLAG, DIRT, AND DEBRIS FROM INSIDE AND OUTSIDE OF PIPES, TUBES, AND FITTINGS BEFORE ASSEMBLY.
   C. THREADED JOINTS: THREAD PIPE WITH TAPERED PIPE THREADS ACCORDING TO ASME B1.20.1. CUT THREADS FULL AND CLEAN USING SHARP DIES. REAM THREADED PIPE ENDS TO REMOVE BURRS AND RESTORE FULL ID. JOINT PIPE FITTINGS AND VALVES AS FOLLOWS:
      - 1. APPLY APPROPRIATE TAPE OR THREAD COMPOUND TO EXTERNAL PIPE THREADS.
      - DAMAGED THREADS: DO NOT USE PIPE OR FITTINGS WITH THREADS THAT ARE CORRODED OR DAMAGED.
   D. DISSIMILAR-MATERIAL PIPING JOINTS: MAKE JOINTS USING ADAPTERS COMPATIBLE WITH MATERIALS OF BOTH PIPING SYSTEMS.
3. HANGERS AND SUPPORT INSTALLATION
   A. SUPPORT PIPES THROUGHOUT BUILDING, BOTH HORIZONTALLY AND VERTICAL IN ACCORDANCE WITH REQUIREMENTS HEREIN AND AS SHOWN ON THE DRAWINGS. DO NOT USE FASTENERS WHICH PENETRATE THE ROOF DECK.
   B. PROVIDE COPPER PLATED HANGERS AND SUPPORTS FOR UNINSULATED COPPER PIPING. PROVIDE PLASTIC INSERTS FOR UNINSULATED COPPER PIPING PENETRATING METAL STUDS.
   C. IN AREAS WITHOUT CEILINGS, SECURE INSULATION SHIELDS TO INSULATION WITH PRESSURE SENSITIVE TAPE AT EACH END OF SHIELD. INSTALL HANGERS TO PROVIDE MINIMUM ½" CLEAR SPACE BETWEEN FINISHED COVERING AND ADJACENT WORK.
   D. PLACE A HANGER WITHIN ONE FOOT OF EACH HORIZONTAL ELBOW.
   E. SUPPORT VERTICAL PIPE RUNS AT ROOF, AT FLOOR, AND AT MAXIMUM 15-FOOT INTERVALS.
   F. SPACE SUPPORTS NOT MORE THAN FIVE FEET APART AT VALVES, STRAINERS OR PIPING ACCESSORIES LARGER THAN 2".
   G. INSTALL LATERAL BRACING WITH PIPE HANGERS AND SUPPORTS TO PREVENT SWAYING.
   H. INSTALL HANGERS AND SUPPORTS TO ALLOW CONTROLLED THERMAL AND SEISMIC MOVEMENT OF PIPING SYSTEMS, TO PERMIT FREEDOM OF MOVEMENT BETWEEN PIPE ANCHORS, AND TO FACILITATE ACTION OF EXPANSION JOINTS, EXPANSION LOOPS, EXPANSION BENDS, AND SIMILAR UNITS.
   I. ADJUSTING
      - HANGER ADJUSTMENTS: ADJUST HANGERS TO DISTRIBUTE LOADS EQUALLY ON ATTACHMENTS AND TO ACHIEVE INDICATED SLOPE OF PIPE.
      - LOAD DISTRIBUTION: ADJUST HANGERS AND SUPPORTS SO THAT PIPING LIVE AND DEAD LOADS AND STRESSES FROM MOVEMENT WILL NOT BE TRANSMITTED TO CONNECTED EQUIPMENT.
      - PIPE SLOPES: ADJUST HANGERS AND SUPPORTS TO PROVIDE INDICATED PIPE SLOPES AND TO NOT EXCEED MAXIMUM PIPE DEFLECTIONS ALLOWED BY ASME B31.9 FOR BUILDING SERVICES PIPING.
      - TRIM EXCESS LENGTH OF CONTINUOUS - THREAD HANGER AND SUPPORT RODS TO 1-1/2 ".
4. PIPE INSULATION INSTALLATION
   A. INSULATE FITTINGS AND VALVES WITH PREFORMED INSULATION FITTINGS WITH PVC JACKET.
5. VALVE AND SPECIALTIES INSTALLATION
   A. PROVIDE DEEP SEAL P-TRAPS FOR FLOOR DRAINS AND MOP BASINS.
   B. FOR CLEANOUTS LOCATED IN CONCEALED PIPING, INSTALL CLEANOUT WALL ACCESS COVERS OF TYPES INDICATED, WITH FRAME AND COVER FLUSH WITH FINISHED WALL.
   C. PROTECT DRAINS DURING CONSTRUCTION PERIOD TO AVOID CLOGGING WITH DIRT OR DEBRIS AND TO PREVENT DAMAGE FROM TRAFFIC OR CONSTRUCTION WORK.

GENERAL NOTES:

A. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE PLUMBING SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.

B. CONTRACT DOCUMENT DRAWINGS FOR PLUMBING WORK ARE DIAGRAMMATIC AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY.

C. INSTALL ALL PLUMBING EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS.

D. PROVIDE VIBRATION ISOLATION FOR ALL PLUMBING EQUIPMENT TO PREVENT TRANSMISSION OF VIBRATION TO BUILDING STRUCTURE.

E. PROVIDE VIBRATION ISOLATORS FOR ALL PIPING SUPPORTS CONNECTED TO AND WITHIN 50 FEET OF ISOLATED EQUIPMENT (EXCEPT AT BASE ELBOW SUPPORTS AND ANCHOR POINTS) THROUGHOUT MECHANICAL EQUIPMENT ROOMS. DO THE SAME FOR SUPPORTS OF STEAM MAINS WITHIN 50 FEET OF BOILER OR PRESSURE REDUCING VALVES.

F. PROVIDE VIBRATION ISOLATORS FOR ALL PIPING SUPPORTS OF STEAM MAINS WITHIN 50 FEET OF BOILERS AND PRESSURE REDUCING VALVES.

G. THE LOCATION OF EXISTING UNDERGROUND UTILITIES IS SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL PAY FOR AND REPAIR ALL DAMAGES CAUSED BY FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES UNLESS OTHERWISE INDICATED.

H. COORDINATE CONSTRUCTION OF ALL PLUMBING WORK WITH ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL WORK, ETC., SHOWN ON OTHER CONTRACT DOCUMENT DRAWINGS.

I. ALL TESTS SHALL BE COMPLETED BEFORE ANY PLUMBING EQUIPMENT OR PIPING INSULATION IS APPLIED.

J. LOCATE ALL TEMPERATURE, PRESSURE, AND FLOW MEASURING DEVICES IN ACCESSIBLE LOCATIONS WITH STRAIGHT SECTION OF PIPE AND DOWNSTREAM AS RECOMMENDED BY THE MANUFACTURER FOR GOOD ACCURACY.

K. WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF EQUIPMENT ARE REQUIRED, THE PRODUCT OF ONE MANUFACTURER SHALL BE USED.

L. REINFORCEMENT, DETAILING, AND PLACEMENT OF CONCRETE SHALL CONFORM TO ASTM 315 AND ACI 318. CONCRETE SHALL CONFORM TO ASTM C94. CONCRETE WORK SHALL CONFORM TO ACI 318, PART ENTITLED "CONSTRUCTION REQUIREMENTS." COMPRESSIVE STRENGTH IN 28 DAYS SHALL BE 3,000 PSI. TOTAL AIR CONTENT OF EXTERIOR CONCRETE SHALL BE BETWEEN 5 AND 7 PERCENT BY VOLUME. SLUMP SHALL BE BETWEEN 3 AND 4 INCHES. CONCRETE SHALL BE CURED FOR 7 DAYS AFTER PLACEMENT.

M. COORDINATE ALL EQUIPMENT CONNECTIONS WITH MANUFACTURERS' CERTIFIED DRAWINGS. COORDINATE AND PROVIDE ALL PIPING TRANSITIONS REQUIRED FOR FINAL EQUIPMENT CONNECTIONS TO FURNISHED EQUIPMENT. FIELD VERIFY AND COORDINATE ALL PIPING DIMENSIONS BEFORE FABRICATION.

N. ALL CONTROL WIRE AND CONDUIT SHALL COMPLY WITH THE NATIONAL ELECTRIC CODE AND DIVISION 16 OF THE SPECIFICATION.

O. WHERE BEAMS ARE INDICATED TO BE PENETRATED WITH PIPING, COORDINATE PIPING LAYOUT WITH BEAM OPENING SIZE AND OPENING LOCATIONS. COORDINATION SHALL BE DONE PRIOR TO CUTTING OF PIPING, OR FABRICATION OF BEAMS.

P. THE LOCATIONS OF ALL ITEMS SHOWN ON THE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT DEFINITELY FIXED BY DIMENSIONS ARE APPROXIMATE ONLY. THE EXACT LOCATIONS NECESSARY TO SECURE THE BEST CONDITIONS AND RESULTS MUST BE DETERMINED BY THE PROJECT SITE CONDITIONS AND SHALL HAVE THE APPROVAL OF THE ENGINEER BEFORE BEING INSTALLED. DO NOT SCALE DRAWINGS.

Q. PROVIDE ACCESS PANELS FOR INSTALLATION IN WALLS AND CEILINGS, WHERE REQUIRED, TO SERVICE CONCEALED PLUMBING EQUIPMENT OR VALVES. ACCESS PANELS SHALL BE TURNED OVER TO GENERAL CONTRACTOR FOR INSTALLATION.

R. ALL EQUIPMENT, PIPING, ETC., SHALL BE SUPPORTED AS DETAILED, SPECIFIED, AND REQUIRED TO PROVIDE A VIBRATION FREE INSTALLATION.

S. ALL PIPING AND EQUIPMENT SUPPORTED FROM STRUCTURAL STEEL SHALL BE COORDINATED WITH GENERAL CONTRACTOR. ALL ATTACHMENTS TO STEEL BAR JOISTS, TRUSSES, OR JOIST GIRDERS SHALL BE AT PANEL POINTS. PROVIDE BEAM CLAMPS MEETING MSS STANDARDS. WELDING TO STRUCTURAL MEMBERS SHALL NOT BE PERMITTED. THE USE OF C-CLAMPS SHALL NOT BE PERMITTED.

T. PLUMBING EQUIPMENT AND PIPING SHALL NOT BE SUPPORTED FROM METAL DECK.

U. LOCATIONS AND SIZES OF ALL FLOOR, WALL, AND ROOF OPENINGS SHALL BE COORDINATED WITH ALL OTHER TRADES INVOLVED. ROOF PENETRATIONS AND FLASHING SHALL BE DONE BY THE ROOFING CONTRACTOR.

V. ALL OPENINGS IN FIRE WALLS DUE TO PIPING, CONDUIT, ETC., SHALL BE FIRE STOPPED WITH A PRODUCT SIMILAR TO 3M OR APPROVED EQUAL. REFER TO TYPICAL DETAILS FOR PIPING AND EQUIPMENT INSTALLATION.

PLUMBING NOTES:

A. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE PLUMBING SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.

B. RUN ALL SOIL WASTE AND VENT PIPING WITH 2% MINIMUM GRADE UNLESS OTHERWISE NOTED. HORIZONTAL VENT PIPING SHALL BE GRADED TO DRIP BACK TO THE SOIL OR WASTE PIPE BY GRAVITY.

C. ELEVATIONS AS SHOWN ON THE DRAWINGS ARE TO THE CENTERLINE OF ALL PRESSURE PIPING AND TO THE INVERT OF ALL GRAVITY PIPING.

D. ADJUST SEWER INVERTS TO KEEP TOPS OF PIPE IN LINE WHERE PIPE SIZE CHANGES.

E. MAINTAIN A MINIMUM OF 3'6" OF GROUND COVER OVER ALL UNDERGROUND WATER MAINS AND A MINIMUM OF 3'0" OF GROUND COVER OVER ALL UNDERGROUND SEWERS AND DRAINS.

F. PROVIDE SHUTOFF VALVES IN ALL DOMESTIC WATER PIPING SYSTEM BRANCHES IN WHICH BRANCH PIPING SERVES TWO OR MORE FIXTURES.

G. UNLESS OTHERWISE NOTED, ALL DOMESTIC COLD AND HOT WATER PIPING SHALL BE 1⁄2 INCH SIZE.

H. UNLESS OTHERWISE NOTED, ALL PIPING IS OVERHEAD, TIGHT TO UNDERSIDE OF SLAB, WITH SPACE FOR INSULATION IF REQUIRED.

I. INSTALL PIPING SO THAT ALL VALVES, STRAINERS, UNIONS, TRAPS, FLANGES, AND OTHER APPURTENANCES REQUIRING ACCESS ARE ACCESSIBLE.

J. INSTALL PIPING VALVES FEEDING MULTIPLE FIXTURES AT CONVENIENT CENTRAL LOCATION AND APPROXIMATELY 6"-12" ABOVE FINISHED HARD GYPSUM BOARD CEILINGS FOR EASE OF ACCESS THROUGH SMALLER CEILING ACCESS PANELS.

K. WHERE DOMESTIC COLD AND HOT WATER PIPING DROPS INTO A PIPE CHASE, THE SIZE SHOWN FOR THE PIPE DROPS SHALL BE USED TO THE LAST FIXTURE.

L. INSTALL ALL PIPING WITHOUT FORCING OR SPRINGING.

M. ALL PIPING SHALL CLEAR DOORS AND WINDOWS.

N. ALL PIPING SHALL GRADE TO LOW POINTS. PROVIDE HOSE END DRAIN VALVES AT THE BOTTOM OF ALL RISERS AND LOW POINTS.

O. UNIONS AND/OR FLANGES SHALL BE INSTALLED AT EACH PIECE OF EQUIPMENT, IN BYPASSES, AND IN LONG PIPING RUNS (100 FEET OR MORE) TO PERMIT DISASSEMBLY FOR ALTERATION AND REPAIRS.

P. ALL VALVES SHALL BE ADJUSTED FOR SMOOTH AND EASY OPERATION.

Q. ALL VALVES (EXCEPT CONTROL VALVES) AND STRAINERS SHALL BE FULL SIZE OF PIPE BEFORE REDUCING SIZE TO MAKE CONNECTIONS TO EQUIPMENT AND CONTROLS.

R. PROVIDE CHAINWHEEL OPERATORS FOR ALL VALVES IN EQUIPMENT ROOMS MOUNTED GREATER THAN 7'-0 " ABOVE FLOOR LEVEL; CHAIN SHALL EXTEND TO 7'-0" ABOVE FLOOR LEVEL.

S. PROVIDE ALL PLUMBING FIXTURES AND EQUIPMENT WITH ACCESSIBLE STOPS.

T. UNLESS OTHERWISE NOTED, DRAINS SHALL BE INSTALLED AT THE LOW POINT OF ROOFS, AREAWAYS, FLOORS, ETC.

U. PROVIDE CLEANOUTS IN SANITARY AND STORM DRAINAGE SYSTEMS AT ENDS OF RUNS, AT CHANGES IN DIRECTION, NEAR THE BASE OF STACKS, EVERY 50 FEET IN HORIZONTAL RUNS AND ELSEWHERE AS INDICATED.

V. ALL CLEANOUTS SHALL BE FULL SIZE OF PIPE FOR PIPE SIZES 6 INCHES AND SMALLER AND SHALL BE 6 INCHES FOR PIPE SIZES LARGER THAN 6 INCHES.

W. ALL BALANCING VALVES AND BUTTERFLY VALVES SHALL BE PROVIDED WITH POSITION INDICATORS AND MAXIMUM ADJUSTABLE STOPS (MEMORY STOPS).

X. ALL VALVES SHALL BE INSTALLED SO THAT VALVE REMAINS IN SERVICE WHEN EQUIPMENT OR PIPING ON EQUIPMENT SIDE OF VALVE IS REMOVED.

Y. ALL PIPING WORK SHALL BE COORDINATED WITH ALL TRADES INVOLVED. OFFSETS IN PIPING AROUND OBSTRUCTIONS SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

Z. PROVIDE FLEXIBLE CONNECTIONS IN ALL PIPING SYSTEMS CONNECTED TO PUMPS AND OTHER EQUIPMENT WHICH REQUIRE VIBRATION ISOLATION. FLEXIBLE CONNECTIONS SHALL BE PROVIDED AS CLOSE TO THE EQUIPMENT AS POSSIBLE OR AS INDICATED ON THE DRAWINGS.

AA. PLUMBING CONTRACTOR TO ENSURE THAT VENT STACK ROUTING FOR WALL MOUNTED LAVATORY FIXTURES DO NOT CONFLICT WITH SINK CARRIER INSTALLATION.

DISCLAIMER NOTE: NOT ALL SPECIFICATIONS OR NOTES ON THIS SHEET MAY APPLY TO THIS SPECIFIC PROJECT. REFER TO PROJECT MECHANICAL PLANS FOR SCOPE OF WORK APPLICABLE TO THIS PROJECT.

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:

FIFTH THIRD BANK

Project Number: 26032
Project Name:

FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:

PLUMBING SPECIFICATIONS AND NOTES

Sheet Number:

P-001

6/30/2026 4:55:07 PM