ROOF FRAMING PLAN NOTES

##k BEAM SIZE ##k

ASD REACTION IN KIPS

FRAMING KEY

— · — · — : INDICATES CONTINUOUS HORIZONTAL RIGID BRACING AT TOP AND BOTTOM CHORD OF JOIST. ADD "X" TYPE BRIDGING IN FIRST PANEL AND AT EVERY SIXTH PANEL. WELD TO JOIST, FRAMING, AND AT CROSSOVER POINTS. SEE SPECIFICATIONS.

: INDICATES THE DIRECTION THE DECK IS SPANNING.

±FORCE (KIPS) INDICATES COLLECTOR ELEMENT FORCE IN JOIST OR BEAM.

#.#k INDICATES LOAD ON JOIST FROM HOSE REEL, FOR SUPPORT DETAILS SEE: 9 / zS686

INDICATES A MOMENT CONNECTION AT EACH END OF BEAM TO COLUMN. SEE TYPICAL DETAIL FOR FULL PENETRATION WELD OF FLANGES AT EACH END. SEE DETAIL 3 / S-682

H.B. : INDICATES ANGLE 3"x3"x1/4" HORIZONTAL BRACE EXTENDING FROM TOP CHORD OF JOIST OR BEAM TO FACE OF COLUMN. WELD ALL AROUND EACH END WITH A 3/16" FILLET WELD.

A.X. : INDICATES ADDITIONAL "X" TYPE BRIDGING. USE 2"x2"x1/4" ANGLE

S.J. : INDICATES A STRUT JOIST, SEE SPECIFICATIONS.

S.P. : INDICATES A BEAM SPLICE POINT, SEE TYPICAL SPLICE POINT DETAIL9 / S-681

NOTE: WHERE STEEL FRAMING IS USED FOR LATERAL RESISTANCE, SEE STEEL FRAMING ELEVATIONS. FOR WORK POINT AND CONNECTION DETAILS AT BRACING AND KNEE BRACING, SEE DETAILS 1 / S-301 AND 3 / S-301

NOTE: AFTER ALL ROOF DEAD LOAD HAS BEEN INSTALLED, PROVIDE ANGLE BRACES, OR TENSION RODS AS NOTED IN "TYPICAL BAR JOIST ROOF CONSTRUCTION" SEE DETAIL 4 / S-682

NOTE: WHERE CONDENSING UNITS BEAR ON ROOF STRUCTURE, PROVIDE A SUPPORT FRAME SIMILAR TO A ROOF OPENING SUPPORT AT THE PERIMETER OF THE UNIT. PROVIDE ANGLES AS SHOWN IN DETAIL 10 / S-681

NOTE : WHERE TUBE FRAME MEMBERS CONNECT TO COLUMNS, PROVIDE A WELDED CONNECTION ALL AROUND FROM TUBE TO COLUMN, TYP.

NOTE: STEEL REINF. TO BE WELDED SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-706 AND THAT WELDING SHALL BE IN ACCORDANCE WITH AWS D1.4, STRUCTURAL WELDING CODE - REINFORCING STEEL BY AMERICAN WELDING SOCIETY FOR COMPLIANCE WITH ACI 318.

NOTE: FOR FRAMING AROUND ROOF HATCH, PROVIDE CHANNEL FRAMING AS SHOWN ON THE TYPICAL DETAIL FOR FRAMING AROUND MECHANICAL UNITS. (UNLESS NOTED OTHERWISE)

NOTE: KEEP STRUCTURE GUYED AND BRACED UNTIL ALL MASONRY/CONCRETE SHEAR WALLS, DIAGONAL BRACES, MOMENT FRAMES, FRAMED FLOORS AND ROOF DECKS ARE IN PLACE.

NOTE: SEE ARCHITECT AND PLUMBING DRAWINGS FOR LOCATIONS OF ROOF DRAINS. ROOF IS DESIGNED FOR A MAXIMUM DEPTH OF 4" OF WATER AT ANY LOCATION OF THE ROOF. WATER SHALL BE RELIEVED BY EITHER SCUPPERS OR AN INDEPENDENT EMERGENCY OVERFLOW DRAIN AT THE 4" LEVEL.

NOTE: FOR FRAMING AROUND THE PERIMETER OF A MECHANICAL UNIT, SEE TYPICAL DETAIL: 3 / S-681

NOTE: FOR FRAMING AROUND ROOF OPENINGS INCLUDING EXHAUST FANS, ROOF DRAINS AND ANY PENETRATIONS LARGER THAN 12", SEE TYPICAL DETAIL: 10 / S-681


NOTE: CONTRACTOR COORDINATE LOCATION OF OPENINGS AND WEIGHTS OF MECHANICAL UNITS, WITH THE MECHANICAL DRAWINGS. IF WEIGHTS EXCEED WHAT IS SHOWN ON THE STRUCTURAL PLAN, THEN NOTIFY THE STRUCTURAL ENGINEER OF THE CHANGE PRIOR TO ANY DETAILING OR FABRICATION OF JOIST, DECK OR STEEL.

NOTE: AT PERIMETER OF ALL ROOFS, EXPANSION JOINTS, AND TRANSITIONS FROM HIGH TO LOW ROOFS, PROVIDE ROOF CLOSURE ANGLES AS PER SECTIONS DETAILED. WHERE NOT SHOWN, PROVIDE A 4" x 3" x 1/4" CONT. ANGLE LONG LEG VERTICAL. WHERE ANGLE BEARS ON JOIST SEATS, FIELD WELD TO EACH JOIST WITH A 3/16" FILLET WELD. WHERE ANGLE BEARS ON A ROOF BEAM, FIELD WELD WITH A 3/16" FILLET WELD 2" at 12" o.c. MAX.

NOTE: FOR SUPPORT OF ROOF PIPING PERPENDICULAR TO JOIST, AND PARALLEL TO JOIST, SEE DETAIL - / ---


SLAB AND DECK SCHEDULE

MARK	DESCRIPTION
RD-1.5	DECK: 1-1/2" WIDE RIB TYPE B GAUGE: 22 (t = 0.0295") FINISH: GALVANIZED (G90) GRADE: 50 ksi FASTENER TYPE AT SUPPORT: 5/8" Ø PUDDLE WELDS WITH WELDING WASHERS END SUPPORT ATTACHMENT PATTERN: 36/4 INTERMEDIATE SUPPORT ATTACHMENT PATTERN: 36/4 PERIMETER SUPPORT ATTACHMENT PATTERN: 12" o.c. MAX. SIDE LAP FASTENER: #10 TEK SCREWS @ 18" o.c. MAX. MINIMUM END LAP = 4" (AT SUPPORTS ONLY)
SOG-4	4" CONCRETE SLAB ON A VAPOR RETARDER ON A GRAVEL BED OR SAND CUSHION AS RECOMMENDED BY THE GEOTECHNICAL REPORT. REINFORCE SLAB WITH WELDED WIRE FABRIC 6/6-W2.9xW2.9 IN FLAT SHEETS. FINISH FLOOR SLAB ELEVATION SEE CIVIL FOR DATUM




2 / S-203 Frame Elevation

3/16" = 1'-0"



3 / S-203 Frame Elevation

3/16" = 1'-0"



1 / S-203 Roof Framing Plan

1/4" = 1'-0"

Gridline Type Legend

NEW GRIDLINE

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
404-876-8884 fax
www.praxis3.com

GEORGIA REGISTERED No. SE001277 STRUCTURAL ENGINEER MARK W. NANNIS

Copyright © 2026 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
1	07/02/2026	PERMIT SET

MARK NANNIS STRUCTURAL ENGINEERS

Mark Nannis Structural Engineers

2060 Buford Highway NE, Suite 106
Buford, GA 30518

All drawings, specifications, and other work product of Mark Nannis Structural Engineers (henceforth referred to as "The Engineer") for this project are instruments of service for this project only and shall remain the property of The Engineer whether the project is complete or not. Reuse of any of the instruments of service of The Engineer by the owner or extensions of this project without the written permission of The Engineer shall be at the owner's risk and the owner agrees to defend, indemnify, and hold harmless The Engineer from all claims, damages, and expenses including attorney's fees arising out of such unauthorized reuse of The Engineer's instruments of service by the owner or others acting through the owner.
© 2026

Client:

FIFTH THIRD BANK

Project Number: 26302
Project Name:

WATSON BLVD.

2711 WATSON BOULEVARD
WARNER ROBINS, GA 31093

Sheet Title:

Structural Plan - Roof

Sheet Number:

S-203

RELEASED FOR CONSTRUCTION/ AND PERMIT

6/26/2026 12:52:19 PM