

4 E-704 ELEVATION PHONE ROOM 114/1
1/4" = 1'-0"



3 E-704 ELEVATION MENS 113/2
1/4" = 1'-0"



2 E-704 ELEVATION MENS 113/1
1/4" = 1'-0"



1 E-704 ELEVATION WOMENS 112/1
1/4" = 1'-0"



8 E-704 ELEVATION JANITOR 115/2
1/4" = 1'-0"

7 E-704 ELEVATION JANITOR 115/1
1/4" = 1'-0"



6 E-704 ELEVATION PHONE ROOM 114/3
1/4" = 1'-0"



5 E-704 ELEVATION PHONE ROOM 114/2
1/4" = 1'-0"



11 E-704 ELEVATION VESTIBULE 116/3
1/4" = 1'-0"



10 E-704 ELEVATION VESTIBULE 116/2
1/4" = 1'-0"



9 E-704 ELEVATION VESTIBULE 116/1
1/4" = 1'-0"

DISCONNECT SWITCH 1.0 EA

2026 2:32:21 PM

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 041504 PROFESSIONAL ENGINEER RAHN ONEAL WILLIAMS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
ELECTRICAL ELEVATIONS

Sheet Number:
E-704

MINIMUM DUCT INSULATION R-VALUES:

LOCATION (1)	SUPPLY DUCT	RETURN DUCT
EXTERIOR OF BUILDING	R-8	R-12
VENTILATED ATTIC	R-8	R-8
UNVENTED ATTIC ABOVE INSULATED CEILING	R-6	R-6
UNVENTED ATTIC WITH ROOF INSULATION	R-8	R-12
UNCONDITIONED SPACES (2)	R-6	R-6
INDIRECTLY CONDITIONED SPACES (3)	R-6	R-6
CONDITIONED SPACES	NONE	NONE

NOTES:

(1) INCLUDES RETURN AIR PLENUMS WITH OR WITHOUT EXPOSED ROOFS ABOVE.

(2) INCLUDES CRAWL SPACES, BOTH VENTILATED AND NON-VENTILATED.

(3) THIS TABLE APPLIES TO COMMERCIAL HVAC SYSTEMS ONLY AND INCLUDES BOTH SUPPLY AND RETURN DUCTS.

(4) MINIMUM INSULATION VALUES ARE BASED ON IECC C403 AND ASHRAE 90.1, AS ADOPTED BY THE AUTHORITY HAVING JURISDICTION.

EQUIPMENT ROOF STAND HEIGHTS:

MOUNTED MECHANICAL UNITS					
WIDTH OF MECHANICAL UNIT (IN)	< 24	25-36	47-48	49-60	> 60
MINIMUM CLEARANCE ABOVE SURFACE	14	18	24	30	48

NOTES:

ROOF MOUNTED MECHANICAL UNITS SHALL BE MOUNTED ON CURBS RAISED A MINIMUM OF 8 INCHES ABOVE THE ROOF SURFACE OR WHERE ROOFING MATERIALS EXTEND BENEATH THE UNIT, ON RAISED EQUIPMENT SUPPORTS PROVIDING A MINIMUM CLEARANCE HEIGHT IN ACCORDANCE WITH TABLE THE TABLE PROVIDED.

MECHANICAL CONTROLS & ACCESSORIES

GENERAL CONTROLS REQUIREMENTS (ALL EQUIPMENT)

MECHANICAL CONTRACTOR(MC) SHALL PROVIDE TEMPORARY DIGITAL THERMOSTATS AS REQUIRED FOR EQUIPMENT START-UP AND INITIAL OPERATION. IOT SHALL FURNISH AND INSTALL ALL PERMANENT KMC CONTROLS AND COMPLETE BMS INTEGRATION AFTER EQUIPMENT START-UP AND PRIOR TO FINAL COMMISIONING.

MOUNT ALL THERMOSTATS AND SENSORS AT 44" AFF TO CENTER LINE OF VERTICAL DEVICE UNLESS NOTED OTHERWISE. COORDINATE FINAL DEVICE COLOR AND FINISH WITH ARCHITECT.

MC SHALL CORDINATE ALL REQUIRED CONTROL WIRING, POWER, INTERFACES, AND ACCESSORIES NECESSARY FOR FULLY FUNCTIONAL AND COMMISSIONED SYSTEM OPERATION.

RTU CONTROLS (CARRIER UNITS)

PERMANENT THERMOSTAT: KMC FLEXSTAT BAC-120063CW
(PURCHASED AND INSTALLED BY IOT)

MONITORING SENSOR: KMC APPROVED SENSORS
(PURCHASED AND INSTALLED BY IOT)

RTU'S TO USE TEMPORARY THERMOSTATS UNTIL THE PERMANENT KMC BRANDED FLEXSTATS WITH BMS INTEGRATION ARE INSTALLED AND COMMISSIONED. UPON CHANGEOVER, TEMPORARY THERMOSTATS SHALL BE REMOVED AND RETURNED TO MC.

RTU ACCESSORIES NOTE:
MECHANICAL CONTRACTOR TO PROVIDE ROOFTOP UNIT WITH THE FOLLOWING ACCESSORIES:

FIELD INSTALLED

1. WALL MOUNTED CO2 SENSOR (PART NO: 33ZCSPTC02-01)
2. RETURN ENTHALPY SENSOR KIT (PART NO: CRENTSEN001A00)
3. OUTDOOR ENTHALPY SENSOR KIT (PART NO: CRENTSEN001A00)
4. WIFI STICK FOR ECONOMIZERS (PART NO: CRWFTCK001A00)

FACTORY INSTALLED

5. ECONOMIZER CONTROLLER (SIEMENS POL224)
6. ACTUATOR (PART NO: HF23BL005)
7. POWER HARNESS (PART NO: 48TC005897)
8. SUPPLY AIR SENSOR (PART NO: HH79NZ039)

FCU THERMOSTAT NOTE:
MECHANICAL CONTRACTOR TO PROVIDE AND INSTALL THERMOSTAT WITH INTERFACE. IOT WILL SUPPLY KMC CONTROLS AND COMPLETE BMS INTEGRATION AFTER EQUIPMENT STARTUP.

THERMOSTAT INTERFACE ADAPTERS (BY MC AS REQUIRED)

- MITSUBISHI / TRANE THERMOSTAT INTERFACE: PAC-US445CN-1
- CARRIER THERMOSTAT INTERFACE: KSAIC0301230
  (EC MAY BE REQUIRED FOR HIGH VOLTAGE WIRING)

SPLIT SYSTEMS SHALL UTILIZE KMC FLEXSTAT WITH BMS INTEGRATION. MINI-SPLITS SHALL UTILIZE OEM-APPROVED THERMOSTAT INTERFACE ADAPTER WITH KMC FLEXSTAT FOR BMS INTEGRATION.

PACKAGED ROOFTOP HEAT PUMP AIR HANDLING UNIT SCHEDULE: GC PROVIDED

MARK	AREA SERVED	MFG.	MODEL	ROOM TEMP	NOMINAL SIZE	SUPPLY AIR FLOW (CFM)	MINIMUM OUTDOOR AIR FLOW (CFM)	FILTER TYPE	EXT S.P. (IN W.C.)	FAN MOTOR		COOLING CAPACITY				HEATING CAPACITY			ELECTRICAL				WEIGHT (LBS)	SEER
										RPM	MOTOR BPH	TOTAL CAPACITY	SENSIBLE CAPACITY	ENTERING AIR (° FDB/°FWB)	MEDIA	HEAT SOURCE	STAGES	MBH	VOLT	PH	HZ	MCA/MOCP (W/ HEAT)		
RTU-1	ENTRY/MEETING	CARRIER	48FEDA05J3M5-8W4D0	75° F	4.0	1,600	--	MERV 13	1.0	--	0.91	52.33 MBH	37.66 MBH	80/67	R-454B	NATURAL GAS	1	67	208V	3	60	24/30	797	14.0
RTU-2	SEATING/LOUNGE	CARRIER	48FEDA05J3M5-8W4D0	75° F	4.0	1600	--	MERV 13	1.0	--	0.91	52.33 MBH	37.66 MBH	80/67	R-454B	NATURAL GAS	1	67	208V	3	60	24/30	797	14.0

SCHEDULE NOTES:
ACCEPTABLE MANUFACTURERS INCLUDE CARRIER (BOD), TRANE, AND DAIKIN GIVEN COMPARABLE MODEL IS SELECTED. FIELD INSTALLED ACCESSORIES ARE ALSO ACCEPTABLE. CONTACT EMAIL FOR CARRIER REPRESENTATIVE: NATIONALACCOUNTS@CARRIER.COM.

1. PROVIDE 18" FACTORY INSULATED ROOF CURB. ROOF CURB TO BE PITCHED 1/4" PER FOOT ACCORDING TO ROOF SLOPE. SHEET METAL CONTRACTOR SHALL PROVIDE EXTENDED ROOF CURB FOR ROUTING OF DUCTWORK WITHIN CURB TO A SINGLE ROOF OPENING, CONFIRM WITH STRUCTURAL THAT DISCHARGE DUCT OPENING IN THE BOTTOM OF THE UNIT FITS BETWEEN THE JOISTS.
2. PROVIDE RTU WITH VERTICAL SUPPLY AND RETURN AIR CONNECTIONS AND DRAW THRU CONFIGURATION WITH STAINLESS STEEL DRAIN PAN.
3. INCLUDE UNIT WITH THE FOLLOWING; REFERENCE ENTHALPY CONTROLLED ECONOMIZER WITH LOW LEAKAGE DAMPERS, BAROMETRIC RELIEF DAMPER, AND OUTSIDE AIR SYSTEM INTAKE HOOD WITH AUTOMATIC DAMPER. EVAPORATOR FAN TO BE DIRECT DRIVE.
4. FURNISH FUSED DISCONNECT FOR INSTALLATION BY ELECTRICAL CONTRACTOR. PROVIDE THROUGH-THE-BASE ELECTRICAL DISCONNECT SWITCH WITH UNPOWERED CONVENIENCE OUTLET ON UNIT. INCLUDE UNIT AUTO RESET PHASE MONITOR.
5. PROVIDE TWO (2) SETS OF 2" MERV 13 CARTRIDGE FILTERS WITH EACH UNIT.
6. PROVIDE FACTORY SEACOAST SPRAY PROTECTION ON UNIT FOR ANY PROJECT LOCATION WITHIN 20 MILES OF A COASTLINE.
7. PROVIDE FACTORY INSTALLED BURGLAR BARS, CONDENSER COIL GUARD, AND EXTERNAL HAIL GUARDS.
8. PROVIDE WITH HURRICANE TIE DOWNS AND REFER TO ENGINEERED WIND LOAD MITIGATION CALCULATIONS.
9. PROVIDE UNITS WITH COIL CONFIGURATION HEAT THEN COOL, COIL LEAVING AIR TEMPERATURES TO BE NO LESS THAN 55°F. UNIT SELECTION SHALL BE BASED ON OUTSIDE AIR TEMPERATURE OF 110°F IN CLIMATE ZONES 1A-2A, ALL OTHER ZONES TO HAVE NET COOLING CAPACITY OF 95°F AMBIENT. HEAD PRESSURE CONTROL TO 0°F AMBIENT.
10. UNIT MOUNTED SIEMENS POL224 ECONOMIZER CONTROLLER. TEMPORARY THERMOSTATS SHALL BE DIGITAL THERMOSTATS FOR START UP THEN REPLACED BY IOT WITH FIFTH THIRD BMS KMC FLEXSTAT. TEMPORARY THERMOSTATS SHALL BE RETURNED TO MC UPON COMPLETION OF THE CONTROLS INSTALLATION. MONITORING SENSORS SHALL BE PROVIDED BY IOT AND INSTALLED BY MC.
11. ALL HVAC SYSTEM CONTROLS SHALL BE SELECTED TO BE COMPATIBLE WITH BMS CONTROL SYSTEM. MECHANICAL CONTRACTOR AND HVAC SYSTEM SUPPLIER SHALL CONFIRM WITH CONTROLS VENDOR TO ENSURE FULL COMPATIBILITY FOR ALL HVAC EQUIPMENT PRIOR TO ORDERING/PURCHASE.
12. PROVIDE DUCT SMOKE DETECTORS IN RETURN AND SUPPLY MAIN DUCT FOR ANY UNITS PROVIDING AT/OVER 2,000CFM OF AIRFLOW.
13. DEMAND CONTROL VENTILATION (DCV) WITH SPACE CO2 SENSOR FROM HVAC EQUIPMENT MANUFACTURER.
14. UNIT SHALL BE ASHRAE 90.1 COMPLIANT.
15. RTU'S TO BE PURCHASED WITH THE ELECTRO-MECHANICAL CONTROLS AND ULTRA LOW LEAK ECONOMIZER WITH BAROMETRIC RELIEF. REFER TO RTU ACCESSORIES NOTE FOR ADDITIONAL INFORMATION.
16. PROVIDE 2" DOUBLE WALL CONSTRUCTION FOR R-13 THERMAL RESISTANCE INCLUDING THE BOTTOM PANEL WITH HINGED ACCESS DOORS.
17. RTU TO COME WITH CONDENSATE OVERFLOW SWITCH - THIS SENSOR AND RELATED CONTROLLER MONITORS THE CONDENSATE LEVEL IN THE DRAIN PAN AND SHUTS DOWN COMPRESSION OPERATION WHEN OVERFLOW CONDITIONS OCCUR. IT INCLUDES:
    - INDICATOR LIGHT - SOLID RED (MORE THAN 10 SECONDS ON WATER CONTACT - COMPRESSORS DISABLED), BLINKING RED (SENSOR DISCONNECTED)
    - 10-SECOND DELAY TO BREAK - ELIMINATES NUISANCE TRIPS FROM SPLASHING OR WAVES IN PAN (SENSOR NEEDS 10 SECONDS OF CONSTANT WATER CONTACT BEFORE TRIPPING)
    - DISABLES THE COMPRESSORS OPERATION WHEN CONDENSATE PLUG IS DETECTED, BUT STILL ALLOWS FANS TO RUN FOR ECONOMIZER.
18. MECHANICAL CONTRACTOR TO NOTIFY IOT IF RTU UNITS ARE NOT EQUIPPED WITH SYSTEM VU CONTROLS. CONTACT GERRIANNE FAULHABER: GERRIANNE@IOFTEAM.COM, 224-213-6908.

MINI-SPLIT SYSTEM AIR CONDITIONER SCHEDULE: GC PROVIDED

MARK		SYSTEM ZONE	MFG.	INDOOR UNIT			OUTDOOR UNIT			COOLING				HEATING			ELECTRICAL				PHYSICAL	
INDOOR UNIT	OUTDOOR UNIT			MODEL NUMBER	MOUNTING	FAN AIRLOW	MODEL NUMBER	SYSTEM TYPE	REFR. TYPE	RATED CAPACITY (BTU/H)	MINIMAL CAPACITY (BTU/H)	SEER	EER	RATED CAPACITY (BTU/H)	MINIMAL CAPACITY (BTU/H)	HSPF	VOLT/PH/HZ	UNIT MCA		MOCP	INDOOR UNIT WEIGHT	OUTDOOR UNIT WEIGHT
																		INDOOR	OUTDOOR			
FCU-1	HP-1	ELECTRICAL / IT ROOM	MITSUBISHI	PKA-A12LNL	WALL MOUNT	385 CFM	PUZ-A12NL	HEAT PUMP	R-454B	12,200	4,300	21.1	14.8	18,000	4,300	10.1	208 / 230V, 1-PHASE, 60HZ	1 A	16 A	27 A	28 LBS	99.21 LBS

SCHEDULE NOTES:
NO ALTERNATIVE MANUFACTURERS OR MODEL NUMBERS ARE ACCEPTABLE. FIFTH THIRD BANK HAS A NATIONAL ACCOUNT AGREEMENT WITH THE TRANE COMPANY. FOR COMPLETE INFORMATION ON THE FOLLOWING EQUIPMENT PACKAGE PLEASE CONTACT TRANE NATIONAL ACCOUNTS: DANIEL SWEGLE AT DANIEL.SWEGLE@TRANE.COM / 636-875-6616.

1. INDOOR UNITS RECEIVE POWER FROM OUTDOOR UNITS THROUGH FIELD-SUPPLIED INTERCONNECTED WIRING. COORDINATE FINAL UNIT INSTALLATION LOCATION WITH STRUCTURAL CONDITIONS.
2. PROVIDE GRAVITY CONDENSATE DRAIN WHERE 1/4" PER FOOT SLOPE IS ACHIEVABLE. WHERE NOT ACHIEVABLE FOR WALL-MOUNTED UNITS, PROVIDE LITTLE GIANT VCMA-15ULST CONDENSATE PUMP WIRED FOR HIGH-WATER SHUTDOWN. DUCTED PEAD UNITS SHALL USE FACTORY CONDENSATE LIFT AND INTERNAL SAFETY; NO ADDITIONAL ACCESSORIES REQUIRED UNLESS LIFT EXCEEDS 27".
3. ZONES FED BY THIS SYSTEM ARE NON-OCCUPIABLE OR ARE NATURALLY VENTILATED.
4. PROVIDE WITH MITSUBISHI PAC-US445CN-1 HARD WIRED BACK-LIT MA REMOTE CONTROLLER. COMPONENTS TO HAVE BACNET INTERFACE AND INTERLOCK WITH BMS, PROVIDE CONTROL WIRING DIAGRAM FOR ENGINEER REVIEW.
5. PROVIDE FACTORY SEACOAST SPRAY PROTECTION ON UNIT FOR ANY PROJECT LOCATIONS WITHIN 20 MILES OF A COASTLINE.
6. REFRIGERANT CIRCUIT ACCESS PORTS LOCATED OUTDOORS SHALL BE FITTED WITH LOCKING TYPE TAMPER RESISTANT CAPS.
7. MOUNT OUTDOOR UNIT ON MINIMUM 18" HIGH NONISOLATED WIND AND SEISMIC RESTRAINT RAILS.BASIS OF DESIGN; VMC GROUP MODEL #R-7000.
8. HANG INDOOR WALL MOUNTED UNIT TO SECURE WALL STRUCTURE PER MANUFACTERE RECOMMENDATIONS (REFER TO INSTALLATION DETAIL).
9. PROVIDE FULL PORT BALL VALVES & SCHRADER VALVES WITH FLARED CONNECTIONS ON INDOOR WALL UNIT.
10. PROVIDE DRAIN PAN WITH UL#508 APPROVED WATER DETECTION SENSOR FOR UNIT SHUTDOWN. WIRE CONTROL CIRCUIT THROUGH NC CONTACT.
11. COOLING CAPACITY RATED AT 95°F AND HEATING CAPACITY RATED AT 17°F.
12. 100% HEATING CAPACITY AT 5°F AND HEATING PERFORMANCE, DOWN TO -13°F WITH AVERAGE OF 80% CAPACITY.
13. ELECTRICAL CONTRACTOR TO INCLUDE AND INSTALL 3-POLE DISCONNECT SWITCH.
14. MECHANICAL CONTRACTOR TO NOTIFY IOT IF DIFFERENT SPLIT SYSTEM IS PROVIDED. CONTACT GERRIANNE FAULHABER: GERRIANNE@IOFTEAM.COM, 224-213-6908.

DUCT SIZING GUIDE

SUPPLY DUCT (0.08SP)				RETURN DUCT (0.05SP)			
ROUND DUCT		RECTANGULAR DUCT		ROUND DUCT		RECTANGULAR DUCT	
CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)	CFM RANGE	SIZE (IN)
1-100	6	1-125	6X6	1-75	6	1-100	6X6
101-210	8	126-260	8X8	76-160	8	101-200	8X8
211-395	10	261-470	10X10	161-290	10	201-365	10X10
396-625	12	471-760	12X12	291-470	12	366-595	12X12
626-910	14	761-1,145	14X14	471-710	14	596-895	14X14
911-1,300	16	1,146-1,635	16X16	711-1,010	16	896-1,275	16X16
1,301-1,800	18	1,636-2,235	18X18	1,011-1,375	18	1,276-1,745	18X18
1,801-2,325	20	2,236-2,955	20X20	1,376-1,815	20	1,746-2,310	20X20

NOTES:

1. FOR RECOMMENDED SQUARE SIZE DUCT AN APPROXIMATE EQUIVALENT RECTANGULAR CROSS SECTIONAL AREA IS ALSO ACCEPTABLE FOR ALTERNATIVE RECTANGULAR DUCT DIMENSIONS. DO NOT EXCEED A 3:1 DIMENSION RATIO.
2. ROUND AND SQUARE DUCT DIMENSIONS HAVE BEEN SIZED BASED ON 0.08 INCHES OF FRICTION HEAD LOSS FOR SUPPLY DUCT AND 0.05 FOR RETURN DUCT.

AIR DISTRIBUTION SCHEDULE

MARK	NECK SIZE	MAX CFM	DESCRIPTION
S (CFM)	6"ø	0-90	FACE SIZE SHALL BE 12X12 (SEE BELOW FOR REMAINING NOTES)
	6"ø	0-100	ARCHITECTURAL SQUARE PANEL CEILING SUPPLY AIR DIFFUSER - STEEL CONSTRUCTION, MODULE SIZE 24X24, CURVED BACK-PAN DESIGN AND ROUND DUCT CONNECTIONS, PROVIDE ROUND RUN-OUTS AS INDICATED BELOW, TITUS D-OMNI-1 (BORDER TYPE 3; LAY-IN FULL FACE FLAT T-BAR CEILING GRID) COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. COORDINATE LOCATIONS WITH LIGHTING DO NOT SCALE FROM MECHANICAL DRAWINGS
	8"ø	101-210	
	10"ø	211-330	
	12"ø	331-480	
	14"ø	481-650	
LSD (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT SUPPLY CEILING DIFFUSER WITH 1" SLOT, 4'-0" LONG WITH INSULATED PLENUM BOX, END BORDERS, AND FACE OPERATED REMOTE DAMPER AT PLENUM INLET. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
LSR (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT RETURN CEILING DIFFUSER, 4'-0" LONG, WITH NO PATTERN CONTROLLER, FOR RETURN AIR DUTY. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
LD (X)	(X) NUMBER OF 1" SLOTS		MODULINEAR SLOT SUPPLY CEILING DIFFUSER, 2'-0" LONG WITH INSULATED PLENUM BOX, END BORDERS, AND FACE OPERATED REMOTE DAMPER AT PLENUM INLET. COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. DESIGN MAKE; TITUS MLTI-39, PROVIDE WITH INSULATED PLENUM BOX.
R (CFM) TR (CFM)	10" X10"	0-400	EGGCRATE RETURN AIR GRILLE - CORE OF 1/2"X1/2"X1" ALUMINUM GRID, TYPICAL PANEL SIZE; 12X12, 24X12, 24X24, AND 24X8. ALL CEILING RETURN, EXHAUST, TRANSFER GRILLES TO BE TITUS 50F (BORDER TYPE 3; LAY-IN FULL FACE FLAT T-BAR CEILING GRID) COORDINATE CEILING TYPE WITH ARCHITECTURAL RCP. SIZE AS INDICATED IN TABLE (PROVIDE SQUARE TO ROUND TRANSITION AS NEEDED). COORDINATE LOCATIONS WITH LIGHTING DO NOT SCALE FROM MECHANICAL DRAWINGS
	22" X 10"	401-800	
	22" X 22"	801-2,000	
	22" X 46"	2,001-4,000	

NOTES:

1. FURNISH WITH STANDARD WHITE BAKED ENAMEL FINISH (#26 WHITE). SUBMIT COLOR SAMPLE FOR ALL AIR DEVICES TO ARCHITECT BEFORE ORDERING.
2. FURNISH "RAPID-MOUNT" FRAMES FOR S-1 & R-1 DEVICES LOCATED IN DRYWALL CEILINGS. COORDINATE MOUNTING FRAME WITH CEILING/WALL TYPE.
3. PROVIDE 120/240 VAC TRANSFORMER POWER MODULE, CONTROLLER/THERMOSTAT AND PRESSURE RELIEF RING FOR ALL VAV DIFFUSERS.
4. SIZE FOR MAXIMUM NOISE CRITERION <30 FOR DIFFUSERS, REGISTERS, AND GRILLES.
5. PROVIDE DIRECTIONAL BLOW CLIPS WHERE REQUIRED OR DIRECTIONAL NECK BAFFLES WHERE INDICATED FOR BLOCKED AIRFLOW.
6. PROVIDE REMOTE CABLE OPERATED VOLUME DAMPERS LOCATED IN INACCESSIBLE CEILING/WALL CONSTRUCTION.

* BASIS OF DESIGN PRODUCTS ARE INDICATED FOR REFERENCE ONLY. COMPARABLE PRODUCTS WILL BE ACCEPTED PROVIDED COMPLIANCE WITH TECHNICAL SPECIFICATION REQUIREMENTS. ACCEPTABLE MANUFACTURERS SHALL BE PRICE, TITUS, ANEMOSTAT AND KRUEGER.

EXHAUST FAN SCHEDULE: GC PROVIDED

MARK	AREA SERVED	PRODUCT		MOUNTING TYPE	CFM	EXT S.P. (IN W.C.)	MOTOR DATA				NOTES
		MANUFACTURER	MODEL				RPM	TYPE	VOLT/PH/HZ	WATTS	
EF-1	JANITOR'S CLOSET	GREENHECK	SP-B90	CEILING	55	0.33	889	FSC	120/1/60	17 W	(1)(2)(4)(5)(6)
EF-2	MEN'S RESTROOM	GREENHECK	SP-B110	CEILING	80	0.33	650	FSC	120/1/60	30 W	(1)(2)(3)(4)(5)(6)
EF-3	WOMEN'S RESTROOM	GREENHECK	SP-B110	CEILING	80	0.33	650	FSC	120/1/60	30 W	(1)(2)(3)(4)(5)(6)

NOTES:

(1) ACCEPTABLE MANUFACTURERS: LOREN COOK, GREENHECK, OR CAPTIVEAIRE AND MUST MEET EQUIVALENT CHARACTERISTICS.

(2) PROVIDE FANS WITH FSC SPEED CONTROLLER (5A-120V), LOCATE WITHIN ACCESSIBLE LOCATION.

(3) EXHAUST FAN SHALL BE INTERLOCKED WITH LOCAL LIGHTING THAT TURN ON DURING ROOM SENSOR OCCUPIED MODE (COORDINATE WITH EC).

(4) PROVIDE FANS WITH THE FOLLOWING: TYPICAL DISCONNECT SWITCH, INTEGRAL GRAVITY BACKDRAFT DAMPER, AND HANGING ISOLATOR KIT.

(5) PURCHASE FANS WITH ALUMINUM CEILING GRILLE IF STANDARD IS PLASTIC.

(6) PROVIDE MOUNTING FRAME FOR GYPSUM BOARD CEILING.

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303

404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON
1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
MECHANICAL SCHEDULES

Sheet Number:
M-101

6/30/2026 4:54:52 PM



1 M-301 FLOOR PLAN - MECHANICAL
1/4" = 1'-0"

MECHANICAL KEY NOTES
(APPLIES TO THIS SHEET ONLY)

1. REFRIGERANT PIPING UP THRU ROOF TO OUTDOOR UNIT.
2. ROUTE REFRIGERANT PIPING AS HIGH AS POSSIBLE TO OUTDOOR UNIT ON ROOF. ROUTE AND SIZE PER MANUFACTURER'S RECOMMENDATIONS (TYP.).
3. DUCT UP AND TRANSITION TO MATCH FULL UNIT OPENING. PROVIDE FLEXIBLE CONNECTION AT UNIT. INSTALL LONG-RADIUS SWEEP ELBOW AT DUCT DROP WHERE SPACE PERMITS; OTHERWISE, PROVIDE SHORT-RADIUS ELBOW WITH TURNING VANES.
4. DUCT TO RISE ABOVE STRUCTURAL BEAM. COORDINATE WITH STRUCTURAL.
5. IN UPPER CEILING. PAINT BLACK.
6. PROVIDE REMOTE CABLE OPERATED DAMPER IN PLENUM SLOTS WITH OPERATION AT SLOT FACE.
7. PROVIDE REMOTE CABLE OPERATED DAMPER IN CEILING FOR DAMPER OPERATION.
8. LSR(3) WITH FULL SIZE SHEETMETAL PLENUM, 12" HIGH. INSIDE TO BE PAINTED FLAT BLACK. CONNECT TO DUCT TO PLENUM BOX.
9. SUPPLY DIFFUSER TO BE VAV TYPE WITH PETROLEUM BASED WAX CONTROLLED DAMPER. DAMPER SHALL CLOSE TO KEEP SPACE FROM BEING OVERHEATED ONCE ROOM TEMPERATURE IS SATISFIED (72°F ADJUSTABLE). DIFFUSER EQUAL TO PRICE ACUTHERM ST THERMA-FUSER. VAV DIFFUSER SCOPE INTENDED ONLY FOR NORTHERN PROJECTS, PREPARE TO PROVIDE BID CREDIT WHERE SCOPE IS REMOVED IN SOUTHERN PROJECTS.
10. TEMPERATURE, CO2, AND RELATIVE HUMIDITY DISPLAY EQUAL TO AUTOMATION COMPONENTS, INC. COORDINATE WITH IOT. SEE CONTROL SEQUENCE.
11. INSTALL WALL MOUNTED FAN COIL UNIT AT AN ELEVATION HEIGHT OF 8'-0" FROM FINISHED FLOOR TO BOTTOM OF UNIT.
12. INSTALL TITUS SB STEEL SECTORIZING BAFFLE IN NECK OF SUPPLY DIFFUSER SUCH THAT IT BLOCKS THE AIRFLOW FROM DIRECTLY BLOWING ONTO THE NIGHT DROP BOX.

8x10 DUCT	31.1 FT
14x12 DUCT	7.3 FT
20x12 DUCT	94.4 FT
24x12 DUCT	13.3 FT
8" DUCT	113.7 FT
8"DIA FLEXIBLE DUCT	50.1 FT
6" DUCT	18.0 FT
6"DIA FLEXIBEL DUCT	6.9 FT
10" DUCT	10.5 FT
10"DIA FLEXIBLE DUCT	4.8 FT
14" DUCT	10.2 FT
14"DIA FLEXIBLE DUCT	3.1 FT
16x12 DUCT	41.4 FT
LSD (2-48")	1.0 EA
LSD (3-48")	1.0 EA
LSD (2-48")CFM: 140	6.0 EA
LSR (3-48")	1.0 EA
LSD (3-48")	1.0 EA
LSD (1-48")	1.0 EA
LSD (1-48")CFM: 90	1.0 EA
LSD (2-24")	2.0 EA
LSD (2-24")	2.0 EA
EF-1	1.0 EA
EF2	1.0 EA
EF3	1.0 EA
24"x24" SUPPLY AIR DIFFUSER	1.0 EA
12"x12" SUPPLY AIR DIFFUSERCFM: 65	2.0 EA
24"x24" SUPPLY AIR DIFFUSER	1.0 EA
24"x24" SUPPLY AIR DIFFUSER	1.0 EA
24"x24" RETURN AIR GRILLENECK SIZE: 12"x12"CFM: 360	1.0 EA
24"x24" SUPPLY AIR DIFFUSER	1.0 EA
24"x24" RETURN AIR GRILLE	2.0 EA
24"x24" RETURN AIR GRILLE	1.0 EA
24"x24" RETURN AIR GRILLENECK SIZE: 8"x8"CFM: 65	1.0 EA
24"x24" SUPPLY AIR DIFFUSER	1.0 EA
24"x24" RETURN AIR GRILLE	1.0 EA
24"x24" RETURN AIR GRILLENECK SIZE: 16"x16"CFM: 1000	1.0 EA
10x10 DUCT	7.4 FT
8x8 DUCT	10.6 FT
12x12 DUCT	9.8 FT
THERMOSTAT CONTROL	4.0 EA
CARBON DIOXIDE (C02) SENSOR	2.0 EA
VOC SENSOR	1.0 EA
PARTICLE COUNTER EQUAL TO SENSIRION AG SP530	1.0 EA
TEMPERATURE & RELATIVE HUMIDITY DISPLAY	1.0 EA
TEMPERATURE SENSOR	4.0 EA
SUPPLY AIR TEMPERATURE SENSOR	2.0 EA
RETURN AIR TEMPERATURE SENSOR	2.0 EA
REMOTE CABLE OPERATED DAMPER	13.0 EA
PETROLEUM BASED WAX CONTROLLED DAMPER	1.0 EA
TITUS SB STEEL SECTORIZING BAFFLE	1.0 EA
PAINT LSD BLACK	4.0 EA
PAINT BLACK LSR	1.0 EA
REFRIGERANT PIPING, SIZE NOT GIVEN	30.9 FT
MANUAL DAMPER	1.0 EA

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

ient:
IFTH THIRD BANK

oject Number: 26032
oject Name:
IFTH THIRD BANK
VATSON
,900 SF

711 WATSON BOULEVARD
ARNER ROBBINS, GA 31093

y Plan:

eet Title:
MECHANICAL
ROPOSED CEILING
LAN

eet Number:
M-301

6/30/2026 4:54:57 PM



1 M-302 ROOF PLAN - MECHANICAL
1/4" = 1'-0"

- HP-1 — 1.0 EA
- RTU-1 — 1.0 EA
- RTU-2 — 1.0 EA
- OUTDOOR AIR TEMPERATURE SENSOR — 2.0 EA
- 1-1/2" RTU CONDENSATE DRAIN W/ P-TRAP & REMOVEABLE VENTED CAP — 1.0 EA
- 24"x22" EXHAUST HOOD, NOA 19-0802.02 EQUAL TO GREENHECK FGR — 1.0 EA

MECHANICAL GENERAL NOTES
(APPLIES TO THIS SHEET ONLY)

1. RTU'S TO BE SCREENED BY NEW BUILDING PARAPET WALL SO THAT ROOF-MOUNTED EQUIPMENT IS OBSCURED FROM VIEW AT GRADE. SEE ARCHITECTURAL DRAWINGS.
2. ALL EXTERIOR-MOUNTED EQUIPMENT AND SUPPORTS SHALL COMPLY WITH APPLICABLE STATE AND LOCAL PRODUCT APPROVAL REQUIREMENTS, INCLUDING FLORIDA PRODUCT APPROVAL OR MIAMI-DADE NOA WHERE REQUIRED.

MECHANICAL KEY NOTES
(APPLIES TO THIS SHEET ONLY)

1. SUPPLY AND RETURN DUCT UP TO RTU ON ROOF. COORDINATE CURB FOOTPRINT WITH STRUCTURAL BEAMS.
2. PROVIDE 1-1/2" RTU CONDENSATE DRAIN WITH P-TRAP AND REMOVABLE VENTED CAP, ROUTE TO PRIMARY ROOF DRAIN.
3. EXHAUST DUCT UP TO EXHAUST FAN ON ROOF. COORDINATE CURB FOOTPRINT WITH STRUCTURAL BEAMS.
4. MAINTAIN 10' CLEARANCE FROM ALL EXHAUST OUTLETS TO FRESH AIR INTAKES.
5. INSTALL ROOFTOP AC UNIT ON 18" WIND-RATED ROOF CURBS. CURBS SHALL BE APPROVED FOR REQUIRED WIND LOADS PER APPLICABLE BUILDING CODE. AIRSOUTH COMMERCIAL UNITS STEEL CURBS (NOA 25-0410.04) OR EQUIVALENT.
6. GRAVITY VENTILATOR SHALL BE APPROVED FOR REQUIRED WIND LOADS PER APPLICABLE BUILDING CODE. EQUAL TO GREENHECK FGR (NOA 23-1122.03) OR LOREN COOK PR-8 FOR STANDARD WIND.
7. INSTALL HP ON WIND-RATED ROOF SUPPORT. SUPPORT SHALL BE APPROVED FOR REQUIRED WIND LOADS PER APPLICABLE BUILDING CODE. EQUIVALENT TO MIAMI-TECH INC. ASMU MECHANICAL UNIT STAND (NOA 24-0117.01).

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
MECHANICAL PROPOSED ROOF PLAN

Sheet Number:
M-302

Category	Item	Responsible
Coordination	GC to coordinate with EC, CBRE & IOT onboarding call to review start-up process and site readiness	GC
Conduit	Wall Boxes - conduit stub-up with pull string/line (for all lighting devices and all HVAC devices) see E and M pages for details	EC
Conduit	Conduit stup up through roof curb for control wire(s) with pull string/line.	EC
Mounting	LCP Panel(s) and override(s).	EC
Power	LCP Panel(s) and override(s).	EC
Mounting	Shades Panel(s) and Override(s)	EC
Power	Shades Panel(s) and Override(s)	EC
Power	BMS control panel(s).	EC
Coordination	GC to coordinate with MC, CBRE & IOT onboarding call to review start-up process and site readiness	GC
Wiring	Thermostat wiring to HVAC system(s). Cable sized to include 2 spare conductors and leave 1 pull wire for BMS network.	MC
Mounting	POL-224 economizer controller to be fully installed and configured with accessories per IOM. Include enthalpy OA & RA sensors	MC
Mounting	Temporary thermostat control for AHU's & RTU's at the space	MC
Wiring	CO2 sensor cabling for RTU DCV control.	MC
Wiring	CO2 sensor cabling for SSAHU Controller.	MC
Start-up & Documentation	Manufacturer specified start-up and report of HVAC systems.	MC
Wiring	Install and configure 24V interface for minisplit based on manufacturer	MC
Start-up & Documentation	Submit copy or picture of start-up report to CI.	MC
Wiring	BMS and BACnet network control system wiring.	CI
Fire, Life Safety	Duct Smoke detector - See note 1.	MC
Fire, Life Safety	Fire alarm shutdown relay/connection to FACP - See note 2.	FAC
Mounting	Relief air damper and actuator.	MC
Mounting	Relief air fan or return air fan.	MC
Mounting	Outside air damper and actuator.	MC
Start-up & Documentation	As-built drawings to ME	MC
Mounting	Replace temporary thermostats with BMS thermostats (return temp to MC).	CI
Start-up & Documentation	BMS network start-up & LCP system commisioning	EC/CI
Start-up & Documentation	BMS controls & HVAC system commissioning	MC/CI
Warranty	HVAC Equipment on-board controls/sensors labor warranty.	MC
Warranty	Controls integration and user interface warranty & tech support.	CI
Warranty	HVAC equipment onboard controls/sensors parts warranty & tech support.	MANUFACTURER

MATRIX NOTES:

1. WHERE A DUCT SMOKE DETECTOR IS SHOWN, THE FOLLOWING ARE THE RESPONSIBILITIES:
   - **A.** WHERE THE BUILDING HAS A FIRE ALARM SYSTEM, THE DUCT SMOKE DETECTOR SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR, INSTALLED BY THE MECHANICAL CONTRACTOR, AND WIRED/CONNECTED BY THE FIRE ALARM CONTRACTOR.
   - **B.** WHERE THE BUILDING DOES NOT HAVE A FIRE ALARM SYSTEM, THE DUCT SMOKE DETECTOR SHALL BE PROVIDED BY THE MECHANICAL CONTRACTOR, INSTALLED BY THE MECHANICAL CONTRACTOR, AND WIRED/CONNECTED BY THE MECHANICAL CONTRACTOR.
2. WHERE A CONTROL MONITOR RELAY IS SHOWN FOR AN HVAC UNIT SHUTDOWN, THE FOLLOWING ARE THE RESPONSIBILITIES:
   - **A.** WHERE THE BUILDING HAS A FIRE ALARM SYSTEM, THE CONTROL MONITOR RELAY SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR, INSTALLED BY THE FIRE ALARM CONTRACTOR, AND WIRED/CONNECTED BY THE FIRE ALARM CONTRACTOR.
   - **B.** WHERE THE BUILDING DOES NOT HAVE A FIRE ALARM SYSTEM, THE CONTROL MONITOR RELAY SHALL BE PROVIDED BY THE MECHANICAL CONTRACTOR, INSTALLED BY THE MECHANICAL CONTRACTOR, INSTALLED BY THE MECHANICAL CONTRACTOR, AND WIRED/CONNECTED BY THE MECHANICAL CONTRACTOR.

IOT BMS NOTE:

IOT SHALL PROVIDE BMS. COORDINATE WITH IOT FOR SUPPORT PRICING. CONTACT JILL MASON AT (512)-649-5142.

MECHANICAL CONTRACTOR TO SCHEDULE ON BOARDING SESSIONS WITH IOT PRIOR TO INSTALL.

1 M-503 IOT MATRIX
NOT TO SCALE

LEGEND:
CI: CONTROLS INSTALLER
EC: ELECTRICAL CONTRACTOR
MC: MECHANICAL CONTRACTOR
ME: MECHANICAL ENGINEER
GC: GENERAL CONTRACTOR
FAC: FIRE ALARM CONTRACTOR
OEM: ORIGINAL EQUIP MANUFACTURER

GENERAL NOTES

1. THE "RESPONSIBLE" COULMN BEARS THE RESPECTIVE CONTRACTOR TO PROVIDE AND INSTALL UNLESS OTHERWISE NOTED.
2. WHERE THERE IS A CONFLICT BETWEEN THE SPECIFICATIONS AND THIS MATRIX, THE MATRIX SHALL TAKE PRECEDENCE.
3. ALL CONDUIT SHALL BE INSTALLED PER NEC AND SPECIFICATIONS. ALL STUB UPS SHALL BE STUBBED UP INTO AN ACCESSIBLE CEILING. THERE SHALL BE NO CONCEALED JUNCTION BOXES

OCCUPIED MODE:
THE WALL MOUNTED PROGRAMMABLE THERMOSTAT SHALL START THE SUPPLY FAN, SUBJECT TO INTERNAL AC UNIT SAFETIES AND SMOKE DETECTOR INTERLOCK (WHERE REQUIRED). THE SPACE TEMPERATURE SENSOR SHALL CYCLE ON THE COMPRESSOR(S) TO MAINTAIN COOLING SETPOINT (74° F - ADJUSTABLE). UPON A DROP IN SPACE TEMPERATURE DURING WINTER MONTHS, THE UNIT SHALL STAGE ON THE COMPRESSOR(S) TO MAINTAIN SPACE TEMPERATURE SETPOINT (70°F - ADJUSTABLE). IF THE HEAT PUMP CANNOT SATISFY SPACE TEMPERATURE SETPOINT, THE ELECTRIC HEAT SHALL STAGE ON. DURING OCCUPIED HOURS, IF THE CO2 LEVELS RISE ABOVE 1200 PPM, THE OSA DAMPER SHALL OPEN. WHEN CO2 LEVELS DROP BELOW 800 PPM, THE OSA DAMPER SHALL CLOSE. WHERE SHOWN, AVERAGING SENSORS SHALL BE INSTALLED TO AVERAGE THE SPACE TEMPERATURE FROM MULTIPLE ZONES.

OCCUPIED HOURS TO BE DETERMINED BY THE OWNER, RECOMMENDED OCCUPIED HOURS ARE MONDAY THRU FRIDAY, 7 A.M. TO 6 P.M.

UNOCCUPIED MODE:
THE SPACE TEMPERATURE SENSOR SHALL CYCLE THE SUPPLY FAN, DX COOLING, DX HEATING, AND ELECTRIC HEAT TO MAINTAIN THE UNOCCUPIED SPACE SETPOINT (60°F HEATING / 80°F COOLING - ADJUSTABLE). THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.

FIELD INSTALL TEMPERATURE SENSORS IN SUPPLY AND RETURN DUCTS OF ALL UNITS. SENSORS SHALL BE CAPABLE OF BEING MONITORED THRU IOT BMS/EMS.

MECHANICAL CONTRACTOR SHALL PROVIDE AND INSTALL A SINGLE TWISTED PAIR FROM THERMOSTAT TO CENTRALLY MOUNTED CONTROL PANEL.

INSTALL PARTICLE COUNTER RETURN DUCT AND VOC SENSOR IN SUPPLY DUCT (RTU-2 ONLY). COORDINATE WITH IOT.

IOT WILL SUPPLY NETWORKABLE THERMOSTAT TO BE INTEGRATED TO THE SYSTEM AND CONTROLS FOR BMS OPERATION AFTER EQUIPMENT START UP.



(T) SPACE TEMPERATURE SENSOR WITH SETPOINT ADJUSTMENT.

(C) SPACE CO2 SENSOR

(S) MONITORING SPACE TEMPERATURE SENSOR (QUANTITY AS SHOWN ON PLANS)

(SAT) FIELD INSTALLED DUCT MOUNTED SUPPLY AIR TEMPERATURE SENSOR TIED TO RTU SYSTEM AND MONITORED THRU IOT CONTROLS

(RAT) FIELD INSTALLED DUCT MOUNTED RETURN AIR TEMPERATURE SENSOR TIED TO RTU SYSTEM AND MONITORED THRU IOT CONTROLS

2 M-503 RTU SEQUENCE AND CONTROL POINTS DETAIL
NOT TO SCALE

THE AC UNIT CONTROLLER SHALL CYCLE ON COMPRESSOR(S) TO MAINTAIN COOLING SETPOINT (74°F - ADJUSTABLE) AND HEATING SETPOINT (70°F - ADJUSTABLE).

CONTRACTOR TO PROVIDE OEM CONVENTIONAL THERMOSTAT ADAPTER WITH UNIT, PLEASE PROVIDE MITSUBISHI PAC-US445CN-1 AT PROJECT START. THE ADAPTER SHALL BE COMPATIBLE BY EITHER USING A BACNET CARD OR ALLOW INTEGRATION WITH A CONVENTIONAL THERMOSTAT.

IOT WILL SUPPLY NETWORKABLE THERMOSTAT TO BE INTEGRATED TO THE SYSTEM AND ADD CONTROLS FOR BMS OPERATION AFTER EQUIPMENT STARTUP.



3 M-503 FCU/HP SEQUENCE AND CONTROL POINTS DETAIL
NOT TO SCALE

MC TO ENGAGE A RESPRESENTATIVE FROM CARRIER (OR ALTERNATIVE MANUFACTURER) FOR START UP PRODECURES AND COORDINATION WITH IOT FOR QC PROCESS.

WORKFLOW:

1. MC TO PERFORM FULL START-UP AND CONFIGURATION OF UNIT TO FULFILL FACTORY AND JOB SCOPE REQUIREMENTS.
2. MC TO SCHEDULE AN ONBOARDING CALL WITH IOT PRIOR TO THE SITE VISIT (IOT IS OPEN FROM 8:00 AM TO 5:00 PM (CST)
   - A. PRIOR TO THE ONBOARDING CALL THE MC NEEDS TO READ THE DIGIMEP USER GUIDE
     - a IT COVERS HOW TO USE THE APP (PG. 1-17)
       - BEST PRACTICES AND EXPECTATIONS
     - b. MEASUREMENTS TO TAKE (PG. 18)
     - c. TOOLS REQUIRED (PG. 19-20)
     - d. APP TROUBLESHOOTING (PG. 21-22)
   - B. WE WILL ALSO NEED THE FOLLOWING INFORMATION FOR THE TECHNICIAN PERFORMING THE SITE VISIT TO MAKE SURE HE/SHE HAS THE CREDENTIALS NEEDED TO LOGIN TO THE APP
     - a. FIRST AND LAST NAME
     - b. EMAIL
     - c. PHONE NUMBER
     - d. MAKE AND MODEL
3. MC TO OPEN THE DIGIMEP APP AND FOLLOW THE STEP-BY-STEP CX AND STARTUP VERIFICATION PROCESS AND SUBMIT REPORT.
4. MC AND DESIGNATED STAKEHOLDERS WILL RECEIVE A REPORT SECONDS AFTER SUBMISSION
   - A. MC WILL NEED TO REVIEW AND ADDRESS ANY DEFICIENCIES FOUND IN PERFORMANCE AND QC READINGS AND CALLOUTS.
   - B. AFTER CORRECTION OF ANY DEFICIENCIES, MC WILL OPEN THE SUBMITTED FORM, TAKE NEW READINGS TO VALIDATE UNIT IS IN PASS STATUS.
     - a. MC TO CALL IOT TO REVIEW AND VALIDATE FORM AT 512-649-5142 EXT. 7
     - b. A COMMISSIONING TECH WILL REVIEW THE FORM WITH YOU TO MAKE SURE YOU ARE GOOD TO GO.

NOTE: ALL OF THESE READINGS AND ASSET DATA, PERFORMANCE DATA AND PICTURES WILL CONFIRM QUALITY OF INSTALL AND WILL BE A PERMANENT ASSET RECORD THAT WILL VALIDATE SCOPE AND THAT THE RESULTANT PERFORMANCE IS ACCEPTED.

4 M-503 ONBOARDING START-UP REVIEW MEETING
NTS

IOT BMS NOTE:

IOT SHALL PROVIDE BMS. COORDINATE WITH IOT FOR SUPPORT PRICING. CONTACT GERRIANNE FAULHABER.

EMAIL: GERRIANNE@IOFTEAM.COM
PHONE: (224)213-6908

MECHANICAL CONTRACTOR TO SCHEDULE ON BOARDING SESSIONS WITH IOT PRIOR TO INSTALL.

STARTUP MEETING NOTE:

GC TO COORDINATE AN ON BOARDING EMAIL WITH THE EC, MC, CBRE PM. THE GC NEEDS TO ATTEND THE MEETING.

LOW VOLTAGE NOTE:

MC TO REVIEW IOM MANUAL FOR LOW VOLTAGE ROUTING. LOW VOLTAGE ROUTING TO BE RUN PER IOM AND NOT ON SAME CONDUIT AS HIGH VOLTAGE.

THERMOSTAT MOUNTING NOTES:

1. ALL THERMOSTATS SHALL BE INSTALLED AT 44" AFF UNLESS NOTED OTHERWISE.
2. MAINTAIN 16" FROM ADJACENT EXTERIOR WALLS. WHERE INSTALLATION IS REQUIRED ON EXTERIOR WALL, PROVIDE INSULATED MOUNTING PAD FOR BASE PLATE.
3. DISTANCE FROM CORNERS AND IF OTHER SENSORS NEARBY TO BE SIDE BY SIDE.
4. DISTANCE FROM WALL CORNERS TO BE 6" MINIMUM.
5. REFRAIN FROM INSTALLING THERMOSTAT NEAR ANY HEATING OR COOLING SOURCES; SUCH AS EQUIPMENT, WINDOWS, OR UNDER SUPPLY DIFFUSERS.
6. ENSURE THERMOSTAT IS INSTALLED IN CORRECT ORIENTATION AND ACCORDING TO ALL MANUFACTURER INSTALLATION INSTRUCTIONS.
7. COORDINATE FINAL LOCATION WITH IN FIELD CONDITIONS, MAINTAIN CLEARANCE FROM NEARBY SWITCHES AND OTHER DEVICES AS NEEDED.
8. IF OTHER SENSORS ARE LOCATED NEARBY INSTALL SIDE BY SIDE.
9. J-BOXES ARE TO BE USED ON ALL MONITORING SENSORS, THERMOSTATS AND CO2 SENSORS.



5 M-503 WALL THERMOSTAT MOUNTING DETAIL
NTS

- DISCONNECT SWITCH — 2.0 EA
- 3-POLE DISCONNECT SWITCH — 1.0 EA
- WIRED REMOTE CONTROLLER — 1.0 EA

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scalers as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON
1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
MECHANICAL CONTROLS DETAILS

Sheet Number:
M-503

2/5/2026 12:55:05 PM



1 PLUMBING PROPOSED FOUNDATION PLAN
P-301 1/4" = 1'-0"

3"DIA STORM PIPE	33.5 FT
4"DIA STORM PIPE	12.7 FT
1-1/4"DIA CW	2.0 FT
4"DIA SANITARY PIPE	21.9 FT
3"DIA SANITARY PIPE	86.7 FT
1"DIA NATURAL GAS PIPE	18.6 FT
1-1/2"DIA SANITARY PIPE	3.6 FT
FL	3.0 EA

MECHANICAL GENERAL NOTES
(APPLIES TO THIS SHEET ONLY)

1. LOCATIONS OF UTILITIES SHOWN ON PLANS ARE APPROXIMATE, VERIFY WITH LOCAL UTILITY PRIOR TO BIDDING.
2. CONTRACTOR SHALL VERIFY EXACT LOCATION, SIZE AND ELEVATION OF ALL EXISTING SERVICES PRIOR TO INSTALLING ANY NEW PIPE.
3. ALL OUTSIDE CLEANOUTS SHALL BE BROUGHT TO GRADE AND EMBEDDED\ IN 18"X18"X6" THICK CONCRETE PAD. (J.R. SMITH 4258 OR EQUAL.)
4. WHEREVER DISSIMILAR METALS ARE CONNECTED ON WATER LINES, A DIELECTRIC UNION SHALL BE USED.
5. ALL HORIZONTAL WATER AND VENT PIPING SHALL BE RUN ABOVE CEILING ON PLAN WHICH SHOWN UNLESS OTHERWISE NOTED.
6. ALL HORIZONTAL SANITARY PIPING IS RUN BELOW FLOOR ON PLAN WHERE SHOWN UNLESS OTHERWISE NOTED.
7. ALL WATER PIPING BELOW SLAB ON GRADE SHALL BE BENT UP AT ENDS SO THAT NO JOINTS OCCUR BELOW FLOOR.
8. COORDINATE ALL PIPE ROUTING TO AVOID CONFLICTS WITH STRUCTURAL, MECHANICAL, AND ELECTRICAL FEATURES OF BUILDING.
9. ALL WALL HYDRANTS AND HOSE BIBBS SHALL BE MOUNTED 24" ABOVE FINISH GRADE OR FINISH FLOOR UNLESS OTHERWISE NOTED.
10. ALL WATER PIPING INSTALLED IN EXTERIOR WALLS SHALL BE LOCATED ON THE INTERIOR SIDE OF THE EXTERIOR WALL INSULATION.
11. NO VENT THRU ROOF IS TO BE LOCATED WITHIN 10 FEET OF ANY BUILDING AIR INTAKES, PER CODE. COORDINATE WITH MECHANICAL AND GENERAL CONTRACTORS.
12. DOMESTIC WATER PIPING AND FIRE PROTECTION PIPING LOCATED ABOVE THE CEILING, SHALL BE INSTALLED BELOW CEILING INSULATION.
13. CONTRACTOR SHALL COORDINATE MECHANICAL FLOOR DRAIN LOCATIONS WITH MECHANICAL EQUIPMENT PRIOR TO INSTALLATION.
14. CONTRACTOR SHALL PROVIDE SHOCK ARRESTORS ON ALL BRANCH LINES.
15. CONTRACTOR SHALL COORDINATE ALL SINKS WITH CASEWORK PRIOR TO ORDERING SINKS.
16. ALL HOT WATER LINES TO BE INSULATED.

MECHANICAL KEY NOTES
(APPLIES TO THIS SHEET ONLY)

1. TERMINATE EMERGENCY DOWNSPOUT 12" ABOVE FINISH CURB. COORDINATE WITH ARCHITECT.
2. FOR CONTINUATION SEE CIVIL SITE UTILITY PLAN.
3. ALL UNDERGROUND SANITARY LINES ARE TO BE NO LESS THAN 3" IN SIZE.
4. VERTICAL STORM RISER TO DROP UNDERGROUND AND ROUTE OUT BUILDING AS INDICATED.
5. PIPE SHALL BE INSTALLED WITH A HORIZONTAL INTERCEPTING TRAP UNDERNEATH EXTERNAL WALL. CLEANOUT TO BE LEFT AS AN AIR INLET.
6. REFER TO CIVIL DRAWINGS FOR PROPOSED EXTERIOR CLEANOUT LOCATION, COORDINATE TO AVOID SIDEWALK PATH OR TRANSFORMER PAD.
7. PLUMBING CONTRACTOR TO ENSURE THAT A "DOUBLE COMBO WYE" FITTING IS USED AT THE LOW FLOW WATER CLOSET CONNECTION TO SANITARY MAIN IN AN EFFORT TO IMPROVE WASTE FLOW.

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK
WATSON
1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
PLUMBING
SANITARY
FOUNDATION PLAN

Sheet Number:
P-301



CD	7.0 EA
1"DIA HW	162.2 FT
3/4"DIA CW	39.8 FT
4"DIA VENT PIPE	47.3 FT
3"DIA VENT PIPE	12.8 FT
2"DIA VENT PIPE	58.2 FT
SHUT-OFF VALVE	2.0 EA
1-1/4"DIA CW	62.5 FT
4"DIA STORM PIPE	103.7 FT
3"DIA STORM PIPE	25.8 FT
1"DIA CW	45.5 FT
HB	2.0 EA
VB	1.0 EA
SK-U	1.0 EA
CP	1.0 EA
MS	1.0 EA
EWH	1.0 EA
WC	2.0 EA
LAV	2.0 EA
SK-T	1.0 EA
EDF	1.0 EA
1/2"DIA CW PIPE TYPE K COPPER	15.3 FT
DW	1.0 EA
STANDARD FILTER SIMILAR TO "WHIRLPOOL L...	1.0 EA
18"x18"x6"THK. CONCRETE PAD FOR CLEAN O...	1.0 EA
DSN	2.0 EA

1 PLUMBING
P-302 1/4" = 1'-0"

FLOOR PLAN

MECHANICAL GENERAL NOTES
(APPLIES TO THIS SHEET ONLY)

1. LOCATIONS OF UTILITIES SHOWN ON PLANS ARE APPROXIMATE, VERIFY WITH LOCAL UTILITY PRIOR TO BIDDING.
2. CONTRACTOR SHALL VERIFY EXACT LOCATION, SIZE AND ELEVATION OF ALL EXISTING SERVICES PRIOR TO INSTALLING ANY NEW PIPE.
3. ALL OUTSIDE CLEANOUTS SHALL BE BROUGHT TO GRADE AND EMBEDDED\ IN 18"X18"X6" THICK CONCRETE PAD. (J.R. SMITH 4258 OR EQUAL.)
4. WHEREVER DISSIMILAR METALS ARE CONNECTED ON WATER LINES, A DIELECTRIC UNION SHALL BE USED.
5. ALL HORIZONTAL WATER AND VENT PIPING SHALL BE RUN ABOVE CEILING ON PLAN WHICH SHOWN UNLESS OTHERWISE NOTED.
6. ALL HORIZONTAL SANITARY PIPING IS RUN BELOW FLOOR ON PLAN WHERE SHOWN UNLESS OTHERWISE NOTED.
7. ALL WATER PIPING BELOW SLAB ON GRADE SHALL BE BENT UP AT ENDS SO THAT NO JOINTS OCCUR BELOW FLOOR.
8. COORDINATE ALL PIPE ROUTING TO AVOID CONFLICTS WITH STRUCTURAL, MECHANICAL, AND ELECTRICAL FEATURES OF BUILDING.
9. ALL WALL HYDRANTS AND HOSE BIBBS SHALL BE MOUNTED 24" ABOVE FINISH GRADE OR FINISH FLOOR UNLESS OTHERWISE NOTED.
10. ALL WATER PIPING INSTALLED IN EXTERIOR WALLS SHALL BE LOCATED ON THE INTERIOR SIDE OF THE EXTERIOR WALL INSULATION.
11. NO VENT THRU ROOF IS TO BE LOCATED WITHIN 10 FEET OF ANY BUILDING AIR INTAKES, PER CODE. COORDINATE WITH MECHANICAL AND GENERAL CONTRACTORS.
12. DOMESTIC WATER PIPING AND FIRE PROTECTION PIPING LOCATED ABOVE THE CEILING, SHALL BE INSTALLED BELOW CEILING INSULATION.
13. CONTRACTOR SHALL COORDINATE MECHANICAL FLOOR DRAIN LOCATIONS WITH MECHANICAL EQUIPMENT PRIOR TO INSTALLATION.
14. CONTRACTOR SHALL PROVIDE SHOCK ARRESTORS ON ALL BRANCH LINES.
15. CONTRACTOR SHALL COORDINATE ALL SINKS WITH CASEWORK PRIOR TO ORDERING SINKS.

MECHANICAL KEY NOTES
(APPLIES TO THIS SHEET ONLY)

1. VENT PIPING IS TO RUN PARALLEL OVER SANITARY PIPING AND TIE INTO 3" VENT THROUGH ROOF.
2. DOMESTIC CW PIPING TO ROOF HYDRANT. FIXTURE REQUIRES 1/8" DRAIN LINE TO BE TIED INTO SANITARY.
3. SHUTOFF VALVES TO BE INSTALLED ON INPUT AND OUTPUT OF WATER HEATER IN A READILY ACCESSIBLE AND VISIBLE LOCATION, WITHIN 4'-0" TO 5'-0" AFF, UNOBSTRUCTED BY EQUIPMENT OR FINISH MATERIALS. A CIRCULATION PUMP AND EXPANSION TANK ARE TO BE INCLUDED WITH WATER HEATER INSTALLATION.
4. 1/2" SOFT COPPER BELOW SLAB TO PRIME FLOOR DRAIN. (TYPICAL)
5. INSTALL AT VERTICAL RISER HORIZONTAL PIPE SECTION FOR INSTALLATION OF A WHOLE BUILDING SEDIMENT FILTER ON THE INCOMING MAIN DOMESTIC WATER SUPPLY LINE. INSTALL A STANDARD FILTER SIMILAR TO "WHIRLPOOL LARGE CAPACITY 10" X 4.5" WHOLE HOUSE WATER FILTER SYSTEM WHKF-DWHBB" OR EQUIVALENT PRODUCT. PLUMBING CONTRACTOR TO INSTALL 10-MICROM FILTER FOR SYSTEM AND PROVIDE CLIENT WITH REPLACEMENT CARTIRIAGE.
6. TAP OFF THE INCOMING WATER SERVICE FROM THE SINK TO A WALL VALVE BOX, RUN A 1/4" FLEXIBLE COPPER OR PCV LINE TO THE FILTERS LOCATED IN THE QUENCH MACHEINE, FROM THERE RUN ANOTHER LINE TO THE KEURIG.

PRAXIS3

100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
PLUMBING DOMESTIC FLOOR PLAN

Sheet Number:
P-302



1 PLUMBING STORM ROOF PLAN
P-303 1/4" = 1'-0"

3/4"DIA GAS PIPE	44.2 FT
1"DIA GAS PIPE	9.7 FT
3/4"DIA CW	4.7 FT
4"DIA STORM PIPE	56.3 FT
3"DIA STORM PIPE	91.2 FT
1-1/2"DIA CONDENSATE DRAIN PIPE, DIA ASSUMED	34.5 FT
OD	2.0 EA
RD	2.0 EA
MANUAL SHUT-OFF VALVE	2.0 EA
RH-1	1.0 EA
SAFETY YELLOW PAINT AT ROOD GAS PIPE	53.9 FT

MECHANICAL GENERAL NOTES
(APPLIES TO THIS SHEET ONLY)

1. LOCATIONS OF UTILITIES SHOWN ON PLANS ARE APPROXIMATE, VERIFY WITH LOCAL UTILITY PRIOR TO BIDDING.
2. CONTRACTOR SHALL VERIFY EXACT LOCATION, SIZE AND ELEVATION OF ALL EXISTING SERVICES PRIOR TO INSTALLING ANY NEW PIPE.
3. ALL OUTSIDE CLEANOUTS SHALL BE BROUGHT TO GRADE AND EMBEDDED\ IN 18"X18"X6" THICK CONCRETE PAD. (J.R. SMITH 4258 OR EQUAL.)
4. WHEREVER DISSIMILAR METALS ARE CONNECTED ON WATER LINES, A DIELECTRIC UNION SHALL BE USED.
5. ALL HORIZONTAL WATER AND VENT PIPING SHALL BE RUN ABOVE CEILING ON PLAN WHICH SHOWN UNLESS OTHERWISE NOTED.
6. ALL HORIZONTAL SANITARY PIPING IS RUN BELOW FLOOR ON PLAN WHERE SHOWN UNLESS OTHERWISE NOTED.
7. ALL WATER PIPING BELOW SLAB ON GRADE SHALL BE BENT UP AT ENDS SO THAT NO JOINTS OCCUR BELOW FLOOR.
8. COORDINATE ALL PIPE ROUTING TO AVOID CONFLICTS WITH STRUCTURAL, MECHANICAL, AND ELECTRICAL FEATURES OF BUILDING.
9. ALL WALL HYDRANTS AND HOSE BIBBS SHALL BE MOUNTED 24" ABOVE FINISH GRADE OR FINISH FLOOR UNLESS OTHERWISE NOTED.
10. ALL WATER PIPING INSTALLED IN EXTERIOR WALLS SHALL BE LOCATED ON THE INTERIOR SIDE OF THE EXTERIOR WALL INSULATION.
11. NO VENT THRU ROOF IS TO BE LOCATED WITHIN 10 FEET OF ANY BUILDING AIR INTAKES, PER CODE. COORDINATE WITH MECHANICAL AND GENERAL CONTRACTORS.
12. DOMESTIC WATER PIPING AND FIRE PROTECTION PIPING LOCATED ABOVE THE CEILING, SHALL BE INSTALLED BELOW CEILING INSULATION.
13. CONTRACTOR SHALL COORDINATE MECHANICAL FLOOR DRAIN LOCATIONS WITH MECHANICAL EQUIPMENT PRIOR TO INSTALLATION.
14. CONTRACTOR SHALL PROVIDE SHOCK ARRESTORS ON ALL BRANCH LINES.
15. CONTRACTOR SHALL COORDINATE ALL SINKS WITH CASEWORK PRIOR TO ORDERING SINKS.
16. ALL HOT WATER LINES TO BE INSULATED.

MECHANICAL KEY NOTES
(APPLIES TO THIS SHEET ONLY)

1. ENSURE OVERFLOW STORM DRAIN IS INSTALLED AT AN ELEVATION OF 2" HIGHER THAN THE PRIMARY STORM DRAIN.
2. 2 CANOPY STORM DRAINAGE CONNECTION WITH CIVIL. CANOPY STORM DRAINAGE SLOPE IS 1/8".
3. PENETRATE ROOF WITH NATURAL GAS PIPING AT EACH RTU. INSTALL A MANUAL SHUTOFF VALVE, DRIP LEG (SEDIMENT TRAP), TEST PORTS UPSTREAM AND DOWNSTREAM OF PRESSURE REGULATOR, LINE PRESSURE REGULATOR (SIZED AND ADJUSTED PER RTU REQUIREMENTS), UNION, AND FLEXIBLE GAS CONNECTOR REDUCED TO RTU INLET SIZE. SUPPORT ALL PIPING PER CODE. REFER TO GAS PIPING DETAIL.

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
PLUMBING PROPOSED ROOF PLAN

Sheet Number:
P-303



1 P-402 DOMESTIC WATER RISER



2 P-402 SAN/VENT RISER

4:55:15 PM

FCO 1.0 EA
NON FREEZE GROUND HYDRANT 1.0 EA

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
PLUMBING ISOMETRIC RISER DIAGRAM

Sheet Number:
P-402



PIPE PAINTING NOTE:

EXTERIOR ROOF-LEVEL NATURAL GAS PIPING SHALL BE PAINTED SAFETY YELLOW. EXTERIOR GAS PIPING BELOW ROOF LEVEL SHALL BE PAINTED TO MATCH ADJACENT SURFACES. INTERIOR GAS PIPING ABOVE CEILINGS SHALL REMAIN UNPAINTED.

INSTALLATION ROUTING NOTE:

NATURAL GAS PIPING UP TO HIGHER ELEVATION ROUTED ABOVE CEILING AND BELOW ROOF.

1 P-403 PLUMBING NATURAL GAS ISO PLAN





GAS PIPING INSTALLATION NOTES:

1. INSTALL MANUAL GAS SHUTOFF VALVE AT EACH RTU, ACCESSIBLE AND NEAR THE UNIT.
2. PROVIDE DRIP LEG (SEDIMENT TRAP) AFTER SHUTOFF VALVE AND BEFORE REGULATOR.
3. PROVIDE TWO TEST PORTS:
   - 3.1. UPSTREAM OF REGULATOR (LINE PRESSURE)
   - 3.2. DOWNSTREAM OF REGULATOR (MANIFOLD PRESSURE)
   - 3.3. USE 1/8" NPT PLUGS OR OTHER APPROVED FITTINGS.
4. INSTALL GAS PRESSURE REGULATOR (E.G. MAXITROL 325-5L OR EQUAL):
   - 4.1. 2 PSI INLET PRESSURE
   - 4.2. 4.5"–14" W.C. OUTLET PRESSURE (MC TO CONFIRM RTU REQUIREMENTS)
   - 4.3. OUTDOOR RATED AND INSTALLED UPRIGHT
   - 4.4. VENT OUTLET TO BE SCREENED OR PIPED PER IFGC 410.3
5. SET REGULATOR OUTLET PRESSURE PER RTU MANUFACTURER SPECIFICATIONS.
6. SUPPORT AND SLOPE GAS PIPING PER CODE; INCLUDE UNION BEFORE RTU CONNECTION.

PIPE PAINTING NOTE:

EXTERIOR ROOF-LEVEL NATURAL GAS PIPING SHALL BE PAINTED SAFETY YELLOW. EXTERIOR GAS PIPING BELOW ROOF LEVEL SHALL BE PAINTED TO MATCH ADJACENT SURFACES. INTERIOR GAS PIPING ABOVE CEILINGS SHALL REMAIN UNPAINTED.

INSTALLATION ROUTING NOTE:

NATURAL GAS PIPE UP TO HIGHER ELEVATION ROUTED ABOVE CEILING AND BELOW ROOF.

NATURAL GAS PIPING CALCULATIONS AND NOTES:

1. NATURAL GAS PIPING SHALL BE SCHEDULED 40 BLACK STEEL COMPLYING WITH ANSI B35.10. FITTINGS SHALL BE STEEL OR MALLEABLE IRON. JOINTS SHALL BE THREADED OR WELDED.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING AND COORDINATING WITH THE LOCAL UTILITY COMPANIES (GAS, WATER, SEWER, ELECTRICAL, TELEPHONE) TO ENSURE TIMELY INSTALLATION OF UTILITY SERVICES TO THE POINTS SHOWN ON THE PLANS.
3. REFER TO THE ARCHITECTURAL PLANS FOR LOCATIONS OF ALL FIXTURES AND EQUIPMENT. PROVIDE ALL FINAL CONNECTIONS PER KITCHEN CONSULTANT SCHEDULES.
4. ALL GAS PIPING IN SCOPE (NEW AND EXISTING) SHALL BE PRESSURE TESTED PRIOR TO BUILDING OCCUPANCY.
5. EXISTING GAS PIPING SIZE VERIFIED USING TABLE 402.4(5) OF THE INTERNATIONAL FUEL GAS CODE USING THE LONGEST LENGTH METHOD 402.4.1 USING THE FOLLOWING INFORMATION:
   - INLET PRESSURE OF 2.0 PSI
   - PRESSURE DROP OF 1.0 IN. W.C. FOR SCHEDULE 40 METALLIC PIPE
   - MAXIMUM DEVELOPED LENGTH OF 100 FT.

NATURAL GAS METER BY GAS COMPANY 1.0 EA

PRAXIS3
100 Peachtree St NW
Suite 1450
Atlanta, GA 30303
404-875-4500 tel
www.praxis3.com

GEORGIA REGISTERED No. 032221 PROFESSIONAL ENGINEER GARRY M. JENKINS

Copyright (c) 2024 Praxis3, LLC

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Praxis3 shall retain all common law, statutory and other reserved rights, including copyright thereto.

This drawing may not be reproduced in whole or in part without written permission of Praxis3. It is to be returned upon request. Scales as stated are valid on the original drawings.

Rev	Date	Comments
	07/02/2026	PERMIT SET

Client:
FIFTH THIRD BANK

Project Number: 26032
Project Name:
FIFTH THIRD BANK WATSON 1,900 SF

2711 WATSON BOULEVARD
WARNER ROBBINS, GA 31093

Key Plan:

Sheet Title:
PLUMBING NATURAL GAS ISO PLAN

Sheet Number:
P-403

2026 4:55:14 PM